



Do not scale drawing, work to figured dimensions. All dimensions to be checked on site. Any errors or discrepancies to be reported to MILLIMETRE DESIGN. This drawing may not be edited or modified without permission. This drawing is to be read in colour and in conjunction with all relevant consultant and specialist drawings, schedules and documentation. Only built from drawings issued as Construction.

- REMOVAL OF 1no. SET OF DOUBLE DOORS, OPE TO BE MADE GOOD IN PREPARATION FOR NEW DOOR TO BE INSTALLED. CONTRACTOR TO ENSURE LEVEL THRESHOLD IS ACHIEVED.
- REMOVAL OF 1no. SHUTTER AND HOUSING MECHANISM AS INDICATED, ALLOW FOR BLOCKWORK INFILL TO EXISTING OPE IN PREPARATION FOR INSTALLATION OF NEW DOUBLE DOOR. CONTRACTOR TO ENSURE LEVEL THRESHOLD IS ACHIEVED.

- STRIP OUT ALL SHOP FRONT FITTINGS (WALL MOUNTED DISPLAYS AND CENTRAL FLOOR SHELVEING) UPON REMOVAL OF MERCHANDISE BY CLIENT.
- COMPLETE STRIP OUT OF OFFICE INCLUDING REMOVAL OF EXISTING CEILING, INCLUDING BOTH PLASTERBOARD BULKHEADS & TILED SECTIONS AND ALL ASSOCIATED HANGING SYSTEM & INTEGRATED LIGHT FITTINGS.
- REMOVAL OF BOXING OUT TO COLUMNS INTERNALLY WITHIN THE SPACE.
- REFER TO STRUCTURAL ENG'S DRAWINGS FOR FULL EXTENT OF PROPOSED WORKS TO EXISTING GROUND FLOOR SLABS.
- REMOVAL OF PLASTER FINISH TO PERIMETER WALLS (BACK TO STRUCTURE) TO REVIEW EXTENT OF RISING DAMP (IF ANY).
- EXISTING CHIMNEY BREAST TO BE EXPOSED & INSPECTED FOR ANY POSSIBLE DEFECTS.
- REMOVAL OF EXISTING SHOP FRONT, GLAZING, SIGNAGE , COLUMN ENCASEMENTS & SHUTTERS TO MAIN FACADE, OPE TO BE MADE GOOD IN PREPARATION FOR NEW FACADE. DEMOLITION TO BE COORDINATED WITH INTERIOR FITOUT WORKS.
- DEMOLITION OF STAIRS AND PARTITION WALLS, ALL TO STRUCTURAL ENG'S SPEC & DETAILS.
- REMOVAL OF 1no. SHUTTER & 1no. EXTERNAL DOOR AS INDICATED TO REAR OF SPACE. ALLOW FOR BLOCKWORK INFILL TO EXISTING SHUTTER OPE IN PREPARATION FOR INSTALLATION OF NEW SINGLE DOOR. CONTRACTOR TO ENSURE LEVEL THRESHOLD IS ACHIEVED.
- DEMOLITION OF INTERNAL STRUCTURAL WALLS AS INDICATED, REFER TO STRUCTURAL ENG'S DETAILS.

- ALLOWANCE FOR SELF LEVELLING SCREED TO ALL AREAS AS PART OF WORK TO ENSURE LEVEL ACCESS AND THRESHOLDS BETWEEN BUILDINGS, ALL TO STRUCTURAL ENG'S DETAILS.
- FINAL LEVELS AND CEILING HEIGHTS TO BE CONFIRMED UPON COMPLETION OF WORKS.
- ALLOWANCE FOR INTEGRATION OF FLOOR BOXES INTO SLAB, FINAL QUANTITIES & LOCATIONS TBC

SCOPE OF WORKS_ GROUND FLOOR_ PHASE 2

- DEMOLITION OF EXISTING STAIRS, INCLUDING REMOVAL OF HANDRAIL & ANY STRUCTURAL SUPPORT WALLS, ALL TO STRUCTURAL ENG's DETAILS.
- REMOVAL OF EXISTING INTERNAL & EXTERNAL DOORS AS INDICATED. EXTERNAL JAMBS TO BE MADE GOOD IN PREPARATION FOR NEW DOORS BEING INSTALLED.
- EXISTING WINDOW GRILLE / VENT TO BE REMOVED AND STRUCTURAL OPE TO FORMED FOR DOUBLE DOOR INSTALLATION. CONFIRMATION REQUIRED FOR EXTENT OF TRENCHES REQUIRED INTO PROPOSED SWITCHROOM (AWAITING FINAL CONFIRMATION FROM EBS ON EXACT REQUIREMENTS)

 AREA OUTSIDE SCOPE OF WORKS

 EXTENT OF DEMOLITION WORKS

CONTRACTORS COMPOUND FOR
DURATION OF WORKS TO BE LOCATED
WITHIN FOOTPRINT OF BUILDING, FINAL
POSITION TO BE CONFIRMED BASED
ON PHASING OF DEMOLITION WORKS

CONTRACTOR TO REVIEW LEVELS OF EXISTING SLABS THROUGHOUT UPON DEMOLITION OF DOOR OPES etc. EXTENT OF SCREED REQUIRED TO EXISTING SLAB IN ORDER TO ACHIEVE LEVEL THRESHOLDS BETWEEN BUILDINGS TO BE CONFIRMED BY STRUCTURAL ENG. FINAL ON SITE FF TO BE CONFIRMED

TO BE READ IN
CONJUNCTION WITH
STRUCTURAL ENG'S DRAWINGS

To be read in conjunction with all relevant drawings & schedules, refer to drawing register for breakdown of drawings.

Drawing to be printed in colour.

SCOPE OF WORKS GROUND FLOOR PHASE 2

- REMOVAL OF 2no. SET EXTERNAL DOUBLE DOORS @ GL5.
- OPE TO BE FORMED IN EXTERNAL WALL TO ALLOW FOR INSTALLATION OF NEW SINGLE DOOR @ GL5.
- DEMOLITION OF EXISTING STAIR CORE & BLOCKWORK WALLS, ALL WORKS CARRIED OUT AS PER STRUCTURAL ENG'S DETAILS.
- DEMOLITION OF COLUMNS TO BE CARRIED OUT IN CONJUNCTION WITH STRUCTURAL ENG's DETAILS.
- PARTIAL DEMOLITION OF EXISTING SLAB AS INDICATED TO ALLOW FOR INSTALLATION OF NEW STAIRS & LIFT SHAFT. ALL TO STRUCTURAL ENG's DETAILS.
- OPES TO BE FORMED IN EXISTING WALLS AS INDICATED TO NEIGHBOURING SPACE, ALL TO STRUCTURAL ENG's DETAILS.
- EXISTING WALL MOUNTED SPRINKLER SYSTEM & PIPEWORK @ GL H & J TO BE RETAINED & PROTECTED FOR DURATION OF WORKS. FULL EXTENT TO BE RETAINED TO BE CONFIRMED ON SITE.

[illegible]

E	29.04.26	SMC	UPDATED FOR TENDER
D	13.03.26	SMC	ISSUED FOR TENDER
C	09.02.26	SMC	UPDATED AS PER CLIENTS COMMENTS
B	06.02.26	SMC	ISSUED FOR TENDER
A	28.01.26	SMC	MINOR UPDATE TO SCOPE
#	21.01.26	SMC	FIRST ISSUE
REV	DATE	APP BY	DESCRIPTION



4 Ongar Square, Ongar Village, Dublin 15. D15 H34C

This drawing is the property of Millimetre Design Ltd & must not be reproduced without prior consent.

CLIENT	Carrolls Irish Gifts Immersive Experience
--------	--

PROJECT ADDRESS Talbot Street, North City,
Dublin 1, D01 X652

DWG TITLE	GROUND FLOOR PLAN DEMOLITION WORKS
-----------	---------------------------------------

EDITION **TENDER**

DWG NO	CIX-TD-11.00
--------	--------------

REV	PROJECT NO	SCALE
F	CIX	1:100

DATE	MAR 2000	DRN	CMC	APP
------	----------	-----	-----	-----

DATE	MAR 2026	DRN	SMC	APP
------	----------	-----	-----	-----