

(09) Preliminaries and Insurances PRELIMINARY PARTICULARS PROJECT, PARTIES AND CONSULTANTS Project A Carrolls Irish Gifts Enabling Works Talbot Street Name and General Description General demolition and refurbishment works required to existing buildings on Talbot Street Location Taslbot Street Dublin 1 Employer Carrolls Irish Gifts Architect Millimetre Design, 4 Ongar Square, Ongar Village, Dublin 15, D15 H34C (Contact William Hanley Tel: 01 8263971) Quantity Surveyors and Project Managers John F Dillon & Associates Ltd, Chartered Quantity Surveyors, Dowland House, 1 Old Street, Malahide, Co Dublin. Structural Engineer B J.A. Gorman Consulting Engineers Ltd Unit 1, Block B, Forest Park, Mullingar, Co. Westmeath. Services Engineer AxisEng Architect and Clerk of Works The term "The Architect" in the Schedule of Works and specification shall include the same persons as are included in that expression in the Articles of Agreement.				
Carrolls Talbot Street BQ/1				To Collection €

(09) Preliminaries and Insurances (Cont) (Cont) PRELIMINARY PARTICULARS (Cont) PROJECT, PARTIES AND CONSULTANTS (Cont) Architect and Clerk of Works Where a Clerk of Works is appointed he will act solely as Inspector under the Architect, and the Contractor shall afford him every facility for examining the work and materials. The Clerk of Works has no power to order or allow any work entailing either additions or omissions in the Contract. The Employer may appoint a Clerk of Works who will be paid by him, but neither his appointment nor his actions shall in any way affect the responsibility of the Contractor, and such Clerks of Works will have no power to authorise variations of any kind. DESCRIPTION OF SITE Boundaries A The boundaries of the site shall be the internal and external areas of the buildings as illustrated on the Architects Drawings. The contractor shall confine his operations within the boundaries of the site except where necessary to carry out works on the contract which extend beyond the boundary of the site. Temporary buildings, stores and all other things and activities pertaining to the carrying out of the works will be subject to the Architects approval. the Contractor is to provide adequate hoarding to all boundaries including gates, dust screens, temporary walls etc to prevent any interference with access. The Contractor is to make good to all areas disturbed on completion including removal of temporary hoardings, reinstating grounds, etc.				
	item	1		
Carrolls Talbot Street BQ/2				To Collection €

(09) Preliminaries and Insurances (Cont) (Cont) PRELIMINARY PARTICULARS (Cont) DESCRIPTION OF SITE				
Access				
A	Access to the site is from either the front or rear entrances of existing buildings as shown. The Contractor is required to ensure that as little disruption as possible is caused to members of the public and to the customers and employees of the existing businesses adjacent which will remain operational for the duration of the contract.	item	1	
Visiting the Site				
B	The Contractor is advised to visit the site and ascertain the facilities of access thereto, the supply of labour, and materials the district will afford and the general convenience of working. He will be taken to have made himself acquainted with the nature, character, dimensions, levels and other features of the site, all existing buildings thereon and all other things in so far as they may have any connection with or affect the Works. He must take all the above matters into account when tendering and no charge for any extra labour or materials will be allowed in consequence of the Contractors failure to do this.	item	1	
C	Arrangements to visit the site by ringing the Project Manager Mrs Sinead Black 086 127 2312	item	1	
D	The contractor will be confined to the areas to be developed under the contract. Any damage caused to the areas which are not to be developed shall be put right at the contractors own expense.	item	1	
E	No use of existing carparks, footpaths or roads will be allowed for parking ;storage of materials; plant; temporary buildings; existing footpaths and roads are to be kept unrestricted at all times.	item	1	
F	Provide all necessary watching and lighting for the protection and security of the works from the public	item	1	
Carrolls Talbot Street			To Collection €	
BQ/3				

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) PRELIMINARY PARTICULARS</u>				
<u>(Cont) DESCRIPTION OF SITE</u>				
<u>(Cont) Visiting the Site</u>				
A	The location of existing services must be ascertained by the Contractor. Any queries relating to services should be addressed to the Architect, Any damage to existing services shall be made good with costs borne by the contractor.	item	1	
<u>Existing Buildings</u>				
B	The Contractor should note the proximity of existing buildings; some of which will be in use for the duration of the contract; the contractor should allow for any additional costs associated for restrictions/difficulties as a consequence of working alongside same - it should be noted adjoining buildings are busy hotels, shops and restaurants producing enterprise and will remain operational for the duration of the works	item	1	
<u>Protection of Existing Buildings and Adjoining Properties</u>				
C	The Contractor shall provide everything that may be necessary for the protection and safety of the existing properties while carrying out the works; this is particularly relevant given the phased nature of the works	item	1	
D	The Contractor shall be held solely responsible for the safety of the adjoining properties and the safety of all temporary work and after removal the making good of disturbed areas.	item	1	
<u>Convenience of Others</u>				
E	The Contractor shall consult the convenience of anybody who may be affected by the work, with regard to the approaches to be used, suitable times for making deliveries and all other matters affecting them.	item	1	

(09) Preliminaries and Insurances (Cont) (Cont) PRELIMINARY PARTICULARS DRAWINGS AND OTHER DOCUMENTS Drawings Drawings which were used in the preparation of this Schedule of Works are as follows:- A See Drawing Issue Sheet B One copy of all drawings and other documents relating to the Contract will be supplied to the Contractor. They will remain the property of the Employer and, together with any copies made by the Contractor, shall be returned to the Architect on completion of the Works. Contract Documents shall be kept on the site in the charge of the foreman and shall be available for the Architects use when required Further Drawings and Instructions C The Architect shall have full power and authority to supply to the Contractors from time to time during the progress of the works any further drawings and instructions as shall be necessary for the purpose of the proper and adequate execution and maintenance of the Works and the Contractor shall be bound by the same as if they had been listed herein. Specifications D The works shall be carried out and completed all in accordance with the specifications of the Architect, Civil and Structural Engineers and the Services Engineers, issued as part of the tender documentation. Any queries in relation to the specifications shall be addressed to the Architect/Engineer/Services Engineer.				
	item	1		
	item	1		
	item	1		
	item	1		
Carrolls Talbot Street BQ/5 To Collection €				

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) PRELIMINARY PARTICULARS</u>				
<u>(Cont) DRAWINGS AND OTHER DOCUMENTS</u>				
<u>Exhibition/Issue of Document</u>				
A	The Articles of Agreement, contract drawings and specification are exhibited at the Quantity Surveyor's office during normal business hours.	item	1	
<u>Schedule of Works</u>				
B	The Schedule of Works is not measured strictly in accordance with the Agreed Rules of Measurement. It is prepared to divide the works into elements suitable for pricing purposes. Tendering contractors should include for all items shown on the tender drawings and included in the tender documents generally. Provisional Quantities included in the schedule of Works will be adjusted in the final account based on the actual quantities for such items as measured on site.	item	1	
<u>CONTRACT</u>				
<u>FORM, TYPE AND CONDITIONS OF CONTRACT</u>				
C	The Articles of Agreement and Conditions of Contract shall be those issued by the Royal Institute of the Architects of Ireland in agreement with the Construction Industry Federation and The Royal Institute of Chartered Surveyors, 2012 Edition (With Addendum to Agreement, Edition 1, 2014) where quantities do not form part of the Contract. Nothing in the specification nor the Schedule of Works shall override, modify or affect in any way whatsoever, the application or interpretation of that which is contained in the conditions of contract.	Item	1	
D	The Contractor will be deemed to have examined these Conditions and to have priced the items in accordance therewith.	Item	1	
Carrolls Talbot Street			To Collection €	
BQ/6				

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) FORM, TYPE AND CONDITIONS OF CONTRACT</u>				
<u>Schedule of Clause Headings</u>				
A schedule of the clause headings of the Conditions is set out hereunder for pricing:-				
		1		
A	1. Definitions (see hereinafter)	Item	1	
B	2. Scope of Contract	Item	1	
C	3. Drawings and Bills of Quantities	Item	1	
D	4. Variations arising from Legislative Enactments	Item	1	
E	5. Contractor to provide everything necessary	Item	1	
F	6. Local and Other Authorities' Notices and Fees (see hereinafter)	Item	1	
G	7. Setting out of Works	Item	1	
H	8. Materials and Workmanship to Conform to Description (See hereinafter)	Item	1	
J	9. Work to be opened up	Item	1	
K	10. Foreman (See hereinafter)	Item	1	
L	11. Access for Architect to works	Item	1	
M	12. Clerk of Works	Item	1	
N	13. Ascertainment of Prices for Variations	Item	1	
P	14. Omissions	Item	1	
Q	15. Assignment or Sub-Letting	Item	1	
R	16. Nominated Sub-Contractors	Item	1	
S	17. Nominated Suppliers	Item	1	
T	18. Provisional Sums	Item	1	
U	19. Prime Cost Sums	Item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) FORM, TYPE AND CONDITIONS OF CONTRACT</u>				
<u>(Cont) Schedule of Clause Headings</u>				
A	20. Independent Contractors, Artists and tradesmen	Item	1	
B	21A. Liability and Indemnity for Damage to Persons and Property	Item	1	
C	21B. Insurance against Damage to Persons and Property	Item	1	
D	22. All Risks Insurance	Item	1	
E	23. Insurance Policies	Item	1	
F	24. Damage due to Excluded Risks	Item	1	
G	25. Damage due to Design	Item	1	
H	26. Responsibility for Existing Structures	Item	1	
J	27. War Damage	Item	1	
K	28. Dates for Possession and Completion (See hereinafter)	Item	1	
L	29. Damages for Non-Completion (See hereinafter)	Item	1	
M	30. Delay and Extension of Time	Item	1	
N	31. Practical Completion and Defects Liability Period (See hereinafter)	Item	1	
P	32A. Partial or Phased Possession	Item	1	
Q	32B. Damage due to Use, Occupation, or Possession by the Employer	Item	1	
R	33. Determination of Contract by Employer	Item	1	
S	34. Determination of Contract by Contractor	Item	1	
T	35. Certificates and Payments	Item	1	
U	36. Wage and Price Variations (See hereinafter)	Item	1	
V	37. Collateral Agreements	Item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) FORM, TYPE AND CONDITIONS OF CONTRACT</u>				
<u>(Cont) Schedule of Clause Headings</u>				
A	38. Disputes Resolution	Item	1	
<u>Appendix to Conditions of Contract</u>				
Particulars to be inserted in the Appendix to the Conditions of Contract shall be as follows:-				
B	Designated Date: Clause 1(a):....not applicable, fixed price contract	Item	1	
C	Percentage for professional fees (if not stated 12.5%)	Item	1	
D	Cost of Site Clearance.....subject to separate tender to determine cost once scope of works was established	Item	1	
E	Minimum Sum for Employer's Liability Insurance (if not stated €13,000,000) Clause 23:....€13,000,000	Item	1	
F	Minimum Sum for Public Liability Insurance (if not stated €3,000,000) Clause 23(e) (ii):....€6,000,000	Item	1	
G	Date for Possession: Clause 28:to be agreed	Item	1	
H	Date for Completion: Clauses 28 & 29(a):to form part of tender competition (see "Order of Work" later in this element)	Item	1	
J	Liquidated and Ascertained Damages: Clause 29(a):....The amount of Liquidated and Ascertained Damages payable by the Contractor pursuant Clause 29 shall be enforceable expense, loss, claim, damage or other liability incurred or suffered by Employer resulting from the Contractors failure to complete the Works on or before the date of Completion	Item	1	
K	Defects Liability Period: Clauses 31 & 35(i):.... 12 months	Item	1	
L	Guarantee Account: Not applicable	Item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) FORM, TYPE AND CONDITIONS OF CONTRACT</u>				
<u>(Cont) Appendix to Conditions of Contract</u>				
A	Period of Interim Certificates (if not stated four weeks): Clause 35(b):....monthly	Item	1	
B	Time for issue of Interim Certificates by the Architect (if not stated 5 working days): Clause 35(b):.... 5 working days	Item	1	
C	Percentage of Certified Value Retained (not to exceed 10%): Clause 35(e):...5%	Item	1	
D	Limit of Retention Fund (not to exceed 5%): Clause 35(e)	Item	1	
E	Joint Account Retention Fund: Clause 35(f):....not applicable	Item	1	
F	Period of Final Measurement (if not stated, 6 months): Clause 35(h)(iii):....6 months	Item	1	
G	Period for Serving Notice of Arbitration (if not stated 14 days): Clause 35(i):....14 Days	Item	1	
AMENDMENTS TO THE CONDITIONS OF CONTRACT				
<u>Clause 3</u>				
H	Delete Clause 3 (a) (i)	item	1	
<u>Clause 21</u>				
J	Delete Clause 21 (B) (ii)	item	1	
<u>Clause 22</u>				
K	Delete Clause 22 (B) (ii)	item	1	
<u>Clause 30</u>				
L	Delete Clause 30 (h).	item	1	
<u>Clause 35</u>				
M	Delete Clause 35 (a) (i).	item	1	
N	Delete Clause 35 (g).	item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) AMENDMENTS TO THE CONDITIONS OF CONTRACT Clause 36 A Delete entirely. Clause 37 B After the words 'Nominated Sub-Contractor' add the words 'and suppliers'. Bond Requirements The Contract Gaurantee Bond shall satisfy the following conditions: The cost of the bond is to be inserted into the Form of Tender 1. That the Bond shall be in favour of the Employer 2. That the amount of the Bond be for 12.50 per cent of the estimated value of the works at the date of signing the Contract. 3. That the Bond incorporates a Clause permitting variations under the terms of the Contract without reference to the Bonding Company. This will not affect the amount stated in the Bond. 4. That the notification period of the Bonding Company of any non-performance or non-observance on the part of the Contractor which may involve a loss for which the Bonding Company would become liable should be at least three months after the date of discovery of such non-performance or non-observance. 5. That the expiry date of the bond and the period in which suits at law or proceedings in equity may be brought against the Bonding Company to recover a claim under the Bond should be a minimum of fifteen months after the date of the issue of the Certificate of Practical Completion.				
	Item	1		
	item	1		
				EXCL
				EXCL
				EXCL
				EXCL
				EXCL
				EXCL

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
CONTRACTORS LIABILITY				
<u>Insurances Generally</u>				
A	See the relevant clauses of the Form of Contract for the pricing of the various insurance requirements.	Item	1	
<u>Particular Insurance Requirements</u>				
B	Employers Liability insurance for a minimum limit of indemnity of €13,000,000	Item	1	
C	Public liability insurance for a limit of indemnity of €6,000,000 each and every claim.	Item	1	
D	The Contractor shall secure prior to commencement and maintain for the duration of the Contract or up to Practical Completion as the case may be, all of the insurances to be provided by virtue of his obligation under the Conditions of Contract and to values not less than those designated.	Item	1	
E	The Contractor shall submit evidence to the Employer in accordance with the provisions of the Conditions of Contract that the required Insurances are in effect prior to commencement of the works.	Item	1	
F	Before commencement on site the Contractor will be required to arrange that his Insurance Brokers will liase with the clients Insurance brokers to ensure that all aspects of the related insurances in respect of the buildings have been accommodated.	Item	1	
<u>Collateral Agreements</u>				
G	Collateral Agreements in the forms issued to Nominated Sub-Contractors and Suppliers may be executed between the Employer and the Sub-Contractors and Suppliers. The Terms of these Conditions are deemed to be amended and supplemented in all respects necessary to give effect to the terms of such Collateral Agreements.	Item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) CONTRACTORS LIABILITY</u>				
<u>(Cont) Collateral Agreements</u>				
A	The Contractor shall make it a condition of any sub-contract with a nominated sub-contractor or supplier or specialist sub-contractor that such sub-contractor or supplier shall, if required by the Employer to do so, execute a Collateral Agreement with the Employer.	Item	1	
B	The Employer may by virtue of the said Collateral Agreement, require a nominated subcontractor or nominated supplier to execute a Guarantee Bond on the Collateral Agreement the Contractor shall be deemed to have made provision in the Contract Sum for any Bond he may require in respect of the relevant subcontract.	Item	1	
C	The Contractor is to note that the Collateral Agreements may be subject to change in the future pending final agreement with the Client.	Item	1	
D	The Contractor should also note that it may be a requirement of this contract that a Collateral Agreement be signed between the Main Contractor and the Employer, Finance House and Management Company.	Item	1	
TENDERING AND PRICING				
<u>Exhibition/Issue if Documents</u>				
E	The Articles of Agreement, Contract Drawings and Specification are exhibited at the Quantity Surveyor's Office during normal working hours	item	1	
<u>Remuneration</u>				
F	No Tenderer will be remunerated for any trouble or expense incurred in the preparation of his tender	item	1	
<u>Acceptance of Lowest Tender</u>				
G	The lowest or any tender will not necessarily be accepted	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) TENDERING AND PRICING</u>				
<u>Opening of Schedule of Works</u>				
A	The Employer reserves the right to open all or any Schedules of Works.	item	1	
<u>Price in Detail</u>				
B	The Schedule of Works, fully priced, must be submitted at the time of tendering. Schedule of Works must be completed and signed by an Authorised Person in ink or electronically with the tenderers signature page signed on ink	item	1	
C	Contractors should note that only Schedules of Works completed in accordance with the tender instructions will be accepted.	item	1	
D	On examination of the priced Schedule of Works any errors discovered will be dealt with in accordance with the "Code of Procedure for Single Stage Selective Tendering" as published by the Liaison Committee of the Construction Industry Federation, the Society of Chartered Surveyors and the Royal Institute of Architects in Ireland.	item	1	
<u>V.A.T.</u>				
E	The Tender Sum shall be inclusive of Value Added Tax which shall be regarded as a provisional sum. In the tender it will be calculated at 13.5% of the tender before tax. In the Final Account it shall be calculated at such rate(s), applied to the final account before tax, as may be properly decided by the Revenue Commissioners under the powers vested in them by the Value Added tax Act,1972, but shall exclude any over payments made or penalties incurred under the Act.	item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) TENDERING AND PRICING Tax Clearance				
A	The Successful Contractor will be responsible for ensuring that any sub-contractor employed is in possession of a bona fide C2 Certificate or a Tax Clearance Certificate and to submit such certificate in each case for inspection by the authorised nominee of Fingal County Council. No claims for increased costs will be entertained in respect of the contractor's compliance with this condition.	item	1	
B	Payments under this Contract will at all times be conditional on compliance with these conditions.In the absence of a Current C2 Certificate tax must be deducted at a rate of 35% from payments due in accordance with Section 17 of the Finance Act, 1970, notwithstanding that a Tax Clearance Certificate has been furnished by the Contractor	item	1	
C	It is a condition precedent to the award of this contract that a firm must produce promptly a C2 Certificate or a Tax Clearance Certificate. A statement from the Revenue will be required in the case of Non-Residents	item	1	
Pension and Sick Pay Scheme				
D	The Contractor shall be a contributor for the duration of the contract, to a Contributory Pension and Sick Pay Scheme approved by the Revenue Commissioners in respect of all Employees and must comply with all relevant labour agreements.	item	1	
Carrolls Talbot Street				To Collection €
BQ/15				

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) TENDERING AND PRICING</u>				
<u>Special Note</u>				
A	The prices to be affixed to items for works throughout this Schedule of Works shall include for all import duty, custom, excise, import licence or other charges, where such are subject thereto, at the date of lodgement of tender, or at any other "designated date", with the sole exception of the addition for V.A.T. The addition for V.A.T. is made as a single figure at the end of the Schedule of Works. In the case of P.C. Items, the sum includes for import duty, customs or other charges with the exception of V.A.T.	Item	1	
B	When submitting detailed progress statements as required under Clause 35 (a) of the Standard Conditions and when submitting details for settlement of the Final Account, the Contractor shall show separately the value of any items, including any such included in sub-contractors accounts, upon which Value Added Tax is chargeable at a rate different from that applicable to building contracts.	Item	1	
C	In the case of fittings as defined by the Revenue Commissioners such values shall be the cost of supply and delivery only. When claiming payment from the Employer on foot of any interim or final certificate which includes the value of items chargeable at a rate different from that applicable to Building Contracts the Contractor shall raise a seperate invoice covering each different rate of VAT applicable.	Item	1	
D	The Revenue Commissioners have stated that failure to raise invoices in this way will render the total Final Account liable to VAT at the highest rate involved. The Employer will not be liable to pay the Contractor for any excess tax becoming payable as a result of failure to comply with this provision which is in accordance with the Regulations of the Revenue Commissioners.	Item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) TENDERING AND PRICING General Notes				
A	(a) All provisional amounts herein, whether in money or quantities, shall be at the entire disposal of the Architect who may add to or deduct from same or make any alterations as he may think fit, any difference to be adjusted at the settlement of accounts.	Item	1	
LOCAL AUTHORITIES FEES AND CHARGES Notices and Fees				
B	The Contractor shall give all notices and pay all fees required to be given or paid by Regulation or Bye-Law of any Local or other Statutory Authority in relation to the execution of the works and by the rules and regulations of all public bodies whose property or rights are affected or may be affected in any way by the works or any temporary works. The Contractor shall conform in all respects with the provision of any general or local Act of Parliament and the Regulations or Bye-Laws of any local or other Statutory Authority which may be applicable to the works or to any temporary works and with such rules and regulations or public bodies and companies as aforesaid and shall keep the Employer indemnified against all penalties and liabilities of every kind for any breach of such Acts, Regulations or Bye Law	item	1	
C	Provide for all fees, charges demandable by the Local Authorities.	item	1	
Customs Duties				
D	The Contractor will be deemed to have included in his tender for all Customs and other duties legally payable at the date of tender	item	1	
Carrolls Talbot Street			To Collection €	
BQ/17				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT OBLIGATIONS AND RESTRICTIONS IMPOSED BY THE EMPLOYER Access to Site for Inspections A The Architect and any person authorised by him shall at all times have access to the works, the site, and all workshops and places where work is being prepared or from whence materials, manufactured articles and machinery are being obtained for the works and the Contractor shall afford every facility for and every assistance in or in obtaining the right to such access. Consultants B All consultants appointed from time to time by the Employer will be able to visit the site and to supervise all or any of the works. The Contractor shall observe their instructions and directions with regard to same and shall collaborate with them fully and to any extent that may be required, provided always that the Architects directions with regard to all or any of the works shall be final and binding. Inspection of Building Local Authority Officers C Should a recognised and responsible officer of a Local Authority desire to see the premises, buildings, drawings, Schedule of Works Specification, the Contractor shall refer him to the Employer. Annoyance to Occupants of Adjoining Property D The Contractor is to allow for executing any work which, in the Architect's opinion, is likely to cause annoyance or inconvenience to occupants of adjoining properties at such times during normal working hours as the Architect may direct.				
	item	1		
	item	1		
	item	1		
	item	1		
Carrolls Talbot Street BQ/18 To Collection €				

(09) Preliminaries and Insurances (Cont)

(Cont) CONTRACT

(Cont) OBLIGATIONS AND RESTRICTIONS
IMPOSED BY THE EMPLOYER

Site Security

A The Contractor should note that the cost of any site security required for the duration of the works will be borne by the contractor. It should be particularly noted that 24 hour security may be needed by static guard to protect and secure the site and all materials. (See also "Protection, watching and lighting later in this element)

Item

1

Dismissal of Men

B The Architect may require the Contractor to dismiss any person employed on the work whom he deems incompetent, or to have misconducted himself.

Item

1

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) OBLIGATIONS AND RESTRICTIONS IMPOSED BY THE EMPLOYER Protection of Persons and Property				
A	The Contractor shall provide for the efficient protection of the public, the Employer's officers, servants and property and all other persons occupying or using the premises, also of adjoining or neighbouring property during the progress of the works included in or required to be done in connection with the Contract. The Contractor shall take all precautions to eliminate the danger to the public and other persons arising from the entry and exit of vehicles to and from the site. The Contractor shall provide general purpose industrial safety helmets complying with B.S. 5240, high visibility vests and any other protective clothing he deems required for the use of all Employer's officers and servants visiting the site in connection with the works. The Contractor shall be responsible for ensuring that all plant is placed and used and all operations carried out in such a manner as to prevent injury to persons or loss or damage to property in the event of any accident occurring. Where acetylene, oxygen, propane or other gas cylinders are used on the site, the Contractor shall provide and maintain a minimum 200 mm x 200 mm international red diamond hazard warning sign displaying the flame motif and the words "FLAMMABLE GAS". Such notice shall be securely fixed externally and prominently where gas cylinders are stored. Convenience of Others	item	1	
B	The Contractor shall consult the Employer regarding the convenience of anybody who may be affected by the work with regard to approaches to be used; suitable for making deliveries and all other matters affecting them.	item	1	
Carrolls Talbot Street BQ/20				To Collection €

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) OBLIGATIONS AND RESTRICTIONS IMPOSED BY THE EMPLOYER Limitation of Working Space				
A	The Contractor shall confine his activities to the work included in the Contract and shall not allow his men to trespass onto adjacent property unless in direct execution of work included in this Contract. In the event of any claims arising due to failure to comply with this clause, the Contractor shall be held entirely responsible and shall pay all costs in connection therewith. It should be noted that the site will be an active live golf course and clubhouse Storage space for materials shall be confined to areas as indicated by the Architect. No materials site huts, etc, shall be placed in a position which is likely to interfere with the progress of the works or interfere with the daily activities of the Golf Club	item	1	
B	Provide a temporary escape exit from the existing building including temporary stairs, ramps, hoardings, signs, protective barriers, lighting etc; at any times the existing escape routes are blocked by the works	item	1	
Carrolls Talbot Street BQ/21 To Collection €				

(09) Preliminaries and Insurances (Cont)

(Cont) CONTRACT

(Cont) OBLIGATIONS AND RESTRICTIONS
IMPOSED BY THE EMPLOYER

Limitation of Working Hours

- A Subject to any provision to the contrary contained in the Contract none of the permanent work shall be carried on during the night without the permission in writing of the Architect save when the work is unavoidable or absolutely necessary for the saving of life or property or for the safety of the works in which case the Contractor shall immediately advise the Architect. If there is any occasion on which work must be carried on outside daytime hours as described in the next item the Environmental Health Officer, local residents and businesses in the areas which are likely to be affected by noise from the proposed works should be notified in advance e.g. in letter or leaflet or advertisement form of a) name, address and telephone number of the company carrying out the works b) nature and reason for the works c) likely duration and times of the work
- B Working hours shall be restricted to between the hours of 8.00am to 7.00pm Monday to Friday and 8.00 am to 2pm on Saturday. No activities shall take place on site on Sundays or Bank Holidays. No activities which would reasonably expected to cause annoyance to residents in the vicinity shall take place between the hours of 7pm and 8am. No deliveries of materials, plant or machinery shall take place before 8am or after 7pm. Operations involving excessive noise such as hammering, jack hammers, rock breakers, con saws, etc. are to be carried out during times as agreed with the Architect.
- C No overtime shall be executed unless specifically directed by the Architect, in writing.
- D Claims for non productive overtime will be entertained only when authorised in writing by the Architect

item

1

item

1

item

1

item

1

Carrolls
Talbot Street BQ/23 To Collection €

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) OBLIGATIONS AND RESTRICTIONS IMPOSED BY THE EMPLOYER (Cont) Historical Finds				
A	The find is not to be disturbed until his written instructions are given as to the disposal of such articles.	item	1	
Temporary Hoardings and Gantries				
B	Provide and maintain all necessary temporary fencing hoardings, fans, planked footways, guard rails, gantries and the like for the proper excecution of the works, for the protection of the public and for meeting the requirements of and Local or other Authority and to comply with Health and Safety Requirements, and later shift and adapt from time to time as necessary. Pay all Local Authority charges and fees in connection with hoardings or the like. The contractors attention is particularly drawn to the location of the works and the fact that all works will be carried out directly adjacent a live environment and is deemed to have included for any items required to protect the safety of its patrons	item	1	
Publicity				
C	The Contractor shall not take photographs, write articles for publication or cause to be issued or displayed any advertisement about the Works, any product therein or any other subject nor permit such acts by others, unless expressly authorised in writing by the Employer	item	1	
Notice Board				
D	Any site notice board or sign proposed by the contractor shall be submitted to the Architect for approval. The proposed structure for same may require approval by the Architect. The cost of Compliance with this approval and total cost of site notice board shall be borne by the Contractor	item	1	
Carrolls Talbot Street BQ/24				To Collection €

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) OBLIGATIONS AND RESTRICTIONS IMPOSED BY THE EMPLOYER</u>				
<u>(Cont) Notice Board</u>				
A	Allow for erecting 5 no. consultants signs; size 1200 x 300 to the Architect's design; and incorporating same in the contractors board as necessary; signs to be supplied by consultants.	item	1	
<u>Existing Services</u>				
B	Provide for arranging the removal and re-routing of any overhead telephone, cable T.V. and electrical cables or the like crossing or entering the site.	item	1	
C	Protect, uphold and maintain all existing services on, under, or over the site (unless expressly told otherwise in the Service Engineers tender documentation of this project) whether the property of local authority, public undertaking or other public and private utility provider or private owners including all pipes, ducts, walls, underground or overhead cables, etc. encountered during the execution of the works. The Contractor is to make good any damage due to any cause within his control at his own expense or pay any costs and charges in connection therewith to the satisfaction of the Employers, Architects, Statutory Authorities or Private Owners.	item	1	
D	The Contractor shall make all necessary arrangements for the proper execution of these works, some of which may be located outside the site boundaries, and shall take such matters into consideration in pricing out the works. No claim for extra payment shall be allowed on the grounds of want of knowledge, adequate preparation and execution of these works in this respect.	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) OBLIGATIONS AND RESTRICTIONS</u>				
<u>IMPOSED BY THE EMPLOYER</u>				
<u>Protection of Existing</u>				
A	The Contractor shall provide all requisite shoring, needling, underpinning, shuttering and other supports to walls, floors, roofs, etc, that may be necessary for the protection and safety of existing and adjoining buildings, boundary walls, fences, etc other than those scheduled for demolition. The Contractor shall alter, adapt and maintain all such temporary works as necessary and finally clear away and make good. The Contractor shall be held solely responsible for the safety of such existing buildings and sufficiency of all temporary works.	item	1	
<u>Eircom Machinery</u>				
B	The Contractor will be held responsible for any damage caused through his want of proper care to any of the fittings, equipment or machinery installed by Eircom Engineers or their agents, other such fittings, equipment or machinery already in the building or in other buildings or already existing on the site or on adjoining sites.	item	1	
<u>Order of Works</u>				
C	On being given possession of the site the Contractor will commence and proceed with the execution of the works in an order as agreed with the Employers and the Architect	item	1	
D	Any changes in sequence required by the contractor from those submitted prior to commencement are to be notified to the deisgn team at least 10 days in advance of those changes to allow an opportunity for the nursing home to attempt to accomodate if possible	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) OBLIGATIONS AND RESTRICTIONS</u>				
<u>IMPOSED BY THE EMPLOYER</u>				
<u>(Cont) Order of Works</u>				
Provide for preparing a detailed time and progress chart and cash flow projection for the whole of the works, including all works to be carried out by Nominated Sub-contractors. The Programme and Cash Flow Projection must be submitted within ten working days of the Architect's instruction to so submit. The Contractor shall, prior to the submission of the programme, contact all relevant Nominated Sub-contractors who are to provide the Contractor with a detailed programme and cash flow for their portion of the works which is to be incorporated into the Contractor's Programme and Cash Flow Projection. The requirement to produce the detailed Programme and Cash Flow is a condition precedent to the letting of the contract. The detailed Programme and Cash Flow will be reviewed by the Architect.	item	1		
The Programme submitted must be a detailed programme containing amongst other items information (including the works to be carried out by Nominated Sub-contractors) as labour force resources, material delivery schedules, material ordering schedules, information flow requirements etc. Include for all costs for altering and updating the programme and cash flow on a monthly basis.	item	1		
The Cash Flow Projection submitted must be a detailed projection based on the approved programme. Include for all costs for monitoring, altering and up-dating the cash flow projection on a monthly basis.	item	1		

(09) Preliminaries and Insurances (Cont)

(Cont) CONTRACT

(Cont) OBLIGATIONS AND RESTRICTIONS
IMPOSED BY THE EMPLOYER

Consultants Site Office

A Provide and maintain a suitable temporary office for site meetings and to accommodate Consultants during visits to the site, approximately 17 square metres in area. The Contractor shall also provide adequate heating appliances, artificial lighting, fuel, cleaning and attendance as required for the above, together with all necessary lock-up cupboards, drawing benches, chairs, tables, etc., as may be required. Allow for re-locating as necessary during course of the contract and removing from site on completion.

item 1

B Provide for computer and printer from commencement and pay all charges, remove and make good on completion.

item 1

Safety, Health and Welfare Legislation

C It should be particularly noted that the building will remain live for the duration of the works; all fire escapes and all means of fire egress and exit are to be maintained at all times for the duration of the works; existing life safety equipment such as the existing fire alarm and nurse call systems are to remain active for the duration fo the works and the contractor is to include here for any reporgramming or amendment works required to those systems to facilitate this requirement

item 1

D Detailed method statements and risk assesments are to be submitted to Millimetre Design for approval prior to commencement of the works

item 1

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) OBLIGATIONS AND RESTRICTIONS IMPOSED BY THE EMPLOYER</u>				
<u>(Cont) Safety, Health and Welfare Legislation</u>				
A	The Contractor shall comply in all respects with the Safety, Health and Welfare at Work Act current at the date of tender, and with any relevant Statutory Instruments or Regulations issued thereafter. In particular the Contractor will comply in all respects with the Safety, Health and Welfare at Work (Construction) Regulations.	item	1	
B	The Contractor shall comply in all respects with the Factory and Safety in Industry Acts and any other Acts amending those Acts and with any Statutory Instrument or Regulations issued thereunder.	item	1	
C	Provide for complying with the provisions of the Building (Safety, Health and Welfare) Regulations under Factories Act.	item	1	
D	Safety Statements in accordance with the provisions of the Safety, Health and Welfare at Work Act (and any amendments thereto) will be provided by the contractor and all sub-contractors.	item	1	
E	The Contractor shall include for a competent person to act as, and carry out the duties of, Project Supervisor for the duration of the Construction Phase as set out in the Safety, Health and Welfare at Work (Construction) Regulation.	item	1	
F	The Contractor shall include for the Project Supervisor for the Construction Stage developing, before the commencement of the construction work, the safety and health plan for the construction site already prepared on a preliminary basis.	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) OBLIGATIONS AND RESTRICTIONS</u>				
<u>IMPOSED BY THE EMPLOYER</u>				
<u>(Cont) Safety, Health and Welfare</u>				
<u>Legislation</u>				
A	The Contractor shall include for the Project Supervisor for the Construction Stage giving notice to the Health and Safety Authority prior to the commencement of the work on site in accordance with the First Schedule of the Safety, Health and Welfare at Work (Construction) Regulations.	item	1	
B	The Contractor / PSCS shall include for the preparation of a Preliminary Safety File for handover to the PSDP on completion of the contract, as per the Preliminary Safety and Health Plan	item	1	
C	Provide for:(i) The operation of the requirements of the SAFE PASS and CONSTRUCTION SKILLS CERTIFICATE SCHEMES.(ii) Safety Officers and all safety supervisors, first aiders, inspectors and certifiers required.(iii) Tests and certificates on plant and equipment.(iv) Safety signs and signals.(v) Provision of Personal Protective Clothing and Personal Protective Equipment.(vi) Provision and maintenance of Emergency routes and exits and designated personnel responsible for emergency procedures.(vii) Energy distribution installations (viii) Temporary Fire detection and fire fighting systems.(ix) Maintenance of appropriate working conditions and work stations. (x) Provision and maintenance of on site traffic routes. (xi) Provision of first aid equipment and first aid room as appropriate. (xii) Welfare facilities for workpeople to comply with the relevant sections of the Safety, Health and Welfare at Work (Construction) Regulations.	item	1	
D	The Contractor shall complete and return with his tender the official Health & Safety Pre Qualification Form for the roles of PSCS and Contractor	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) OBLIGATIONS AND RESTRICTIONS IMPOSED BY THE EMPLOYER</u>				
<u>(Cont) Safety, Health and Welfare Legislation</u>				
A	The Contractor shall enter into a collateral agreement with the Employer for the Contractor's appointment as Project Supervisor for the Construction Stage. Provide for any costs arising thereunder not provided for elsewhere herein	item	1	
B	Provide for all costs as necessary for obtaining all additional information as may be required from the Health and Safety Authority	item	1	
C	The Contractor shall procure that insurance cover required to be obtained and maintained by the Contractor pursuant to the Provisions of Clause 21and 23 of the Main Contract shall provide indemnity in respect of any claim for bodily injury or property damage which the Contractor may incur by reason of the preformance of the functions and duties of the Project Supervisor for the Construction Stage for the Project.This provision is without prejudice to the Client's assertion that he had no liability under the Regulations or at all from the moment he appoints the Project Supervisor for the Construction Phase	item	1	
<u>Building Regulations and Licences and Consents</u>				
D	The Contractor shall carry out the works in accordance with the provisions of the current Building Regulations and any amendment thereto which shall relate to the works. The Contractor shall inform the Architect of any specific requirement of the drawings or specification which he considers to be in contravention of the Building Regulations and the Architect/Engineer shall take account of the Contractors submission and issue instructions accordingly as he shall see fit.	Item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR				
<u>Contractors Compound</u>				
A	The Contractor's compound is to be located in a location to be agreed internally within the work area no external area will be made available for the purpose of the works; locaton to be agreed with the employer; provide for setting up compound and removing compound on completion of the works and reinstating site to satisfaction of the Architect	item	1	
<u>Work to be carried out under licence</u>				
B	Provide for all costs associated with working under licence outside the site area as defined in the project particulars.The Contractor shall provide all necessary watching, lighting, hoarding etc. as is necessary for the protection of the public and for the protection of the works under licence against trespass and interference. No work is to be carried out, outside the site area as defined, except with the written permission of the Architect	item	1	
<u>Work by Others Engaged Directly by the Employer</u>				
C	The Contractor is to facilitate the works of all firms or authorities to be employed on the site during the currency of the works, with particular reference to the ESB, Bord Gais, Eircom or other telecom company, cable television company.	item	1	
<u>General</u>				
D	The existing roadways shall be kept clear of construction traffic and operatives private vehicles at all times.	item	1	
E	Parking of contractor's vehicles or Contractor's employee's vehicles will not be permitted in the existing car park currently in use for patrons of the golf club, its employees and visitors	item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Proprietary Items				
A	In every case where, in the Specification, materials, appliances or fittings of special design, manufacture or description, patented or otherwise, are described, or the names of the manufacturers or agents are given, it is clearly understood that such references are inserted solely for the guidance of intending contractors with respect to the nature and quality of the articles or services required	item	1	
Samples				
B	Samples of all materials, manufactured articles and executed work shall be submitted to the Architect for approval before adoption. Such adoption will not relieve the Contractor from responsibility for any defects.	item	1	
C	Materials and manufactured articles supplied or fixed, or work executed without submission and approval of samples shall be removed and the necessary reinstatements executed at the Contractor's expense should the Architect so direct.	item	1	
D	All materials are to be new unless otherwise specified and, if required, the contractor is to furnish evidence that the materials are of the origin, description and quality or price specified.	item	1	
E	Except where otherwise provided for in the tender other factors being equal, it is desirable that all the articles, appliances, goods and materials provided under the contract shall, where possible be manufactured in the Republic of Ireland, and shall bear the Irish Trade Mark where same can be applied.	item	1	
Carrolls Talbot Street			To Collection €	
BQ/33				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Tests AThe Contractor shall supply samples of materials, fixed or unfixed for such tests as may be required by Clause 8 of the Conditions and execute all necessary removals and reinstatements BThe contractor shall provide for the delivery of samples and materials, including aggregates and concrete test cubes, to testing authorities. CMaterials for which testing facilities are not available with the Council shall be sent to the National Standards Association of Ireland or equal approved testing body. DAn official order from the contractor is to accompany the samples sent to NSAI. Rates EPay all rates on temporary buildings. Unsuitability FIf in the opinion of the Contractor anything described in the specification or shown on the drawing is unsuitable or undesirable or inconsistent with his guarantees and responsibilities under the contract, he shall draw such matters to the attention of the Architect & Quantity Surveyor before submitting his tender or in the case of documents or instructions issued after the time of tendering as soon as practicable and in any case before the commencement of any part of the works which might be affected. Schedule of Works GThe Contractor shall keep one unpriced copy of the Schedule of Works on site and the Architect or his representative shall at all reasonable times have access to it.				
	item	1		
	item	1		
	item	1		
	item	1		
	item	1		
	item	1		
	item	1		
	item	1		
Carrolls Talbot Street BQ/34 To Collection €				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Garda Requirements				
A	The Contractor shall, when necessary,make arrangements with the Garda and Local Authorities to provide access for lorries, plant, etc., to the site and these arrangements must be carried out to reduce the obstruction to traffic to a minimum. The Contractor shall comply with all police regulations.	item	1	
Imported Items				
B	The Contractor will be required to provide a list of all imported items included in his tender together with the date of quotation and the currency conversion upon which the quotation is based.	item	1	
Setting Out				
C	The Contractor shall set out the works and keep them correct. Errors in setting out shall be put right by the Contractor at his own expense. Opening up and excavation shall not be commenced until the Engineer has inspected the setting out. The checking of any setting out or of any line or level by the Engineer or the Clerk of Works shall not relieve the Contractor of his responsibility for correctness thereof.	item	1	
Engineer's Inspection				
D	Before proceeding with work that covers and conceals previous work, the contractor shall give early notice in writing to the design team and shall afford them an opportunity of inspecting the previous work. Approvals given at such inspections will not relieve the Contractor from full responsibility for the quality of the work throughout.	item	1	
Carrolls Talbot Street BQ/35				To Collection €

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Foundations AThe Contractor shall excavate for all foundations to walls and piers and for all underground drainage work and shall put in and if specified reinforce the several footings, beds, rising walls and underground parts of the works in the positions and to the dimensions indicated on the drawings, Schedule of Works, and specification.If the nature of the subsoil renders it necessary or desirable in the opinion of the Engineer to vary the work from that drawn or specified, such variations shall be deemed an omission, alteration, addition or substitution as the case may be coming within Clause 13 of the Conditions of Contract. Pipe Courses B Pipe, cable and wire courses shall be laid out by the Contractor as far as practicable for approval by the Engineer and laying or fixing shall not be commenced without such approval. C Existing pipe, cable or wire courses interfered with during the execution of the work, shall be reinstated to the Engineer's satisfaction. Charge of Work D The Contractor shall be given possession of the site at the commencement of the work and he shall take entire charge of the building works from commencement to completion of same, and he shall make good all injuries, damages and repairs occasioned or rendered necessary to same by any act whatsoever.				
	item	1		
	item	1		
	item	1		
	item	1		
Carrolls Talbot Street BQ/36				
To Collection €				

(09) Preliminaries and Insurances (Cont)

(Cont) CONTRACT

(Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR

Maintenance Period

A The work shall be maintained by the Contractor in perfect condition for twelve (12) months after the issue of the Architect's Certificate that the work is practically completed and any work exhibiting defects during that period shall be made good by the Contractor at his own expense.

item

1

Liability for Defects

B Any work showing defects or any other damage, whether such defects or damage were caused by or consequential upon the negligence of the Contractor or not and whether the discovery of such defects etc., was made during the progress of the work, or completion of the work, or whether payment had been fully certified or the works approved of, the Contractor shall make good, at his own expense, such defects or damage complained of or on his refusal to do so the Employer shall be entitled to carry out the work and recover expenses in accordance with the Condition of Contract.

item

1

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Liquidated Damages for Delay A If the Contractor shall fail to complete the works within the time prescribed herein or within the extended time for completion then the Contractor shall pay to the Employer the sum as set out in the Appendix as liquidated and ascertained damages for such default for every week or part of a week which shall elapse between the time prescribed in the Agreement or extended time as the case may be and date of completion of the works. The Employer may without prejudice to any other method of recovery deduct the amount of such sums from any monies due or which may become due to the Contractor. The payment or deduction of such damages shall not relieve the Contractor from his obligation to complete the works or from any other of his obligations and liabilities under the Contract. Meaning of Practical Completion B 'Practical Completion' means that the Works have been carried out to such a stage that they can be taken over and used by the Employer for their intended purpose and that any items of work or supply then outstanding or any defects then patent are of a trivial nature only and are such that their completion or rectification does not interfere with or interrupt such use. Such outstanding items and defects shall be proceeded with expeditiously and shall be finished or rectified within a reasonable time after the date of Practical Completion. Retention C The Retention money shall be paid on completion of the work and the at the end of the retention period, and only then if the contract terms of maintenance have been properly carried out.				
	item	1		
	Item	1		
	item	1		
Carrolls Talbot Street BQ/38				To Collection €

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Proof of Vesting of Title of Materials				
A	Where a progress statement has been made in accordance with the provisions of Clause 35 of the General Conditions includes a claim for payment of materials off site, the Contractor shall submit as a part of the said statement a Vesting Certificate in respect of each such item.	Item	1	
B	Vesting Certificates shall be in an approved form and shall certify that full ownership, free from any lein or charge, in the certified item passes to the Contractor or to a Nominated sub-contractor not later than upon delivery of such said item to site notwithstanding any contract which may otherwise exist in respect of the said item and whether or not any party has been paid for the said item or part thereof. Vesting certificates must be submitted to the Employer's legal advisers for approval and payment will not be made until approval has been received by the contractor from the Employer's legal advisers.	Item	1	
C	Vesting certificates shall be duly executed by the suppliers of the said items and shall warrant title in the said items sufficent to maintain the provisions of this Clause. Vesting certificates must be submitted to the Employer's legal advisers for approval and payment will not be made until approval has been received by the contractor from the Employer's legal advisers.	Item	1	
Carrolls Talbot Street			To Collection €	
BQ/39				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Workpeople				
A	None but fully qualified and competent workpeople shall be employed on the works and the Contractor shall furnish such evidence as the Architect may require as to the qualifications and competence of any workperson. The Architect shall have the power to have dismissed from site any workperson who misconducts himself/herself or who is incompetent negligent and , the Architect, shall be the sole judge in this.	item	1	
B	The Contractor shall be responsible for keeping all workpeople under his control and within the confines of the site.	item	1	
C	Every possible means must be availed of on the part of the Contractor and his Foreman in charge of the works to ascertain that the clauses of the General Conditions of Contract with reference to Trade Union and Local Labour are complied with. Insurance cards of all workpeople employed on the works, including those employed by sub-contractors are to be available for inspection from time to time by the Clerk of Works or responsible Trade Union Officials at reasonable periods during the progress until the completion of the contract.	item	1	
D	Provide all transport required for workpeople.	item	1	
Materials and Workmanship				
E	The Contractor shall warrant that he has not used and will not use in the construction of the Works any materials known to be deleterious to health and safety or to the durability of the Works or not in compliance with Irish Standards (or if there are no Irish Standards, the relevant British Standards).	Item	1	
Carrolls Talbot Street BQ/40				To Collection €

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR (Cont) Materials and Workmanship				
A	Materials, goods and workmanship are to be of the best quality of their respective kinds and those for which there is an Irish or British Standard or Code of Practice are to comply therewith unless otherwise stated.	Item	1	
B	The Contractor shall provide for a quality control system as required by the Architect.	Item	1	
C	The Architect shall have power to direct the removal of all defective materials from the works by the Contractor.	Item	1	
D	The Contractor shall comply with the provisions of the current Building (Safety, Health, Welfare and Environmental) Regulations.	Item	1	
E	If required by the Engineer, the Contractor shall provide a copy of any Code of Practice for use by the foreman on site.	Item	1	
F	Preambles and descriptions of materials, goods and workmanship given in any one section or trade are to apply throughout this Schedule of Works unless otherwise described	Item	1	
G	Materials generally shall be of Irish manufacture.	Item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR</u>				
<u>(Cont) Materials and Workmanship</u>				
A	Where components or materials are specified to comply with a National Standard, the relevant standard number shall be marked on the commodity or on the delivery docket. Generally, reference to Irish, British or other Standard or Code of Practice do not give the year of issue or dates of amendments and the latest relevant published version including any relevant amendments published at the date of tender shall apply. Where a Standard or Code of Practice has been superceded, the edition current at the date of invitation to tender shall apply. The Contractor shall provide a copy of the Irish Standards Handbook or other relevant Codes of Practice for use by his supervisory staff.	Item	1	
B	Where appropriate all materials delivered to the site shall bear the manufacturers name, brand or any other data that may be required to verify the exact nature of the material and relate it to the requirements of the specification. Where applicable materials shall bear the British Standards Certification mark and or the British Board of Agreement Certificate mark.	Item	1	
C	Work test certificates shall include whenever applicable, the location of the work or the delivery or batch which the sample represents.	Item	1	
D	Assessment of the quality of the materials and workmanship shall be made in the presence of the Architect or his representative, unless otherwise instructed.	Item	1	
E	The Contractor shall make available to the Architect or his representative any instruments or other equipment and every assistance that they may require for checking the accuracy and quality of the works.	Item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR</u>				
<u>(Cont) Materials and Workmanship</u>				
A	Unless otherwise specified the accuracy of the work shall comply with B.S. 5606.	Item	1	
B	The Contractor shall be deemed to have included in his rates for all items to comply with the specified tolerances as well as completing the works to tolerances of existing structures, finishes and services which currently pertain on site.	Item	1	
C	The Main Contractor is to provide for maintenance manuals on each system installed by him or his domestic Sub-Contractors outlining product literature, maintenance, dismantling and providing specialist tools for same, cleaning, test certificates, guarantees, warranties etc., bound in A4 indexed volumes with electronic copy made availbale upon request from the Employer	Item	1	
<u>Standards</u>				
D	Where National Standards to which equipment or materials must comply are cited goods meeting other authoritative standards which ensure an equal or higher quality than the standards mentioned, will also be accepted. Where reference is made in the Schedule of Works to specific brand names, catalogue numbers or type of equipment or a specific manufacturer, offer of alternative equipment, articles or materials which have similar characteristics and provide equal performance and quality to those specified will also be considered. Any substitutions which the Contractor proposes to make in this respect must be approved by the Architect in writing before incorporating into the work. Any approval given by the Architect in this respect shall not relieve the Contractor from his responsibility for the performance and quality of his proposed substitutions.	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR</u>				
<u>(Cont) Standards</u>				
A	Agrement certificates are to be provided for all materials proposed by the Contractor	item	1	
<u>Local Labour</u>				
B	Persons engaged upon the works should insofar as practical and without affecting the efficiency of the work be recruited from the local offices of FAS to the extent that the total labour requirement of the contract exceeds the contractors core work force.	item	1	
<u>Fire Prevention during Construction</u>				
C	Contractors attention is drawn to the fire hazard that may exist during the construction and commissioning period of the building. It is recommended that the Site Safety Officers responsibilities should extend into the field of fire safety and should cover all facets of the subject.	item	1	
D	Particular attention is drawn to the schedule of Safety Precautions the use of bottle propane on building sites issued by the manufacturers.	item	1	
E	No outdoor burning of any description is to accur on the site.	item	1	
F	Provide for setting up, maintaining and removing on completion of the job, sufficient suitable first aid fire fighting equipment.	item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Notice re P.C. Sums				
A	Where P.C. Sums are provided for the execution by himself or other Contractor of special works requiring cutting out, reinstatement, the use of scaffolding, ladders, planks, etc. or other attendance, the Contractor shall give due notice in writing to the Engineer so that such special works may be completed before the tradespeople whose attendance is required have completed their work elsewhere in the building but no claim for extra remuneration on account of their non-completion before such date shall be made.	item	1	
Time and Material				
B	No work of any kind, payment for which is to be made on a "Time and Material" basis, shall be executed unless the complete arrangements for such are specially authorised by the Architect in writing beforehand. The Contractor in such cases shall be paid at the Daywork Charges agreed between the Society of Chartered Surveyors and the Construction Industry Federation and approved by the Royal Institute of the Architects of Ireland.	item	1	
C	Vouchers specifying the time for each day (and if required by the Architect, the workmens names) and the materials used shall be delivered for verification to the Architect or his authorised representative at or before the end of the week following that in which the work has been executed.	item	1	
Carrolls Talbot Street			To Collection €	
BQ/45				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) SPECIAL FACILITIES, OBLIGATIONS AND RESTRICTIONS ON CONTRACTOR Patent Rights & Royalties				
A	The Contractor shall save harmless and indemnify the Employer from and against all claims and proceedings for or on account of infringement of any patent rights design, trademark or name or other protected rights in respect of any constructional plant machine works or material used for or in connection with the works	item	1	
Definitions				
B	Words importing the singular only also include the plural and visa versa where the context requires.	item	1	
C	The following abbreviations are used:-	item	1	
D	IS-Irish Standard Specification; BS-British Standard Specification; ARM agreed rules of measurement	item	1	
E	The term "the works" shall mean the whole of the works envisaged by this Contract, including, unless expressly stated otherwise, the works of Sub-Contractors, Nominated Suppliers, Local Authorities and Public Under-takings.	item	1	
F	The term "Fix" where used in connection with materials or goods supplied by a Nominated Supplier shall include the actual fixing in position, also unloading, storing, hoisting and returning packing materials, carriage paid, to the merchants.	item	1	
Carrolls Talbot Street			To Collection €	
BQ/46				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT WORKS BY NOMINATED SUB-CONTRACTORS, GOODS AND MATERIALS FROM NOMINATED SUPPLIERS AND WORKS BY PUBLIC BODIES Work by Nominated Sub-Contractors General Attendances A Notwithstanding the fact that the Schedule of Works has not been prepared in accordance with the ARM it should be noted as a guide that the facilities referred to in ARM Clause B.4 are deemed to be included in the items of general attendance on Nominated Sub-Contractors, Local Authorities and Public Undertakings. those items are as follows: the use of contractor's temporary roads, hardstandings, standing scaffolding, standing power operated hoisting plant, the provision of temporary lighting and water supplies, clearing away and disposal of rubbish, provision of space for the subcontractors own offices and the storage of his plant and materials, and the use of the messrooms, sanitary accommodation and welfare facilities. B In addition, all items of general attendance shall be deemed to include arranging with Nominated Sub-Contractors, Local Authorities, Public Undertakings and Nominated Suppliers as to time for commencement of their work on this site or the manufacture and delivery of their goods and materials as appropriate, obtaining from them particulars of holes,mortices, chases, recesses, fixings and the like and supply them with all dimensions and other information required for the proper execution of the works.				
	item	1		
	item	1		
Carrolls Talbot Street				To Collection €
BQ/47				

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) WORKS BY NOMINATED SUB-CONTRACTORS, GOODS AND MATERIALS FROM NOMINATED SUPPLIERS AND WORKS BY PUBLIC BODIES</u>				
<u>Special Attendances</u>				
A	Notwithstanding the fact that the Schedule of Works has not been prepared in accordance with the ARM it should be noted as a guide that the Contractor shall allow for all costs arising from the items of special attendance, as outlined in clause 3.1 of the ARM, which have been included where required, after the items of general attendance. The meaning of such items shall be as below:-	item	1	
B	Unloading and hoisting shall include for unloading all materials and plant, storing, hoisting or lowering to various floor levels where required and depositing where requested if possible.	item	1	
C	Unless otherwise stated, the handling and moving of plant and materials to their positions after depositing at the required floor will be carried out by the Sub-Contractor.	item	1	
D	Special scaffolding shall include for providing, erecting and dismantling scaffolding or the equivalent beyond that required for the Contractors own use to enable Sub-Contractors to execute their work. Special scaffolding has been referred to only where Sub-Contractors may require scaffolding in locations where there is no contiguous work by the Contractor for which scaffolding would generally be used.	item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) WORKS BY NOMINATED SUB-CONTRACTORS, GOODS AND MATERIALS FROM NOMINATED SUPPLIERS AND WORKS BY PUBLIC BODIES (Cont) Special Attendances				
A	Notwithstanding the absence of a reference to special scaffolding, the Contractor is to allow in the item for attendance for the provision of scaffolding for the Sub-Contractors if the method of scaffolding he proposes to use for contiguous work would not provide adequate scaffolding for the Sub Contractor's work described, due consideration being given to the period of the Contract at which the Sub- Contractors work will be carried out. Other facilities shall be as described in the items.	item	1	
B	The provision of adequate covered storage and accommodation including lighting and power thereto.	item	1	
Goods and Materials from Nominated Suppliers Fixing				
C	Fixing of goods and materials supplied by Nominated Suppliers shall be deemed to include unloading, storing, hoisting the goods and materials and returning packing materials to the Nominated Suppliers-carriage paid and obtaining credits therefor.	item	1	
Conveying Goods and Materials to the Site and Special Packing				
D	Notwithstanding the fact that the Schedule of Works has not been prepared in accordance with the ARM and notwithstanding the provisions of ARM Clause B.3.2., the costs required to be paid by the Contractor of conveying goods and materials to the site, any special packing and the like, are included in the appropriate prime cost sums and particulars are not in the measured items.	item	1	
Carrolls Talbot Street			To Collection €	
BQ/49				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) WORKS BY NOMINATED SUB-CONTRACTORS, GOODS AND MATERIALS FROM NOMINATED SUPPLIERS AND WORKS BY PUBLIC BODIES Assignment and Subletting				
A	The Contractor shall not assign the contract or any part thereof or benefit or interest therein or there under without the written consent of the Employer.	item	1	
B	The Contractor shall not sub-let the whole of the works. Except where otherwise provided by the contract the Contractor shall not sub-let any part of the Works without written consent of the Engineer, and such consent, if given, shall not relieve the Contractor from any liability or obligation under the Contract and he shall be responsible for the acts, defaults and neglect of any Sub-Contractor, his agents, servants or workpeople as fully as if they were the Acts, defaults, or neglects of the Contractor, his agents,servants or workpeople. This paragraph shall apply to Sub-Contractors,manufacturers or others for the Contractor, as it applies to the Contract insofar as it is applicable to their work and the necessary extracts shall be sent to them.	item	1	
	Sub-Contractors			
C	The Contractor shall give all facilities and render all necessary assistance to Sub-contractor allowing them the use of scaffolding, platforms, ladders, hoists, screens, water supply power, safe storage accommodation, labour for unloading and bringing in and all help save only the materials, labour and special equipment specifically covered by their sub contracts.	item	1	
Carrolls Talbot Street			To Collection €	
BQ/50				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) WORKS BY NOMINATED SUB-CONTRACTORS, GOODS AND MATERIALS FROM NOMINATED SUPPLIERS AND WORKS BY PUBLIC BODIES Provisional Items				
A	Work described as "provisional" or covered by the inclusion of a Provisional Sum shall not be commenced without the Architect's's approval as to the manner in which it is to be done and the way in which its cost is to be ascertained. The Contractor shall apply for such instructions in good time.	item	1	
GENERAL FACILITIES AND OBLIGATIONS Supervision and Coordination of the works				
B	The Contractor shall give and provide all neccessary personal superintendence during the execution of the works and for as long thereafter as the Architect may consider necessary. It shall include person(s) with first class experience in general construction, steel portal frame construction,concrete and roof works within a live environment	item	1	
C	The Contractor shall be responsible for the co-ordination of all work carried out by Nominated Sub-contractors. He shall familarise himself totally with all sub-contract drawings and details. He shall also obtain from each sub-contractor, detailed programme of their works and examine these closely in conjunction with the relevant drawings.The Contractor shall identify items of work or operations on site as a result of these examinations which may interfere with one another to the detriment of the progress of the works. He shall discuss these with the Sub Contractors and reach agreement with them on altering the sequence of the work or revising the programme (if necessary) so that the overall project is not affected.	item	1	
Carrolls Talbot Street			To Collection €	
BQ/51				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) GENERAL FACILITIES AND OBLIGATIONS Site Management Costs				
A	Provide for all on and off site management costs (including the cost of Foreman in charge referred to in Clause 10 of the Conditions of Contract).	Item	1	
B	The Contractor shall agree to maintain an adequate professional site management team duration of the Works for so long as they may remain in the employment of the Contractor, it being understood that continuity of the Contractor's personnel throughout the Works is of the utmost importance to the Employer. The Contractor shall agree that the services of the Works shall be dedicated solely to the Works unless otherwise agreed by the Employer.	Item	1	
Project Manager				
C	The Contractor will be required as one of the Conditions of Contract to appoint an experienced and competent Project Manager, approved by the Architects whose sole duties will be the management of the job on the Contractor's behalf. The person selected by the Contractor for this position will be a member of the Contractor's staff who has already had experience of acting in a similar capacity on a job of similar size and complexity to that of this development.	Item	1	
His duties will include the following:				
D	(a) The preparation and keeping up to date of a programme which will incorporate the activities of all those participating in the Contract, this programme to be continuously developed and amended as the list of Sub-Contractors grows and agreements on dates and times are made.	Item	1	
Carrolls Talbot Street			To Collection €	
BQ/52				

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) GENERAL FACILITIES AND OBLIGATIONS</u>				
<u>(Cont) Project Manager</u>				
A	(b) The co-ordination of the activities of all Sub-Contractors and Suppliers by the arrangement of scheduled site meetings on a monthly or twice monthly basis as the progress of the Contract demands. These meetings would be chaired by the Contractor's Project Manager who would keep and circulate minutes to all parties concerned including the Architect.	Item	1	
B	(c) The facilitation of formal site meetings which will be attended by the Architect, Employer's Project Manager, Quantity Surveyor, Fire Consultant and any Sub-Contractor whose presence for the discussion of some particular aspect of the job would be desired. The Employer's Project Manager will be responsible for calling and chairing the formal site meetings and will keep and circulate the minutes.	Item	1	
C	(d) The organisation of ad hoc informal meetings attended by all or some of the main participants in the project. Such meetings may be called at the instigation of the Architect or of the Employer's Project Manager for the purpose of dealing with problems which may require immediate attention or are of too detailed a nature to be discussed at the site meetings.	Item	1	
D	(e) Liaison between the Architect and Sub-Contractors (the Architect intends, as far as possible, to avoid having direct contact with any Sub-Contractor except through the Main Contractor or in exceptional cases in the presence of the Contractor's Project Manager as representative of the Main Contractor).	Item	1	
E	(f) Liasing as required with the Golf Club manager to ensure construction and golf related activities are as aligned as is possible at all times	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) GENERAL FACILITIES AND OBLIGATIONS</u>				
<u>Overtime</u>				
A	Contractors are required to include for all necessary overtime necessary for the completion of the works within the programmed dates. Where the working of overtime is made a condition of employment in any particular trade, no claim for extra will be allowed under this heading. Claims for specific overtime will only be entertained when authorised in writing by the Architect as an extra on the Contract. Approval of the Architect must be obtained for any nightwork.	Item	1	
<u>Superintendence</u>				
B	The Contractor shall give and provide all necessary personnel and superintendence during the execution of the works and for as long as thereafter as the Architect may consider necessary. It shall include persons with first class experience in nursing home development .	Item	1	
<u>Setting Out</u>				
C	The Contractor shall set out the works and keep them correct. All instrument work in setting out to be done by personnel experienced and practised in this work. Opening up and excavation shall not be commenced until the Engineer has inspected the setting out. The checking of any setting out or of any line or level by the Engineer shall not relieve the Contractor of his responsibility for the correctness thereof.	Item	1	
D	If the setting out personnel are not members of the Main Contractors staff, they must be members of a properly established surveying firm, with the necessary qualifications to carry out the whole of the work in an expert manner. The contractor will be wholly responsible to the Employer for any errors in the work and meet all costs arising therefrom.	Item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) GENERAL FACILITIES AND OBLIGATIONS Plant, Tools and Vehicles Provide all plant, craneage, tools and vehicles necessary for the proper execution of the works. Include for bringing all plant to site and removal of same on completion including crane bases etc. Include for maintaining on site for the duration of the works.				
A	(a) Mechanical Plant and Vehicles	Item	1	
B	(b) Non-Mechanical Plant	Item	1	
C	(c) Tressles, ladders and access equipment	Item	1	
General Scaffolding D Provide all necessary temporary scaffolding for the proper execution and completion of the works. If the Contractor should strike any of this scaffolding before ascertaining whether it is required by a Sub-Contractor or Public Authority, he must re-erect it, if so required, at his own expense. It should be particularly noted that full scaffolding of the gallery building and any additional works required to prevent water ingress into the building during the works should be included against this item, as well as any other areas requiring scaffolding to execute the described works				
		Item	1	
Removal of Plant E Plant/scaffolding etc shall not be removed until ordered by the Architect and when so ordered it shall be removed expeditiously.				
		Item	1	
Site Administration and Site Records F The Contractor shall keep fully detailed daily records of all plant and labour force, identifying their occupation, trade and status and materials used on site (Including manufacturer's certificates).				
		item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) GENERAL FACILITIES AND OBLIGATIONS (Cont) Site Administration and Site Records				
A	The Contractor shall keep detailed dated records of the progress of the works, and where directed by the specification, of dimensions of completed works.	item	1	
B	The Contractor shall keep a daily record of weather conditions. Records should record changes in conditions which occur within any one day.	item	1	
C	The Contractor may be required to liaise with local organisations/residents, etc., during the course of the works. The Contractor is to include here for all costs involved in this regard.	item	1	
Protection Watching and Lighting				
D	The Works shall be protected at all times against damage from inclement weather, impact, or any other cause and the Contractor shall provide water-proof and frost-proof coverings, temporary shelters, temporary drainage and any other necessary protection for this purpose	item	1	
E	The Contractor shall provide all necessary watching, lighting, fencing, hoardings, etc., as is necessary for the protection of the public; for protection of the works and grounds; for protection of the works being carried out; for protection and security of all materials on site; and for the protection of the site against trespass and interference.	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) GENERAL FACILITIES AND OBLIGATIONS</u>				
<u>(Cont) Protection Watching and Lighting</u>				
A	The Contractor shall provide adequate fencing or other such security means as necessary to the boundary of the site. In this respect, the Contractor's attention is drawn to the requirement to visit the site to ascertain its nature and to maintain access to existing services, etc. Provide Protection generally. Provide safety nets, etc. (See also "Temporary Hoardings and Gantries" previously in this element for hoardings etc. specifically required by the Employer and "Hoardings and Screens" later in this element.)	item	1	
B	Provide and erect all necessary temporary road barriers held securely across carriageways and remove off site on completion.	item	1	
C	The Contractor, if deemed required to adequately protect the works, is to provide static guard security from 6pm to 8am during weekdays and from 1pm Saturday (if Saturday morning operation by Contractor is envisaged) to 8 am on Monday for the entire duration of the contract	item	1	
D	Provide adequate protection to the site, materials etc., and erect efficient and sufficient guards to prevent unauthorised persons trespassing on the site and for the proper protection of the public, staff, visitors and all invitees and licencees of the employer.	item	1	
E	Notwithstanding the fact that the Schedule of Works has not been prepared in accordance with the ARM the Rules of Arm dispense with the requirement for items of protecting the works in each element and for the protection of individual floor finishes. the Contractor shall provide here for all costs in connection with protecting the works at all stages and for protecting all finished works until completion of the project.	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) GENERAL FACILITIES AND OBLIGATIONS</u>				
<u>Water for the Works</u>				
A	The Contractor shall allow for all temporary plumbing work, etc., necessary and shall make his own arrangements for the supply of water for the works.	item	1	
<u>Temporary Services</u>				
B	The Contractor shall provide all necessary supplies of electricity (single and three phase) and other services necessary for the execution of the works, shall pay all charges in connection therewith and shall ensure that all temporary installations are made in a safe and proper manner, and cleared away and made good on completion.	item	1	
<u>Local Residents and Businesses</u>				
C	The Contractor must ensure that his operation causes least inconvenience to local residents and business, etc.. Any damage caused to residents' or other property, public property, etc., must be made good at Contractor's cost.	item	1	
D	Take all reasonable precautions to minimise nuisance to the occupants of the adjoining properties. Include for complying with all statutory regulations in this regard	item	1	
<u>Temporary Roads</u>				
E	Provide and maintain all necessary temporary roads, hardstandings and crossings on site and remove on completion	item	1	
F	The contractor shall be responsible for all damage to existing roads caused by his own or sub-contractors or suppliers transport to and from the site.	item	1	
G	Maintain and protect public property and the property of Public and Private Utility Companies and make good or pay for the making good of all damage thereto.	item	1	
Carrolls Talbot Street				To Collection €
BQ/58				

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) GENERAL FACILITIES AND OBLIGATIONS Temporary Accommodation for use by the Contractor				
A	(a) Storage Sheds: - Suitable sheds for use by the workpeople and the storage of materials shall be provided by the Contractor, maintained during the duration of the work and removed on completion, the site thereof being made good. Stores for cement and other materials prone to water damage are to be watertight and are to have raised floors to the approval of the Engineer.	item	1	
B	(b) Foreman's, Site Agents Office: - Provide, erect and maintain separate suitable lockable offices for the use of the Main Contractor's site staff with all necessary fittings and remove on completion. Provide for telephone and fax from commencement and pay all charges, remove and make good on completion	item	1	
C	(c) Sanitary Conveniences: - Provide suitable sanitary convenience(s) for the clerk of works and the workpeople in an appropriate area of the site and to the approval of the Architect. They shall be maintained by the Contractor at all times in a clean and hygienic condition and removed at the completion of the works, the site being made good and deodorised where necessary	item	1	
D	(d) Provide suitable common canteen facilities for all workpeople in an appropriate place on the site and to the approval of the Architect. They shall be maintained by the Contractor at all times in a clean and hygienic condition and removed on completion of the works, the site being made good and deodorised where necessary. All food/drink consumption must be limited to within the designated area. Builder's compound/carparks to kept litter free at all times during the works.	item	1	
Carrolls Talbot Street			To Collection €	
BQ/59				

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) GENERAL FACILITIES AND OBLIGATIONS</u>				
<u>(Cont) Temporary Accommodation for use by the Contractor</u>				
A	(e) Provide appropriate areas for Nominated Sub-Contractors to set up their site accommodation and secure storage huts.	Item	1	
B	On completion, the temporary offices including hardcored areas and temporary fencing, shall be removed and the site made good.	Item	1	
<u>Traffic Regulations</u>				
C	(i) The Contractor shall be responsible for the control of traffic on to the public road and within the car park and shall, if necessary, provide the services of a flagman and/or temporary traffic lights to control the traffic. ii) Provide temporary car-parking facilities for Contractors staff.(See also "Garda Requirements" previously in this element.); this will be particularly relevant during ocmpletion of the siteworks on a phased basis	item	1	
<u>Disbursements arising from the Employment of Workpeople</u>				
D	Provide for all costs in respect of all workpeople for:-	item	1	
E	(a) Social Welfare Insurance Contributions-	item	1	
F	(b) Pensions/Sick Pay Scheme The Construction Industry Federation (CIF) Pension/Sick Pay Scheme is legally binding on all contractors in the industry, tenderers should therefore comply with their obligation to make pension fund/sick pay contributions. Membership of the above scheme is a condition precedent to the award of the contract.	item	1	
G	(c) Annual and Public Holidays	item	1	
H	(d) Travelling time, expenses, fares and transport	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) GENERAL FACILITIES AND OBLIGATIONS</u>				
<u>(Cont) Disbursements arising from the Employment of Workpeople</u>				
A	(e) Guaranteed time	item	1	
B	(f) Non-productive overtime and other expenses in connection with over-time	item	1	
C	(g) Incentive and bonus payments	item	1	
D	(h) Sick Pay Disbursements	item	1	
E	(i) Country Money, Subsistence Payments	item	1	
F	(j) FAS Levy	item	1	
G	(k) Any other disbursements arising from employment of labour	item	1	
<u>Maintenance of Public and Private Roads</u>				
H	Maintain public and private roads, Public pavings, footpaths, kerbs, etc., and keeping the approaches to the site clear of mud or debris. The Contractor is to make good any damage caused by his own or any Sub- Contractors or Suppliers transport, at his own expense and pay costs and charges in connection therewith.	item	1	
<u>Clearance of the Site</u>				
J	On completion of the Works and as and when directed by the Architect, the Contractor shall clear away and remove from the site constructional plant, surplus materials, rubbish and temporary works of every kind and leave the whole of the site and Works clean in a workmanlike condition to the satisfaction of the Engineer.	item	1	
<u>Cleaning</u>				
K	Clean the works generally remove all rubbish and leave the entire works in a tidy condition ready for occupation or use to a standard of finish provided by contract cleaners	item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) GENERAL FACILITIES AND OBLIGATIONS (Cont) Cleaning				
A	Allow for cleaning roads and carparks by brushing and hosing at regular intervals as instructed by the Architect and as previously noted	item	1	
Dust Control				
B	The contractor must control dust levels at all times; this is particularly relevant given the live nature of the environment; the contractor is deemed to have included for all dust screens, regular cleaning, water sprays etc to keep all areas of the existing buildings free from dust for the duration of the works. This applies also to areas adjacent the proposed contractors compound and any areas through which materials for the contract have been distributed. The contractor should include for cleaning the front and rear path and roadways as required of any construction related dirt or residue	Item	1	
Making Good Defects				
C	The work shall be maintained by the Contractor in perfect condition for 12 months after the issue of the Architect's Certificate of 'Practical Completion' and any work exhibiting defects during that period shall be made good by the Contractor at his own expense prior to the issue of the Final Certificate.	Item	1	
D	Provide for making good defects within the defects liability period immediately after notification of same.	item	1	
Protection of the Works				
E	The Contractor's attention is drawn to the necessity to provide adequate protection to all new works, fencing, boundary walls, paving, ductwork , drainage, pipework and gullies, landscaping, etc.	Item	1	

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) GENERAL FACILITIES AND OBLIGATIONS Inclement Weather				
A	Provide for maintaining and protecting the building in a watertight and frost proof condition, at all times from inclement weather.	Item	1	
Compliance with Waste Management Statutory Requirements				
B	Materials excavated from the site shall unless expressly stated otherwise be removed from site and disposed of at a tip to be provided by the Contractor. The Contractor shall ensure that all waste is removed from site by approved waste disposal contractors, to approved waste disposal facilities. Details of the final destination of all waste shall be furnished to the Engineer quoting the reference number of the Waste Collection Permit issued under the Waste Management (Collection Permit) Regulations 2001. Prior to the construction a formal Project and Construction Waste Management Plan is to be submitted to the Environment Department of Fingal County Council. This plan shall include information requested in Sections 3.2, 3.3 and 3.4 of the document entitled "Best Practice and Guidelines on the Preparation of Waste Management Plans for Construction and Demolition Projects" published by the Department of Environment, Heritage and local government.	item	1	
Carrolls Talbot Street BQ/63				To Collection €

(09) Preliminaries and Insurances (Cont) (Cont) CONTRACT (Cont) GENERAL FACILITIES AND OBLIGATIONS Drying the Works				
A	Provide all necessary equipment, fuel and attendance for drying and controlling the humidity of the works to the complete satisfaction of the Architect and in sufficient time to ensure that completion of his own and sub-contractors work is not delayed by failure to do so. Where the permission of the Architect is given to use the permanent heating system for drying and obtaining the necessary temperature levels, the Contractor shall allow for all costs related to this item including fuel and the extending of warranties	item	1	
Enclosing				
B	The site of the works shall be effectively enclosed and protected against trespass and interference.	item	1	
Hoardings and Screens				
C	The Contractor shall provide secure temporary dust proof screens to fence off his working area. Suitable temporary signs shall be erected in positions nominated by the design team to indicate alternative escape routes when a route has been closed to execute the work. The Contractors shall provide suitable secure temporary hoardings to all new openings in external walls and make good all work disturbed on completion.	item	1	
D	Suitably constructed hoardings; shall be provided around the specific work areas to ensure the adequate segmentation of these areas from the live environmnet and the protection of all existing patrons and staff; include here also for any additonal health and safety requirements that may be necessary as a result of this environment;	item	1	
Carrolls Talbot Street			To Collection €	
BQ/64				

<u>(09) Preliminaries and Insurances (Cont)</u>				
<u>(Cont) CONTRACT</u>				
<u>(Cont) GENERAL FACILITIES AND OBLIGATIONS</u>				
<u>Temporary Propping and Shoring</u>				
A	Temporary works as required are NOT MEASURED in this document and the cost of all such works is deemed to be included in the Contractors general rates.	Item	1	
<u>Control of Noise and Pollution</u>				
B	Wherever construction and demolition noise could cause nuisance to the public or to adjacent occupiers, the Contractor shall take measures to minimise such effects by applying those recommendations contained in B.S. 5228: Part 1, and in particular clauses 15 and 16 of Section 5 and Table 6 of Appendix C, which are applicable to the circumstances.	item	1	
C	Compliance with the above requirements does not in itself constitute any grounds for defence against any legal proceedings which may be instituted against the Contractor.	item	1	
D	No claim for delay or costs arising therefrom will be accepted by the Architect in respect of this clause.	item	1	
E	On no account will the burning of rubbish or surplus materials be allowed and all the provisions of the Air Pollution Act 1987 shall be met by the Contractor.	item	1	
<u>Contingency Sum</u>				
F	Include a Provisional Sum of €25,000.00 to be used as an Employer's contingency for work which cannot be entirely defined or detailed		1	
ADDITIONAL ITEMS				
G	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	

<u>(09) Preliminaries and Insurances (Cont)</u>				
COLLECTION				
Page No. BQ/1				
Page No. BQ/2				
Page No. BQ/3				
Page No. BQ/4				
Page No. BQ/5				
Page No. BQ/6				
Page No. BQ/7				
Page No. BQ/8				
Page No. BQ/9				
Page No. BQ/10				
Page No. BQ/11				
Page No. BQ/12				
Page No. BQ/13				
Page No. BQ/14				
Page No. BQ/15				
Page No. BQ/16				
Page No. BQ/17				
Page No. BQ/18				
Page No. BQ/19				
Page No. BQ/20				
Page No. BQ/21				
Page No. BQ/22				
Page No. BQ/23				
Carrolls Talbot Street				BQ/66

(09) Preliminaries and Insurances (Cont)				
COLLECTION				
Page No. BQ/24				
Page No. BQ/25				
Page No. BQ/26				
Page No. BQ/27				
Page No. BQ/28				
Page No. BQ/29				
Page No. BQ/30				
Page No. BQ/31				
Page No. BQ/32				
Page No. BQ/33				
Page No. BQ/34				
Page No. BQ/35				
Page No. BQ/36				
Page No. BQ/37				
Page No. BQ/38				
Page No. BQ/39				
Page No. BQ/40				
Page No. BQ/41				
Page No. BQ/42				
Page No. BQ/43				
Page No. BQ/44				
Page No. BQ/45				
Page No. BQ/46				
Carrolls Talbot Street				BQ/67

(09) Preliminaries and Insurances (Cont)				
COLLECTION				
Page No. BQ/47				
Page No. BQ/48				
Page No. BQ/49				
Page No. BQ/50				
Page No. BQ/51				
Page No. BQ/52				
Page No. BQ/53				
Page No. BQ/54				
Page No. BQ/55				
Page No. BQ/56				
Page No. BQ/57				
Page No. BQ/58				
Page No. BQ/59				
Page No. BQ/60				
Page No. BQ/61				
Page No. BQ/62				
Page No. BQ/63				
Page No. BQ/64				
Page No. BQ/65				
(09) Preliminaries and Insurances Carried to Summary				
Carrolls Talbot Street				
BQ/68				

<u>(- -) Existing Shop Strip Out</u>				
NOTES				
A	Note: - The contractor should note that all works described take place at ground level of an existing shop on a busy pedestrian and vehicular street; the contractor is deemed to have included for any additional costs arising from this constraint	Note		
B	Note: - Any additional works required to remove demolished material from site are deemed to be included within the rates below; the contractor is deemed to have visited the site to ascertain the method by which demolished material is to be removed as well as any access constraints which may impact on the works described below	Note		
C	Note: - It should be noted that there are directly attached neighbouring occupied properties on all sides of the proposed work area; the contractor is deemed to have included for any additional costs arising from this constraint	Note		
DEMOLITIONS GROUND FLOOR LEVEL				
<u>Removing Existing Central Display Units (Gondolas)</u>				
<u>Remove existing central storage racked units freestanding within floor space; include for deconstructing as required and removing and disposing from site; consisting of stock racking on an assumed steel framework; the contractor is deemed to have visited site to ascertain the precise extent of removals required</u>				
D	3000mm long x 1800mm wide x 1700mm high	Nr	10	

(- -) Existing Shop Strip Out (Cont) Removing Existing Racking Carefully disassemble and store on site existing shop racking for re-use; include for carefully protecting all elements during disassembly and storing in a location on site as directed by the client for future use; the contractor will be required to replace or make good any elements damaged during disassembly and storage				
A	Approximately 60 linear running metres stocked both sides 1600mm high	item	1	
Removing Existing Till Area Fittings Break up and remove from site existing till areas fittings; consisting of timber shelved units and associated worktops and upstands; include for any electrical attendance required to facilitate removal				
B	4200mm long x 800mm wide x 1600mm high at tallest point (remainder 1000mm high)	item	1	
Removing Changing Room Take down and remove from site existing changing room fitting including associated timber panels, rails and curtain;				
C	1000mm wide x 900mm deep x 2200mm high	item	1	
Removing Stud Enclosure at Front of Office Carefully take down and remove from site existing stud partition enclosure to rear of shop at front wall of office separating original timber stairs from the shop floor and remove from site; consisting of timber studwork lined in timber sheeting; 100mm thick approximately; include for removal of any sundry timberwork or boxing enclosing the stairs and any bulkheads separating it from the existing ceiling void; leave stairs fully exposing and accessible for inspection on completion				
D	4200mm long x 3500mm high	item	1	
Carrolls Talbot Street BQ/70				To Collection €

(- -) Existing Shop Strip Out (Cont) Removing Stud Enclosure at Rear of Shop Take down and remove from site existing partition enclosing rear elevation of existing shop and extending into rear of office room; assumed to consist of a timber stud partition lined one side in timber sheeting to enclose existing columns and openings in rear elevation of existing building; include for carefully protecting existing structure being retained behind and removing demolished material from site				
A	10800mm long x assumed 3800mm high x 100mm thick	item	1	
B	extra over the above for removal and disposal of single access door incorporated with same	Nr	1	
Removing Stud Enclosure at Build out in Shop Take down and remove from site existing partition enclosing build out in existing shop; assumed to consist of a timber stud partition lined one side in timber sheeting to enclose existing structure under; include for carefully protecting existing structure being retained behind and removing demolished material from site				
C	7000mm long x assumed 3800mm high x 100mm thick	item	1	
Removing Existing Suspended Grid and Tile Ceilings Take down and remove from site existing suspended grid and tile ceilings; include for removal of all primary and secondary grid members, suspended tiles, suspension arms, supports etc				
D	Ceiling Generally	m2	353	
E	Extra for any additional works associated with stepped level section of ceiling	item	1	
Carrolls Talbot Street BQ/71				To Collection €

(- -) Existing Shop Strip Out (Cont) (Cont) Removing Existing Suspended Grid and Tile Ceilings (Cont) Take down and remove from site existing suspended grid and tile ceilings; include for removal of all primary and secondary grid members, suspended tiles, suspension arms, supports etc				
A	Extra for any additional works required to facilitate removal of lighting, emergency lighting, fire alarm points etc	item	1	
B	Extra for any additional works required to facilitate removal of any mechanical equipment incorporated within the ceiling	item	1	
Removing Existing Suspended Plasterboard Ceilings Take down and remove from site existing plasterboard section of ceiling over till area and at front entrance adjacent shopfront; include for stripping all plasterboard and removing any associated framing, supports, fittings etc				
C	Ceiling Generally	m2	25	
D	Extra for any additional works required to facilitate removal of lighting, emergency lighting, fire alarm points etc	item	1	
Taking up Existing Floor Finishes				
E	Hack up existing tiled floor finishes and dispose off site; include for removal of any associated trims etc; include for removing any excess adhesive from floor slab as required	m2	368	

<u>(- -) Existing Shop Strip Out (Cont)</u>				
<u>Stripping Existing Wall Cladding</u>				
A	Carefully strip existing wall racking and storing on site for re-use; include for carefully protecting all elements during disassembly and storing in a location on site as directed by the client for future use; the contractor will be required to replace or make good any elements damaged during disassembly and storage. Include for removing any plywood or timber grounds under and disposing off site	m2	245	
<u>Stripping Plasterboard from Walls</u>				
B	Strip plasterboard and associated studwork / battens to internal face of external walls and remove from site; include for carefully protecting existing walls being retained and making good as necessary on completion	m2	245	
<u>Strip Plasterboard From Beams and Columns</u>				
<u>Carefully remove plasterboard and timberwork from existing boxed out columns; leave columns free from plasterboard or timber grounds and clear and ready for inspection</u>				
C	320mm x 320mm x 3800mm high	Nr	7	
<u>Demolition of Blockwork Walls (Provisional)</u>				
<u>Demolish existing 215mm thick solid concrete blockwork internal walls; include for all propping required; include for carefully separating from existing structures being retained and making good as necessary; the contractors attention is particularly drawn to the temporary works as illustrated on the Engineers drawings and specifications</u>				
D	Wall enclosing rear office and redundant staircase	m2	65	

<u>(- -) Existing Shop Strip Out (Cont)</u>				
<u>Removal of Staircase</u>				
Take out and remove from site existing timber staircase and associated balustrades and handrails; include for removal of all cladding and supporting structures associated; include for carefully protecting structures adjacent being retained and making good as necessary				
A	Staircase 1200mm wide consisting of three flights and two half landings; first flight 10 steps; half landing 1200mm x 1200mm; second flight 15 steps; half landing 1200mm x 2200mm; third flight 4 steps	item	1	
B	Extra over the above for demolition of associated supporting blockwork walls and blockwork walls forming alcove and balustrade to first flight	item	1	
<u>Sundry Disposal</u>				
C	The contractor is to include for the provisional of a 15 cubic yard skip and the provision of labour to fill it should the client choose to dispose of any surplus retained material from the description above, or any sundry fixtures, fittings or furniture from the existing shop deemed no longer to be required	item	1	
PROVISION FOR SUNDRY REMOVAL OF HARD PLASTERED FINISHES				
<u>Hacking off Sand and Cement Plaster (Provisional)</u>				
D	Hack off hard plaster from existing brickwork and expose brickwork entirely; include for carefully protecting brickwork and disposing of demolished material from site; it should be strictly noted that these works are not to take place until the engineer has inspected the internal face of all existing external walls following removal of stud and plasterboard linings (stud and plasterboard lining removal e.m.)	m2	100	

Carrolls
Talbot Street

<u>(- -) Existing Shop Strip Out (Cont)</u> COLLECTION Page No. BQ/69 Page No. BQ/70 Page No. BQ/71 Page No. BQ/72 Page No. BQ/73 Page No. BQ/74 Page No. BQ/75 (- -) Existing Shop Strip Out Carried to Summary				
Carrolls Talbot Street				

(- -) Demolitions Ground Floor Retail NOTES A Note: - The contractor should note that all works described take place at ground level of an existing shop on a busy pedestrian and vehicular street; the contractor is deemed to have included for any additional costs arising from this constraint B Note: - Any additional works required to remove demolished material from site are deemed to be included within the rates below; the contractor is deemed to have visited the site to ascertain the method by which demolished material is to be removed as well as any access constraints which may impact on the works described below C Note: - It should be noted that there are directly attached neighbouring occupied properties on all sides of the proposed work area; the contractor is deemed to have included for any additional costs arising from this constraint PROPPING AND TEMPORARY WORKS Propping and Temporary Works The contractor should include here for all propping and temporary works required to facilitate all demolitions as outlined on the Engineers Drawings and Specifications; the contractor should include for all temporary works as outlined on the engineers drawings and specifications including any temporary works required to sections of existing suspended floors or roofs being retained and any additional works required to safely complete the removal works described below; include for issuing temporary works design to the Engineer for approval prior to completion of works D See Engineers Drawing T4988-S003				
	Note			
	Note			
	Note			
	item	1		
Carrolls Talbot Street BQ/77				To Collection €

(- -) Demolitions Ground Floor Retail (Cont)

(Cont) Propping and Temporary Works

**DEMOLITION OF LOAD BEARING WALL BETWEEN
GROUND FLOOR RETAIL AND EXISTING SHOP**

Demolition of Load Bearing Wall

Carefully demolish existing 700mm thick brick and stonework original load bearing party wall; include for carefully divorcing from sections of existing structures being retained and making good as necessary; include for removal of all demolished material from site; include for any sundry propping or health and safety requirements; the contractors attention is particularly drawn to the temporary works drawings and specifications as prepared by the project Engineer

A 10600mm long x 3800mm high x 700mm thick

item

1

**DEMOLITION OF NON LOAD BEARING WALL
BETWEEN GROUND FLOOR RETAIL AND EXISTING
SHOP**

Demolition of Non Load Bearing Wall

Carefully take down and remove from site existing stud partition party wall between existing shop and retail space 2; consisting of timber studwork lined in timber and plasterboard sheeting; 100mm thick approximately; include for removal of any sundry timberwork or boxing; include for carefully divorcing from any structures being retained and making good as necessary; include for removal of all demolished material from site

B 11000mm long x 3800mm high x 100mm thick

item

1

(- -) Demolitions Ground Floor Retail (Cont) (Cont) Demolition of Non Load Bearing Wall FORMING OPENINGS BETWEEN GROUND FLOOR RETAIL AND GALLERY BUILDING Openings to Gallery Building Form openings through existing 600mm thick originally external wall of existing gallery building; include for for saw cutting and breaking out sections of wall as required; include for propping as required; include for all temporary works required; include for removing all demolished material from site; opening is to be supported by proposed structural steel beams; include for all preparatory works required to facilitate insertion of structural steelwork (structural steelwork e.m.)				
A	1710mm wide x 2065mm high	item	1	
B	1910mm wide x 3000mm high	item	1	
REMOVAL OF CAST CONCRETE STAIRCASE (STAIRCASE 1) Balustrade and Handrail Take down and remove from site existing mild steel balustrade and handrail to existing cast concrete staircase				
C	1200mm high	m	12	
Cast Concrete Stairs Break out and remove from site existing cast concrete stairs; assumed reinforced concrete; include for divorcing from existing walls being retained and making good walls as necessary on completion				
D	Consisting of two flights and a half landing 1000mm wide; first flight 9 steps; half landing 2000mm x 1000mm; second flight 7 steps	item	1	
Carrolls Talbot Street			To Collection €	
BQ/79				

<u>(- -) Demolitions Ground Floor Retail (Cont)</u>				
<u>Removal of Supporting Blockwork</u>				
<u>Carefully demolish existing 215mm thick solid concrete blockwork supporting walls and dispose off site; include for carefully divorcing from external walls being retained and making good as necessary</u>				
A	215mm thick within staircase 1	m2	9	
<u>Double Doors</u>				
<u>Take out and remove from site existing steel door and associated frame and ironmongery; leave opening ready to receive new internal door</u>				
B	1800mm wide x 2200mm high	Nr	2	
FORMING OPENINGS IN EXTERNAL WALL AT STAIRCORE 1				
<u>External Opening to Proposed Switch Room</u>				
<u>Form openings through existing 300mm thick external wall of staircore 1; include for for saw cutting and breaking out sections of wall as required; include for propping as required; include for all temporary works required; include for removing all demolished material from site; opening is to be supported by proposed structural steel beams; include for all preparatory works required to facilitate insertion of structural steelwork (structural steelwork e.m.)</u>				
C	1740mm wide x 2100mm high	item	1	

(- -) Demolitions Ground Floor Retail (Cont) (Cont) External Opening to Proposed Switch Room REMOVAL OF EXISTING FLOOR SLAB Breaking up Floor Slab Break up and remove from site existing assumed 220mm thick reinforced concrete ground bearing slab; include for removing any associated insulation or damp proof membraines; excavate through sub base to formation level; total depth of excavation assumed 350mm to formation level pending site inspection; include for removal of all demolished and excavated material from site				
A	Total depth concrete and sub base 550mm thick	m2	465	
B	extra over the above for carefully removing slab and fill around existing foundation structures; the contractors attention is drawn to the engineers foundation plan which outlines the extent of existing foundation and structure; the contractors attention is also particularly drawn to a structural steel underground membrane spanning the width of the existing retail unit	item	1	
C	extra over the above for testing of fill removed from around existing foul drainage and disposal to safe site as required	item	1	
REMOVAL OF EXISTING FOUL DRAINAGE LINE Removal of Existing Drainage				
D	Grub up existing clay foul drainage line and dispose off site; include for removing any associated manholes, AJ's etc; include for sequencing removal to ensure drain remains live to existing restaurant above	item	1	

<u>(- -) Demolitions Ground Floor Retail (Cont)</u>				
<u>(Cont) Removal of Existing Drainage</u>				
PROVISIONAL SUM				
<u>Provisional Sum</u>				
A	Include a Provisional Sum of €2,500.00 for sundry additional demolitions which may be required		1	
ADDITIONAL ITEMS				
B	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	

(- -) Demolitions Ground Floor Retail (Cont)				
COLLECTION Page No. BQ/77 Page No. BQ/78 Page No. BQ/79 Page No. BQ/80 Page No. BQ/81 Page No. BQ/82 (- -) Demolitions Ground Floor Retail Carried to Summary				
Carrolls Talbot Street				
BQ/83				

(- -) Demolitions Cinema Space				
NOTES				
A	Note: - The contractor should note that all works described take place at first floor level of an existing building on a busy pedestrian and vehicular street; the contractor is deemed to have included for any additional costs arising from this constraint	Note		
B	Note: - Any additional works required to remove demolished material from site are deemed to be included within the rates below; the contractor is deemed to have visited the site to ascertain the method by which demolished material is to be removed as well as any access constraints which may impact on the works described below	Note		
C	Note: - It should be noted that there are directly attached neighbouring occupied properties on all sides of the proposed work area; the contractor is deemed to have included for any additional costs arising from this constraint	Note		
PROPPING AND TEMPORARY WORKS				
<u>Propping and Temporary Works</u>				
<u>The contractor should include here for all propping and temporary works required to facilitate all demolitions as outlined on the Engineers Drawings and Specifications; the contractor should include for all temporary works as outlined on the engineers drawings and specifications including any temporary works required to sections of existing suspended floors or roofs being retained and any additional works required to safely complete the removal works described below; include for issuing temporary works design to the Engineer for approval prior to completion of works</u>				
D	See Engineers Drawing T4988-S003 to S004	item	1	
Carrolls Talbot Street				To Collection €
BQ/84				

(- -) Demolitions Cinema Space (Cont) (Cont) Propping and Temporary Works DEMOLITION OF STAGE AND PARTY WALL AT STAGE Demolish Raised Concrete Stage Carefully demolish existing concrete raised stage area and dispose off site; assumed solid concrete for the purpose of pricing; include for carefully protecting internal face of existing external walls and divorcing from same; include for making good as necessary				
A	10300mm long x 2300mm wide x 500mm thick	item	1	
B	Break out and remove from site set of 4nr steps to raised stage area in solid concrete 1100mm wide x 1200mm deep x 500mm thick	item	1	
C	extra over the above for forming crash deck under composed of timber propping and reinforced timber decking to engineer specification	m2	74	
Demolish Party Wall at Stage Carefully demolish existing solid blockwork party wall at face of stage; consisting of 300mm thick solid concrete blockwork lined both sides with timber battens and plasterboard; include for carefully divorcing from existing feature ceiling being retained and making good as necessary; include for carefully divorcing from external walls being retained and making good as necessary; include for removing all demolished material from site; include for any sundry propping, temporary works or health and safety required				
D	10500mm long x 4500mm high	item	1	

Carrolls
Talbot Street

(- -) Demolitions Cinema Space (Cont) Removing Roof Remove existing flat roof entirely consisting of felted roof finish; on plywood, insulation and roof joists and bridging; include for carefully protecting any structures adjacent being retained and removing all demolished material from site; the contractor should particularly note that the existing escape route from the restaurant adjacent is to be maintained for the duration of the works				
A	Flat roof area	m2	65	
B	extra for removal of associated rooflights 1200mm x 1200mm	Nr	4	
C	extra for removal of associated rooflights 1200mm x 1600mm	Nr	1	
Removing Existing Partition Lining to External Walls Carefully demolish existing insulated timber stud partition lining to external walls; consisting of timber studs inside blockwork with inuslation to cavity and any sundry support timbers; dispose of all demolished material from site; include for carefully divorcing from existing structures adjacent being retained				
D	100mm thick	m2	98	
Demolishing Blockwork External Walls Demolish existing 215mm thick solid concrete blockwork external walls and remove demolished material from site; include for carefully divorcing from existing structures being retained and making good as necessary; include for any works required to protect external escape routes for the duration of the works and from debris during demolitions; include for maintaining that escape route for the duration of the works				
E	215mm thick blockwork external walls	m2	44	
F	extra over the above for precast concrete capping	m	15	
Carrolls Talbot Street			To Collection €	
BQ/87				

(- -) Demolitions Cinema Space (Cont) (Cont) Demolishing Blockwork External Walls DEMOLITIONS AT STAIRCASE 1 Forming Splash Decks Forming crash deck under areas of suspended floor proposed to be removed; crash deck to be composed of timber propping and reinforced timber decking to engineer specification; include for stripping and removing from site on completion; include for preparation of temporary works design and submission of same to engineer prior to erection AFirst floor staircase 1 Removing Sections of Floor Slabs Break out sections of existing reinforced concrete floor slab 170mm thick and remove from site; include for forming clean straight saw cut junctions with sections of slab being retained; include for carefully protecting existing sections of walls and floors adjacent being retained and making good as necessary BFirst floor staircase 1 Demolition of Concrete Steps to Cinema Slab Level Break out and remove from site set of 6nr steps to cinema area in solid concrete; include for carefully divorcing from sections of external wall being retained and making good as necessary C2200mm wide x 1400mm deep x 900mm thick Protection of Existing Structural Steelwork DInclude for the protection of all retained existing structural steel beams and columns for the duration of the works described above; any damage to steelwork will be made good at the contractors expense				
	m2	11		
	m2	11		
	item	1		
	item	1		
Carrolls Talbot Street			To Collection €	
BQ/88				

(- -) Demolitions Cinema Space (Cont) Removing Roof Remove existing flat roof entirely consisting of felted roof finish; on plywood, insulation and roof joists and bridging; include for carefully protecting any structures adjacent being retained and removing all demolished material from site; the contractor should particularly note that the existing escape route from the restaurant adjacent is to be maintained for the duration of the works				
A	Flat roof area	m2	11	
Removing Steel Plant Remove existing structural plant in ceiling space of stairwell one and protruding through external wall; the contractor is deemed to have visited site to ascertain the quantum associated with the removal of this piece of equipment; include for infilling any openings left in existing external walls following removal				
B	Historic plant item	item	1	
REMOVING SECTIONS OF EXISTING CONCRETE SUSPENDED FLOOR Forming Splash Decks Forming crash deck under areas of suspended floor proposed to be removed; crash deck to be composed of timber propping and reinforced timber decking to engineer specification; include for stripping and removing from site on completion; include for preparation of temporary works design and submission of same to engineer prior to erection				
C	Within Cinema Area	m2	50	
Carrolls Talbot Street			To Collection €	
BQ/89				

(- -) Demolitions Cinema Space (Cont) Removing Sections of Floor Slabs Break out sections of existing reinforced concrete floor slab 170mm thick and remove from site; include for forming clean straight saw cut junctions with sections of slab being retained; include for carefully protecting existing sections of walls and floors adjacent being retained and making good as necessary A To rear of proposed cinema for stairwell and lift shaft m2 50 Protection of Existing Structural Steelwork B Include for the protection of all retained existing structural steel beams and columns for the duration of the works described above; any damage to steelwork will be made good at the contractors expense item 1 SUNDRY DEMOLITIONS Removing Timber Infill at Opening in Existing Suspended Floor Remove existing timber infill to opening in existing suspended floor within cinema area; include for stripping sheeting at floor level and ceiling level below; removal of any associated supporting timber and leaving opening ready to receive new concrete infill; include for removal of all demolished material from site C 4300mm x 1600mm item 1 Temporary Handrail Form temporary stud partition handrail around opening and remove once ope has been infilled; consisting of timber stud with head and base rail and studs @ 200m centres D 1200mm high m 13				
Carrolls Talbot Street BQ/90				To Collection €

(- -) Demolitions Cinema Space (Cont) (Cont) Temporary Handrail FORMING OPENINGS TO GALLERY BUILDING Openings to Gallery Building Form openings through existing 600mm thick originally external wall of existing gallery building; include for for saw cutting and breaking out sections of wall as required; include for propping as required; include for all temporary works required; include for removing all demolished material from site; opening is to be supported by proposed structural steel beams; include for all preparatory works required to facilitate insertion of structural steelwork (structural steelwork e.m.)				
A	1710mm wide x 2065mm high	item	1	
PROVISIONAL SUM Provisional Sum				
B	Include a Provisional Sum of €2,500.00 for sundry additional demolitions which may be required		1	
ADDITIONAL ITEMS				
C	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	
Carrolls Talbot Street			To Collection €	
BQ/91				

Carrolls
Talbot Street

(- -) Demolitions Gallery Building				
NOTES				
A	Note: - The contractor should note that all works described take place over multiple floors from basement to third floor level on a busy pedestrian and vehicular street; the contractor is deemed to have included for any additional costs arising from this constraint	Note		
B	Note: - Any additional works required to remove demolished material from site are deemed to be included within the rates below; the contractor is deemed to have visited the site to ascertain the method by which demolished material is to be removed as well as any access constraints which may impact on the works described below	Note		
C	Note: - It should be noted that there are directly attached neighbouring occupied properties on all sides of the proposed work area; the contractor is deemed to have included for any additional costs arising from this constraint	Note		
PROPPING AND TEMPORARY WORKS				
Propping and Temporary Works				
The contractor should include here for all propping and temporary works required to facilitate all demolitions as outlined on the Engineers Drawings and Specifications; the contractor should include for all temporary works as outlined on the engineers drawings and specifications including any temporary works required to sections of existing suspended floors or roofs being retained and any additional works required to safely complete the removal works described below; include for issuing temporary works design to the Engineer for approval prior to completion of works; temporary works designer to carry PI at levels indicated in specifications				
D	See Engineers Drawings T4988-S002 to S005	item	1	
Carrolls Talbot Street				To Collection €
BQ/93				

<u>(- -) Demolitions Gallery Building (Cont)</u>				
<u>(Cont) Propping and Temporary Works</u>				
DEMOLITION OF INTERNAL SOLID WALLS				
<u>Demolish Blockwork Internal Walls</u>				
<u>Demolish existing solid concrete blockwork internal walls and dispose of demolished material from site; include for carefully divorcing from any existing structures being retained and making good as necessary</u>				
215mm thick at basement level	m2	9		
215mm thick at ground floor level	m2	21		
215mm thick at first floor level	m2	9		
215mm thick at second floor level	m2	21		
215mm thick at third floor level	m2	9		
REMOVAL OF EXISTING STAIRCASES				
<u>Removing Existing Concrete Staircases</u>				
<u>Demolish existing concrete staircases assumed solid reinforced concrete including any associated supporting structures; include for carefully divorcing from internal face of external walls being retained and making good as necessary; include for removal of all demolished material from site</u>				
Basement to Ground Floor				
Staircase 1000mm wide consisting of two flights and one half landing; first flight 7 steps; half landing 2200mm x 1000mm; second flight 7 steps	item	1		
extra over the above for removing and disposing of temporary timber balustrading 1200mm high	item	1		
Carrolls Talbot Street			To Collection €	
BQ/94				

<u>(- -) Demolitions Gallery Building (Cont)</u>				
(Cont)	Removing	Existing	Concrete	
<u>Staircases</u>				
(Cont)	Demolish	existing	concrete	
staircases	assumed	solid	reinforced	
concrete	including	any	associated	
supporting	structures;	include	for	
<u>carefully divorcing from internal face of</u>				
<u>external walls being retained and making</u>				
<u>good as necessary; include for removal of</u>				
<u>all demolished material from site</u>				
Ground Floor to First Floor				
Staircase 1000mm wide consisting of two flights and one half landing; first flight 7 steps; half landing 2200mm x 1000mm; second flight 7 steps				
	item		1	
extra over the above for removing and disposing of temporary timber balustrading 1200mm high				
	item		1	
First Floor to Second Floor				
Staircase 1000mm wide consisting of two flights and one half landing; first flight 7 steps; half landing 2200mm x 1000mm; second flight 7 steps				
	item		1	
extra over the above for removing and disposing of temporary timber balustrading 1200mm high				
	item		1	
Second Floor to Third Floor				
Staircase 1000mm wide consisting of two flights and one half landing; first flight 7 steps; half landing 2200mm x 1000mm; second flight 7 steps				
	item		1	
extra over the above for removing and disposing of temporary timber balustrading 1200mm high				
	item		1	

(- -) Demolitions Gallery Building (Cont) (Cont) Removing Existing Concrete Staircases REMOVAL OF GROUND BEARING SLAB Breaking up Floor Slab Break up and remove from site existing assumed 300mm thick reinforced concrete ground bearing slab; include for removing any associated insulation or damp proof membraines; excavate through sub base to formation level; total depth of excavation assumed 350mm to formation level pending site inspection; include for removal of all demolished and excavated material from site				
A	Total depth concrete and sub base 650mm thick	m2	86	
B	allow for continious dewatering during construction process discharging to nearest surface water manhole; include for apply and procuring any permits necessary for same	item	1	
REMOVAL OF SUSPENDED SLABS Temporary Works Associated Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details				
C	Fabricated members; provisionally included as per engineers drawings to prop external walls of gallery during floor removals			
Columns				
D	Columns; member profile 25-50kg/m (152 x 152 UC44) - C9	tonne	0.44	

<u>(- -) Demolitions Gallery Building (Cont)</u>				
<u>(Cont) Temporary Works Associated</u>				
<u>(Cont) Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details</u>				
Beams				
A	PFC; member profile 25-50kg/m (PFC - 200 x 90 30kg/m) - B10	tonne	4.56	
B	Beams; member profile 50-100kg/m (203 x 203 UC52) - B3	tonne	1.25	
C	Beams; member profile 50-100kg/m (203 x 203 UC60) - B12	tonne	1.8	
D	Beams; member profile 25-50kg/m (152 x 152 UC44) - C9	tonne	0.33	
E	Beams; member profile 25-50kg/m (203 x 203 UC46) - C3	tonne	0.7	
Provisional Sum				
F	Include a Provisional Sum of €5,000.00 for sundry additional steelwork which may be specified	item	1	
<u>Sundries</u>				
Holding down assemblies				
G	450mm x 450mm x 25mm S275 baseplate; 8 FW full profile; include 4 Nr M20 grade 8.80 holding down bolts x 400mm long (galvanised) and associated washers; include tapered sleeves; include 150 x 150 x 12mm RSA anchor plates with 50mm void former; all as shown on Engineers Drawing 2000/B01 P2	nr	4	
Grouting; non shrink grout 40N/mm2; as per Engineers specification				
H	holding down bolts; 100 diameter x 400 long	nr	16	

<u>(- -) Demolitions Gallery Building (Cont)</u>				
<u>(Cont) Temporary Works Associated</u>				
<u>(Cont) Sundries</u>				
A	baseplates; 25mm thick; under 450 x 450 plate	nr	4	
Sundries				
B	drilling/forming holes in reinforced concrete to facilitate insertion of bolts	nr	16	
C	drilling holes in steel plate to facilitate insertion of bolts	nr	16	
Erection of all the foregoing steelwork				
D	generally	item	1	
<u>Preparing; Blast clean all steelwork to preparation grade SA 2.5 to ISO 8501-01. Remove all traces of loose rust, grit, etc by compressed air hose, inspect for laminations and remove by careful grinding leaving a smooth surface; Pre fabrication apply one coat of zinc rich blast primer to a minimum DFT of 25 microns; Post fabrication apply one coat of zinc rich site holding primer to a minimum DFT of 75 microns (125 microns where intumescent coat is to be applied); apply one coat of intumescent paint, where required, for fire resistance periods as specified on drawings; touch up damaged surfaces and fixings after erection; cosmetic painting to Architects Specification; all work to comply with BS5493 and paint manufacturer's instructions ; all in accordance with the Structural Engineers drawings and specification</u>				
Protective coatings				
E	general surfaces	tonne	9.08	

(- -) Demolitions Gallery Building (Cont) Additional Temporary Works AThe contractor should include here for any other propping or temporary works required to facilitate the removal of floors and temporary propping of the gallery building; the contractor should include for all temporary works as outlined on the engineers drawings and specifications including any temporary works required to sections of existing suspended floors or roofs being retained and any additional works or sequencing costs required to safely complete the removal works described in this element; include for issuing temporary works design and detailed method statement to the Engineer for approval prior to completion of works; temporary works designer to carry PI at levels indicated in specifications Removing Sections of Suspended Floor Slabs Demolish existing suspended concrete floor slabs in solid reinforced concrete 170mm thick; include for carefully divorcing from existing external walls being retained and making good as necessary; include for preparing temporary works proposals and method statements and issuing same to engineer and PSDP for review and approval prior to actioning works on site; include for removing all demolished material from site; the contractor is deemed to have visited the site and consulted with a temporary works engineer prior to pricing this item to ascertain a safe desired sequence for the execution of the works described Ground Floor B170mm thick suspended concrete floor forming first level First Floor C170mm thick suspended concrete floor forming second level				
	item	1		
	m2	82		
	m2	82		
Carrolls Talbot Street BQ/99				To Collection €

(- -) Demolitions Gallery Building (Cont) (Cont) Removing Sections of Suspended Floor Slabs (Cont) Demolish existing suspended concrete floor slabs in solid reinforced concrete 170mm thick; include for carefully divorcing from existing external walls being retained and making good as necessary; include for preparing temporary works proposals and method statements and issuing same to engineer and PSDP for review and approval prior to actioning works on site; include for removing all demolished material from site; the contractor is deemed to have visited the site and consulted with a temporary works engineer prior to pricing this item to ascertain a safe desired sequence for the execution of the works described Second Floor A170mm thick suspended concrete floor forming third level Third Floor B170mm thick suspended concrete floor forming fourth level				
	m2	82		
	m2	82		
Carrolls Talbot Street				To Collection €
BQ/100				

(- -) Demolitions Gallery Building (Cont) Removing Structural Steel Framework Supporting Same Remove and dispose off site existing structural steel columns and beams supporting suspended concrete floors generally; include for any propping or temporary works required; include for sequencing in line with a safe method statement; include for carefully divorcing any interactions with internal face of external walls being retained and making good as necessary; the contractor is deemed to have visited the site to ascertain the specific size and type of beams and columns to be removed Ground Floor A Columns 203 x 133 UB; 2300mm high; including associated holding down assemblies; include for removing any concrete required to access holding down assemblies or bolted connections B Beams 8000mm long; include for removing any concrete required to access bolted connections First Floor C Columns 203 x 133 UB; 2300mm high; including associated holding down assemblies; include for removing any concrete required to access holding down assemblies or bolted connections D Beams 8000mm long; include for removing any concrete required to access bolted connections Second Floor E Columns 203 x 133 UB; 2300mm high; including associated holding down assemblies; include for removing any concrete required to access holding down assemblies or bolted connections F Beams 8000mm long; include for removing any concrete required to access bolted connections								
					Nr	6		
					Nr	3		
					Nr	8		
					Nr	4		
					Nr	8		
					Nr	4		
Carrolls					To Collection €			
Talbot Street					BQ/101			

Carrolls
Talbot Street

<u>(- -) Demolitions Gallery Building (Cont)</u>				
COLLECTION				
Page No. BQ/93				
Page No. BQ/94				
Page No. BQ/95				
Page No. BQ/96				
Page No. BQ/97				
Page No. BQ/98				
Page No. BQ/99				
Page No. BQ/100				
Page No. BQ/101				
Page No. BQ/102				
(- -) Demolitions Gallery Building Carried to Summary				
Carrolls Talbot Street				BQ/103

(19) Substructure				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
E	Note: - All quantities measured in this element are provisional	Note		
Carrolls Talbot Street			To Collection €	
BQ/104				

(19) Substructure (Cont)				
(Cont) NOTES				
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note		
B	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below	Note		
EXCAVATION AND EARTHWORK				
EXCAVATION				
Excavation				
Foundation trenches; starting from reduced ground level				
C	less than or equal to 2.00m deep (Strip foundations)	m3	39	
D	less than or equal to 2.00m deep (Pad Foundations)	m3	29	
Extra over all excavation items for the following: -				
E	excavating below ground water level	m3	20	
F	breaking up existing rock	m3	10	
Carrolls Talbot Street			To Collection €	
BQ/105				

(19) Substructure (Cont)				
(Cont) EXCAVATION AND EARTHWORK				
(Cont) EXCAVATION				
(Cont) Excavation				
All soft spots shall be immediately brought to the attention of the Engineer. The amount to be excavated shall be agreed with the Engineer and the Contractor shall furnish to the Engineer at the end of each week an accurate sketch of each softspot excavated during the week. Each sketch shall show the average plan dimensions, commencement level and depth, and shall be approved and signed by the Engineer				
A	Excavate soft spots (irrespective of depth); dispose of excavated material off site; backfill and consolidate with 15N 20 leanmix concrete to the Engineers specification	m3	10	
Disposal				
Surface water				
B	keeping the surface of the site free of surface water	item	1	
Ground water				
C	keeping the excavations free of ground water	item	1	
Contaminated ground water				
D	keeping the excavations free of contaminated ground water	item	1	
Excavated material				
E	off site	m3	68	
FILLING				
Hardcore; SR21, in accordance with Engineer's specification; depositing and compacting in layers 150mm maximum thickness				
Filling; depositing in layers; compacting				
F	to excavations; average thickness exceeding 250mm	m3		
Carrolls Talbot Street			To Collection €	
BQ/106				

<u>(19) Substructure (Cont)</u>				
<u>(Cont) EXCAVATION AND EARTHWORK</u>				
<u>(Cont) FILLING</u>				
<u>(Cont) Hardcore; SR21, in accordance with Engineer's specification; depositing and compacting in layers 150mm maximum thickness</u>				
A	to make up levels; average thickness less than or equal to 250mm	m3	93	
<u>Surface treatments</u>				
Blinding filling				
B	levelling with sand of fine gravel; 50mm thick, T3; compacting	m2	550	
<u>CONCRETE WORK</u>				
<u>Information</u>				
C	For kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specification	note		
D	Power floated concrete floor slabs are to be finished to a sufficient level to obviate the necessity for the spreading of levelling compound for all floor coverings. The main contractor should consult with all floor subcontractors/ suppliers to obtain their requirements for finish of concrete surfaces prior to the concrete being poured.	note		
<u>IN SITU CONCRETE</u>				
<u>Grade C20/25 X0 lean mix concrete, as per Engineers specification</u>				
Blinding				
E	poured against earth or unblinded hardcore	m3	5	
<u>Reinforced in-situ concrete; Grade C28/35; as per Engineer's Specification; vibrated</u>				
Foundations				
F	Strip and pad foundations	m3	28	

(19) Substructure (Cont) (Cont) CONCRETE WORK (Cont) IN SITU CONCRETE Reinforced in-situ concrete; Grade C28/35, as per Engineer's Specification; vibrated; include for polyfibres at 9kg per m3 Beds; poured on or against earth or unblinded hardcore				
A	less than or equal to 150mm deep (Floor Slab)	m3	72	
B	450mm deep in gallery slab	m3	41	
SUNDRIES Designed Joints; all in accordance with Engineers Drawings Isolation joint in reinforced concrete floor slab; 20 x 12mm two part gun grade polysulphide sealant to B.S. 4254; 20x150mm deep "Aerofill" or other approved cork based joint filler board				
C	perimeter isolation joint; 150mm - 300mm deep; all in accordance with isolation joint detail described on Engineers Drawing	m	30	
Sawn Restraint Movement Joint; all in accordance with detail shown on Engineers Drawing				
D	5mm x 50mm formed saw cut	m	90	
REINFORCEMENT Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps Fabric				
E	horizontal; slab	m2	475	

<u>(19) Substructure (Cont)</u>				
<u>(Cont) CONCRETE WORK</u>				
<u>(Cont) REINFORCEMENT</u>				
<u>Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps</u>				
Fabric				
A	horizontal; foundations	m2	124	
<u>Reinforcement bars; of various diameter; deformed high yield steel to B.S. 4449 or 4461; spacers and chairs as necessary to support reinforcement in position, as specified by Engineer</u>				
Bars; straight and bent				
B	Greater than 12mm diameter (B20); Gallery Floor Slab	tonne	6.61	
C	less than or equal to 12mm diameter (B12); Provisional Additional Tie Bars	tonne	0.05	
FORMWORK (Note: - formwork has been measured to foundations but may not be required; no payment will be made if formwork is not used)				
<u>Formwork; generally as described in Engineer's specification</u>				
Sides of foundations				
D	250mm - 500mm	m	137	
Edges of beds				
E	not exceeding 250mm high	m	258	
F	extra for formwork as required at junction of suspended and ground bearing slabs in gallery building	item	1	

(19) Substructure (Cont)				
(Cont) CONCRETE WORK				
TANKING				
Preprufe 160 R waterproof membraine or similar approved waterproofing system to outside face of lift pit walls and underside of slab; all installed in accordance with Engineers Specification and manufacturers recommendations				
A	Under Basement Ground Bearing Slab	m2	90	
UNDERPINNING				
Temporary Support				
B	Provide all necessary temporary supports including propping and shoring to existing walls to which underpinning works are proposed in accordance with Engineers Drawings and Specification	item	1	
Preparation				
Removing existing projected reinforced concrete foundation and dispose material off site; access from one side only				
C	400mm wide x 300mm deep (Provisional)	m	22	
Excavation				
Preliminary excavation under and around existing structure; access from one side only; starting from existing ground level; including disposal of excavated material off site; strictly in sequence of underpinning schedule as illustrated on Engineers Drawing				
D	less than or equal to 2.00m deep	m3	33	
Working Space				
Working space; one side only; including excavation, disposal of excavated material from site and backfilling with hardcore to Engineer's specification				
E	to facilitate underpinning; less than or equal to 2.00m deep	m2	33	
Carrolls Talbot Street			To Collection €	
BQ/110				

(19) Substructure (Cont) (Cont) UNDERPINNING Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps Fabric Ahorizontal; foundations Reinforcement bars; of various diameter; deformed high yield steel to B.S. 4449 or 4461; spacers and chairs as necessary to support reinforcement in position, as specified by Engineer Bars; straight and bent Bless than or equal to 12mm diameter (B12) Underpinning Underpinning works to be carried out strictly in accordance with underpinning sequence illustrated on Engineers Drawing C500mm wide x 750mm deep in 950mm sections; C28/35 XC2 concrete, vibrated; placed over and including formwork as required; including connecting sequences together with 600mm H20 dowel bars at 0.20m centres; allow 48hrs between each section; include for packing last 100mm with kilsaran Kpro non shrink grout NSG2601-HF; all as per Engineers Drawings and specifications BRICKWORK AND BLOCKWORK BRICKWORK/BLOCKWORK Solid concrete loadbearing blockwork to I.S.20; compressive strength 7.5N/mm2; stretcher bond; bedded in cement and sand mortar (1:3) Walls in trenches D215mm thick				
	m2	21		
	tonne	0.21		
	m	22		
	m2	41		

<u>(19) Substructure (Cont)</u>				
<u>(Cont) BRICKWORK AND BLOCKWORK</u>				
<u>(Cont) BRICKWORK/BLOCKWORK</u>				
<u>(Cont) Solid concrete loadbearing blockwork to I.S.20; compressive strength 7.5N/mm2; stretcher bond; bedded in cement and sand mortar (1:3)</u>				
A	extra over for roadstone thermal lite soapbar blocks	m2	13	
Labours				
B	on blockwork	item	1	
Sundries				
C	like items; forming opes in 350mm thick rising walls including building in precast concrete lintels and making good as required to Engineers details; ope to accommodate 100mm diameter pipework	nr	10	
D	like items; weep holes; cathnic weep vents type WV; colour as specified by Architect	nr	10	
ANCILLARIES TO BRICKWORK/BLOCKWORK				
<u>Damp proof courses; Necoflex Easiload 0.5mm DPC; as per Architect's specification; 150mm lapped joints; welded in accordance with manufacturers instructions; bedding in cement, sand, lime, mortar (1:1:6); no allowance in measurement for laps</u>				
E	over 225mm wide	m2	29	
<u>ROOFING, CLADDING AND WATERPROOFING</u>				
MASTIC ASPHALT AND WATERPROOF NON-METAL FLEXIBLE SHEET COVERINGS				
<u>1000 gauge visqueen membrane, as described in the Architects Specification; laid strictly in accordance with the manufacturers instructions on blinded hardcore base; no allowance for laps</u>				
Vapour control layer				
F	horizontal; over 300mm wide	m2	550	

(19) Substructure (Cont) (Cont) ROOFING, CLADDING AND WATERPROOFING (Cont) MASTIC ASPHALT AND WATERPROOF NON-METAL FLEXIBLE SHEET COVERINGS 1200 gauge "Monarflex" RMD350 radon membrane, as described in the Architects Specification; laid strictly in accordance with the manufacturers instructions on blinded hardcore base; no allowance for laps Radon proofing A horizontal; over 300mm wide B vertical; not exceeding 300mm wide 150mm wide Tescon Air Tightness tape sealed to wall and floor with Arcon F or equivalent sealant; all installed in accordance with manufacturers recommendations and Architects Specification C vertical; not exceeding 300mm wide WOODWORK IRONMONGERY, ACCESSORIES AND SUNDRIES Kingspan TF70 insulation or similar approved; 150mm thick (laid in two 75mm thick layers); all laid strictly in accordance with manufacturer's instructions Thermal; underfloor D horizontal; over 300mm wide Kingspan TF70 high density insulation or similar approved; 45mm thick; all laid strictly in accordance with manufacturer's instructions Thermal; underfloor E vertical; 350mm high				
	m2	550		
	m	258		
	m	258		
	m2	550		
	m	258		
Carrolls Talbot Street BQ/113 To Collection €				

<u>(19) Substructure (Cont)</u>				
<u>RADON DRAINAGE</u>				
DRAINAGE BELOW GROUND				
<u>Monarflex Radon Sump complete and associated easi-cap; including all base supports as required; back fill all around with clean broken stone to engineer's specification; including all excavation and disposal off site</u>				
Radon sump				
A	internal size - 600mm wide x 600mm long x 225mm deep with and including 2 nr 110mm diameter openings	nr	2	
<u>uPVC pipes; I.S. 424; air tight welded joints in the running length</u>				
100mm pipework; laid in trenches				
B	laid in position	m	20	
C	Extra for capping vent pipes and labelling at footpath level	nr	2	
<u>Sundries</u>				
Sealing pipes				
D	sealing pipes with proprietary radon seals when penetrating radon barrier	nr	2	
<u>Testing and comissioning</u>				
Testing				
E	testing the radon drainage system to the Architect's satisfaction as the work proceeds and on completion	item	1	

(19) Substructure (Cont) (Cont) RADON DRAINAGE LEVELLING FLOORS GENERALLY 3mm-15mm self levelling compound to existing floor area as required prior to installation of floor finishes; Ardex or equal approved installed in accordance with manufacturers recommendations; include for preparing existing concrete floor as required for application				
A	under all floor finishes at floor slabs	m2	475	
ADDITIONAL ITEMS				
B	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	
Carrolls Talbot Street			To Collection €	
BQ/115				

<u>(19) Substructure (Cont)</u>					
COLLECTION					
Page No. BQ/104					
Page No. BQ/105					
Page No. BQ/106					
Page No. BQ/107					
Page No. BQ/108					
Page No. BQ/109					
Page No. BQ/110					
Page No. BQ/111					
Page No. BQ/112					
Page No. BQ/113					
Page No. BQ/114					
Page No. BQ/115					
(19) Substructure Carried to Summary					
Carrolls Talbot Street		BQ/116			

<u>(21) External Walls</u>				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/117				

(21) External Walls (Cont) (Cont) NOTES				
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note		
B				
	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below ALL OF THE FOLLOWING IN ALTERATIONS OF OPENINGS TO REAR ELEVATION CONCRETE WORK PRECAST CONCRETE <u>Prestressed, precast reinforced concrete lintols, standard units; spanlite or other approved; in accordance with Engineers Drawing and Specification</u> Lintels; 215mm wide x 65mm thick	Nr	10	
C	2450mm long			
D	1650mm long	Nr	2	
BRICKWORK AND BLOCKWORK BLOCKWORK (Altering Openings at Rear Elevation) <u>Solid concrete blocks; I.S. 20; minimum compressive strength 7N/mm2; nominal size 440 x 215mm; built in cement, lime, sand mortar, as described in the Engineer's specification</u> Walls				

(21) External Walls (Cont) (Cont) BRICKWORK AND BLOCKWORK (Cont) BLOCKWORK (Altering Openings at Rear Elevation) (Cont) Solid concrete blocks; I.S. 20; minimum compressive strength 7N/mm2; nominal size 440 x 215mm; built in cement, lime, sand mortar, as described in the Engineer's specification				
A	215mm thick infilling openings	m2	32	
	Labours			
B	on blockwork	item		
	Bonding to other work			
C	"Ancon" or similar approved wall starter system; Stainless steel, single flange, integral tie wall starter; include for drilling existing block wall with 10mm masonry bit avoiding mortar joints; include for plugging; include for screwing starter system to wall; include for weather seal approximately 10mm wide between the Starter and the existing wall	m	24	
	Damp proof courses; Ruberoid Hyload original as per Architect's specification; 150mm lapped joints; welded in accordance with manufacturers instructions; bedding in cement, sand, lime, mortar (1:1:6); no allowance in measurement for laps			
	On horizontal surfaces			
D	over 225mm wide	m2	4	
	ADDITIONAL ITEMS			
E	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	

(21) External Walls (Cont) COLLECTION Page No. BQ/117 Page No. BQ/118 Page No. BQ/119 (21) External Walls Carried to Summary				
Carrolls Talbot Street				BQ/120

(- -) Comms Room Superstructure and Sundries				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
F	Note: - All quantities measured in this element are provisional	Note		
Carrolls Talbot Street			To Collection €	
BQ/121				

(- -) Comms Room Superstructure and Sundries		(Cont)			
(Cont) NOTES					
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note			
B	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below	Note			
FORMING CONCRETE UPSTAND TO ROOF					
<u>IN SITU CONCRETE</u>					
<u>Reinforced in-situ concrete; Grade C30/37 XC3, as per Engineer's Specification; vibrated</u>					
Upstand Walls to Terrace					
C	Upstand to Roof	m3	3		
<u>REINFORCEMENT</u>					
<u>Reinforcement bars; of various diameter; deformed high yield steel to B.S. 4449 or 4461; spacers and chairs as necessary to support reinforcement in position, as specified by Engineer</u>					
D	less than or equal to 12mm diameter	tonne	0.45		
E	extra for tying reinforcing bars of upstand to reinforcing bars in cast concrete roof	item	1		

(- -) Comms Room Superstructure and Sundries		(Cont)			
A	FORMWORK Formwork; in WBP plywood and associated supporting timbers generally; as described in Engineer's specification Sides of Upstand 300mm high	m	61		
	EXTERNAL STUD PARTITIONS STUD PARTITIONS Structural timber stud partitions; 100 x 44mm vertical timber stud, as per Engineer's specification, at 300mm centres; 2nr 100 x 44mm sole and head plates fixed to timbers of existing roofs; 1nr rows of bridging ; 300mm thick "Isover" or equal approved quilt insulation packed between studs Partition, fixed to concrete roof upstand				
	External structural studs forming upstand extensions				
	BOARDING AND SECOND FIXINGS 18mm thick WBP plywood decking in accordance with Engineers specification Boarding and sheeting fixed to stud partitions 12.50mm thick Knauf Aquapanel exterior cement board fixed to timber stud partitions on Tyvek breather membrane to manufacturers recommendations; all installed in accordance with Architects Specification and manufacturers recommendations				
D	Face of Upstands over 300mm girth	m2	24		

(- -) Comms Room Superstructure and Sundries (Cont)				
FLEXIBLE SHEET METAL COVERING Aluminium capping by "Alupress" or similar approved; to be delivered to site powder coated in lengths to be agreed prior to fabrication; powder coated in RAL colours to match windows; Capping fixed and sealed to solid block parapet wall in accordance with manufacturers instructions; all edges to be prepared and protected with edge protection lacquer, all work to be in accordance with manufacturers instructions and to include ends, filled ends, angles and intersections as necessary: Parapet Capping A 450-600mm girth; bends -4; fixed to top of parapet wall				
	m	13		

(- -) Comms Room Superstructure and Sundries (Cont)				
(Cont) FLEXIBLE SHEET METAL COVERING				
EXTERNAL WALLS				
RIGID SHEET COVERINGS AND DECKING				
Coverings; Quadcore KS1000RW insulated wall panels by Kingspan Ltd 80mm thick insulation core thickness (overall thickness 111mm) include for factory applied weather seals, Insulation core consisting of 80mm thick rigid Kingspan insulation board; external finish of hot dip zinc/aluminium galfan coated metal to BS EN 10346: 2015 in Kingspan Spectrum semigloss finish, to colour as specified by Architect; internal panel finished in hot dipped zinc coated steel to BS EN 10346: 2009 with Kingspan Cleansafe 15 coating; Horizontal rebated tounge and groove panel joints with factory applied weather seal set in rebate, PIR insulation board with gaps filled with fire rated cannister inuslation site applied at end of each panel where flashings pass over joints & at panel ends; Vertical Joints , 20mm wide, including VJ1 EPDM self adhesive air seal bubble gasket; 60mm x 10mm applied to vertical cladding rails and lapped over drip flashing; all vertical joints filled with canister applied PIR insulation to fill any gaps and maintain insulation continuity; vertical joint finished with push in EDPM gasket; All panels fixed to steel frame with vertical & horizontal cladding rails (cladding rails e.m.) with Quadcore suitable fixings in steel or carbon steel; include all necessary rubber sealant, silicone sealant, top hat clips, fixings, flashings, snap on flashings, EPDM isolation tape, cover caps, profiled fillers, anti- condensation tape, fasteners, sealant tape and sealing, air seals etc.; all in accordance with manufacturers details and instructions and with Architects specification Panels Coverings; fixed horizontally to walls exceeding 300mm		m2	59	

(- -) Comms Room Superstructure and Sundries		(Cont)		
A	(Cont) RIGID SHEET COVERINGS AND DECKING (Cont) Coverings; Quadcore KS1000RW insulated wall panels by Kingspan Ltd 80mm thick insulation core thickness (overall thickness 111mm) include for factory applied weather seals, Insulation core consisting of 80mm thick rigid Kingspan insulation board; external finish of hot dip zinc/aluminium galfan coated metal to BS EN 10346: 2015 in Kingspan Spectrum semigloss finish, to colour as specified by Architect; internal panel finished in hot dipped zinc coated steel to BS EN 10346: 2009 with Kingspan Cleansafe 15 coating; Horizontal rebated tounge and groove panel joints with factory applied weather seal set in rebate, PIR insulation board with gaps filled with fire rated cannister inuslation site applied at end of each panel where flashings pass over joints & at panel ends; Vertical Joints , 20mm wide, including VJ1 EPDM self adhesive air seal bubble gasket; 60mm x 10mm applied to vertical cladding rails and lapped over drip flashing; all vertical joints filled with canister applied PIR insulation to fill any gaps and maintain insulation continuity; vertical joint finished with push in EDPM gasket; All panels fixed to steel frame with vertical & horizontal cladding rails (cladding rails e.m.) with Quadcore suitable fixings in steel or carbon steel; include all necessary rubber sealant, silicone sealant, top hat clips, fixings, flashings, snap on flashings, EPDM isolation tape, cover caps, profiled fillers, anti- condensation tape, fasteners, sealant tape and sealing, air seals etc.; all in accordance with manufacturers details and instructions and with Architects specification Cladding Rails			
	Cladding rails; M265065 2.7mm gauge; 265mm deep; sections member profile not exceeding 10kg/m; bolted to cleats in accordance with manufacturers recommendations (cleats e.m.); to receive aluminium wall finish	m	195	

(- -) Comms Room Superstructure and Sundries		(Cont)		
(Cont) RIGID SHEET COVERINGS AND DECKING (Cont) Coverings; Quadcore KS1000RW insulated wall panels by Kingspan Ltd 80mm thick insulation core thickness (overall thickness 111mm) include for factory applied weather seals, Insulation core consisting of 80mm thick rigid Kingspan insulation board; external finish of hot dip zinc/aluminium galfan coated metal to BS EN 10346: 2015 in Kingspan Spectrum semigloss finish, to colour as specified by Architect; internal panel finished in hot dipped zinc coated steel to BS EN 10346: 2009 with Kingspan Cleansafe 15 coating; Horizontal rebated tounge and groove panel joints with factory applied weather seal set in rebate, PIR insulation board with gaps filled with fire rated cannister inuslation site applied at end of each panel where flashings pass over joints & at panel ends; Vertical Joints , 20mm wide, including VJ1 EPDM self adhesive air seal bubble gasket; 60mm x 10mm applied to vertical cladding rails and lapped over drip flashing; all vertical joints filled with canister applied PIR insulation to fill any gaps and maintain insulation continuity; vertical joint finished with push in EDPM gasket; All panels fixed to steel frame with vertical & horizontal cladding rails (cladding rails e.m.) with Quadcore suitable fixings in steel or carbon steel; include all necessary rubber sealant, silicone sealant, top hat clips, fixings, flashings, snap on flashings, EPDM isolation tape, cover caps, profiled fillers, anti- condensation tape, fasteners, sealant tape and sealing, air seals etc.; all in accordance with manufacturers details and instructions and with Architects specification (Cont) Cladding Rails				
A	extra over for cleats as specified by Engineer; bolted to structural steel in accordance with manufacturers recommendations	nr	150	

(- -) Comms Room Superstructure and Sundries (Cont)				
(Cont) RIGID SHEET COVERINGS AND DECKING (Cont) Coverings; Quadcore KS1000RW insulated wall panels by Kingspan Ltd 80mm thick insulation core thickness (overall thickness 111mm) include for factory applied weather seals, Insulation core consisting of 80mm thick rigid Kingspan insulation board; external finish of hot dip zinc/aluminium galfan coated metal to BS EN 10346: 2015 in Kingspan Spectrum semigloss finish, to colour as specified by Architect; internal panel finished in hot dipped zinc coated steel to BS EN 10346: 2009 with Kingspan Cleansafe 15 coating; Horizontal rebated tounge and groove panel joints with factory applied weather seal set in rebate, PIR insulation board with gaps filled with fire rated cannister inuslation site applied at end of each panel where flashings pass over joints & at panel ends; Vertical Joints , 20mm wide, including VJ1 EPDM self adhesive air seal bubble gasket; 60mm x 10mm applied to vertical cladding rails and lapped over drip flashing; all vertical joints filled with canister applied PIR insulation to fill any gaps and maintain insulation continuity; vertical joint finished with push in EDPM gasket; All panels fixed to steel frame with vertical & horizontal cladding rails (cladding rails e.m.) with Quadcore suitable fixings in steel or carbon steel; include all necessary rubber sealant, silicone sealant, top hat clips, fixings, flashings, snap on flashings, EPDM isolation tape, cover caps, profiled fillers, anti- condensation tape, fasteners, sealant tape and sealing, air seals etc.; all in accordance with manufacturers details and instructions and with Architects specification Flashings at Existing Structures				
Carrolls Talbot Street		BQ/128		To Collection €

(- -) Comms Room Superstructure and Sundries		(Cont)		
(Cont) RIGID SHEET COVERINGS AND DECKING (Cont) Coverings; Quadcore KS1000RW insulated wall panels by Kingspan Ltd 80mm thick insulation core thickness (overall thickness 111mm) include for factory applied weather seals, Insulation core consisting of 80mm thick rigid Kingspan insulation board; external finish of hot dip zinc/aluminium galfan coated metal to BS EN 10346: 2015 in Kingspan Spectrum semigloss finish, to colour as specified by Architect; internal panel finished in hot dipped zinc coated steel to BS EN 10346: 2009 with Kingspan Cleansafe 15 coating; Horizontal rebated tounge and groove panel joints with factory applied weather seal set in rebate, PIR insulation board with gaps filled with fire rated cannister inuslation site applied at end of each panel where flashings pass over joints & at panel ends; Vertical Joints , 20mm wide, including VJ1 EPDM self adhesive air seal bubble gasket; 60mm x 10mm applied to vertical cladding rails and lapped over drip flashing; all vertical joints filled with canister applied PIR insulation to fill any gaps and maintain insulation continuity; vertical joint finished with push in EDPM gasket; All panels fixed to steel frame with vertical & horizontal cladding rails (cladding rails e.m.) with Quadcore suitable fixings in steel or carbon steel; include all necessary rubber sealant, silicone sealant, top hat clips, fixings, flashings, snap on flashings, EPDM isolation tape, cover caps, profiled fillers, anti- condensation tape, fasteners, sealant tape and sealing, air seals etc.; all in accordance with manufacturers details and instructions and with Architects specification (Cont) Flashings at Existing Structures ^^^ Flashing junctions with existing structures to suit the above system; bends x 2; 450mm - 600mm girth; fixed in accordance with manufacturers instruction and recommendations including all fixings; include all necessary rubber sealant, silicone sealant, fixings, EPDM isolation tape, anti- condensation tape, fasteners, air seals, sealing with sealant tape etc; all in strict accordance with				
Carrolls Talbot Street		m	To Collection €	
BQ/129				
Carrolls Talbot Street			To Collection €	
BQ/129				

(- -) Comms Room Superstructure and Sundries		(Cont)		
A	(Cont) RIGID SHEET COVERINGS AND DECKING (Cont) Coverings; Quadcore KS1000RW insulated wall panels by Kingspan Ltd 80mm thick insulation core thickness (overall thickness 111mm) include for factory applied weather seals, Insulation core consisting of 80mm thick rigid Kingspan insulation board; external finish of hot dip zinc/aluminium galfan coated metal to BS EN 10346: 2015 in Kingspan Spectrum semigloss finish, to colour as specified by Architect; internal panel finished in hot dipped zinc coated steel to BS EN 10346: 2009 with Kingspan Cleansafe 15 coating; Horizontal rebated tounge and groove panel joints with factory applied weather seal set in rebate, PIR insulation board with gaps filled with fire rated cannister inuslation site applied at end of each panel where flashings pass over joints & at panel ends; Vertical Joints , 20mm wide, including VJ1 EPDM self adhesive air seal bubble gasket; 60mm x 10mm applied to vertical cladding rails and lapped over drip flashing; all vertical joints filled with canister applied PIR insulation to fill any gaps and maintain insulation continuity; vertical joint finished with push in EDPM gasket; All panels fixed to steel frame with vertical & horizontal cladding rails (cladding rails e.m.) with Quadcore suitable fixings in steel or carbon steel; include all necessary rubber sealant, silicone sealant, top hat clips, fixings, flashings, snap on flashings, EPDM isolation tape, cover caps, profiled fillers, anti- condensation tape, fasteners, sealant tape and sealing, air seals etc.; all in accordance with manufacturers details and instructions and with Architects specification Vertical angles			
	External Corner Detail to suit KS1000RW System; include all necessary rubber sealant, silicone sealant, fixings, EPDM isolation tape, anti- condensation tape, fasteners, air seals, sealing with sealant tape etc; all in strict accordance with manufacturers details and instructions	m	5	
Carrolls Talbot Street		BQ/130		To Collection €

(- -) Comms Room Superstructure and Sundries		(Cont)		
(Cont) RIGID SHEET COVERINGS AND DECKING (Cont) Coverings; Quadcore KS1000RW insulated wall panels by Kingspan Ltd 80mm thick insulation core thickness (overall thickness 111mm) include for factory applied weather seals, Insulation core consisting of 80mm thick rigid Kingspan insulation board; external finish of hot dip zinc/aluminium galfan coated metal to BS EN 10346: 2015 in Kingspan Spectrum semigloss finish, to colour as specified by Architect; internal panel finished in hot dipped zinc coated steel to BS EN 10346: 2009 with Kingspan Cleansafe 15 coating; Horizontal rebated tounge and groove panel joints with factory applied weather seal set in rebate, PIR insulation board with gaps filled with fire rated cannister inuslation site applied at end of each panel where flashings pass over joints & at panel ends; Vertical Joints , 20mm wide, including VJ1 EPDM self adhesive air seal bubble gasket; 60mm x 10mm applied to vertical cladding rails and lapped over drip flashing; all vertical joints filled with canister applied PIR insulation to fill any gaps and maintain insulation continuity; vertical joint finished with push in EDPM gasket; All panels fixed to steel frame with vertical & horizontal cladding rails (cladding rails e.m.) with Quadcore suitable fixings in steel or carbon steel; include all necessary rubber sealant, silicone sealant, top hat clips, fixings, flashings, snap on flashings, EPDM isolation tape, cover caps, profiled fillers, anti- condensation tape, fasteners, sealant tape and sealing, air seals etc.; all in accordance with manufacturers details and instructions and with Architects specification Provisional Sum				
A	Include a Provisional Sum of €2,000.00 for sundry structure required to extended section of roof upstand to receive cladding rails		1	
Carrolls Talbot Street		BQ/131		To Collection €

<u>(- -) Comms Room Superstructure and Sundries (Cont)</u>				
<u>(Cont) RIGID SHEET COVERINGS AND DECKING</u>				
INSTALLING NEW SECTION OF HANDRAIL				
<u>New Section of Guardrail to Existing Walkway</u>				
Include for installation of a new guardrail to one side of existing steel walkway; include for any alterations required to existing walkway to facilitate installation; include for any fixings or additional support steels required; guard rail to consist of 50mm galvanised steel handrail; install on 50nmm galvanised steel posts at 1000mm centres; posts fitted to bottom rail; bottom rail fixed to underside of existing walkway; the contractor is deemed to have visited site to ascertain the make up of the existing walkway and to have included for any additional works required to facilitate installation of the proposed handrail				
A	1200mm high	m	10	
WORKS TO EXISTING ROOF COVERINGS				
<u>Cleaning Roofs Generally</u>				
Include here for thoroughly cleaning all roof finishes to provide visibility of existing condition generally; cleaning to be carried out in a manner so as to introduce as little water to the areas as possible to avoid ingress into units prior to repair works; include for disposal of any surplus waste arising off site				
B	Roof at Comms Room with Escape Walkway	m2	59	
C	Roof Behind Comms at Covered Area	m2	20	

(- -) Comms Room Superstructure and Sundries		(Cont)			
Forming Timber Uprand					
<u>Form timber upstand to existing roof structure to facilitate end of new replacement roof finishes; consisting of 100mm x 44mm C24 treated timbers and 18mm thick WBP plywood sheeting forming narrow shallow upstand fixed to existing timber roof structure</u>					
A	300mm wide x 300mm high	m	4		
<u>Tapered Insulation (Provisional)</u>					
<u>Kingspan Kooltherm K7 Tapered Insulation; tapered to falls to outlets as required; installed butt jointed and staggered as required over existing roof finishes to manufacturers recommendations; all installed in accordance with Architects Drawings and Specifications</u>					
B	150mm thick tapered to falls	m2	79		
C	extra over the above for forming insulation around existing raised sections of roof appearing to enclose old openings	item	1		
<u>New Sheeting Roof Finishes (Provisional)</u>					
<u>Single ply roofing system; Sarnafil G410-EL; 1.8mm thick; lead grey in colour; Install butt jointed and staggered, incorporating manufacturer approved insulated angle fillets at upstands and kerbs; on Sika S-Vap 5000E vapour control layer, sealed and detailed as required to insulation boards under; all in accordance with the manufacturers recommendations and Architects Drawings & Specification</u>					
To Rear of Comms					
D	Roof at Comms Room with Escape Walkway	m2	59		
E	extra over the above for forming insulation around existing raised sections of roof appearing to enclose old openings	item	1		

(- -) Comms Room Superstructure and Sundries		(Cont)			
(Cont) New Sheeting Roof Finishes (Provisional) (Cont) Single ply roofing system; Sarnafil G410-EL; 1.8mm thick; lead grey in colour; Install butt jointed and staggered, incorporating manufacturer approved insulated angle fillets at upstands and kerbs; on Sika S-Vap 5000E vapour control layer, sealed and detailed as required to insulation boards under; all in accordance with the manufacturers recommendations and Architects Drawings & Specification (Cont) To Rear of Comms					
A	Upstands to the above; installed in accordance with manufacturers recommendations	m	42		
To Side of Comms					
B	Roof Behind Comms at Covered Area	m2	20		
C	Upstands to the above; installed in accordance with manufacturers recommendations	m	21		
PLASTERED FINISH TO EXTERNAL FACE OF BLOCKWORK WALL					
New Plastered Finishes Sand and cement rendered finish; consisting of bonding coat; twop undercoats and one finishing coat of sand and cement render; undercoats to consist of 1:5-6 air entrained sulfate resisting cement:sand; first underocat to be 8-12mm thick, second undercoat to be 6-10mm thick; finish coat to consist of 1:4-5 Masonry sand:cement 5-8mm thick; plain smooth finish; all applied in accordance with manufacturers instructions and Architects Specification					
D	over 300mm girth	m2	10		

(- -) Comms Room Superstructure and Sundries		(Cont)		
<u>(Cont) New Plastered Finishes</u>				
MAINTAINING EXISTING FIRE ESCAPE ROUTES				
<u>Maintaining Fire Escape</u>				
A	The contractors attention is drawn to the existing fire escape walkway running through the works area of the items described below; this walkway is to be maintained as an active escape route for the duration of the works and any costs associated with achieving this should be included against this item	item	1	
PROVISIONAL SUM				
<u>Sundry Works to Roof Structures</u>				
B	Include a Provisional Sum of €5,000.00 for sundry works to existing roof structures to facilitate the works described above		1	
ADDITIONAL ITEMS				
C	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	
Carrolls Talbot Street		BQ/135		To Collection €

(- -) Comms Room Superstructure and Sundries (Cont)				
COLLECTION				
Page No. BQ/121				
Page No. BQ/122				
Page No. BQ/123				
Page No. BQ/124				
Page No. BQ/125				
Page No. BQ/126				
Page No. BQ/127				
Page No. BQ/128				
Page No. BQ/129				
Page No. BQ/130				
Page No. BQ/131				
Page No. BQ/132				
Page No. BQ/133				
Page No. BQ/134				
Page No. BQ/135				
(- -) Comms Room Superstructure and Sundries Carried to Summary				

<u>(22) Internal Walls</u>				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/137				

	(22) Internal Walls (Cont) (Cont) NOTES				
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note			
B	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below	Note			
	CONCRETE WORK PRECAST CONCRETE <u>Prestressed, precast reinforced concrete lintols, standard units; spanlite or other approved</u> Lintels 215mm x 65mm Ground Floor				
C	2850mm long	Nr	1		
D	1500mm long	Nr	2		
	First Floor				
E	1500mm long	Nr	1		
	Gallery Building				
F	1500mm long	Nr	4		
Carrolls Talbot Street BQ/138				To Collection €	

<u>(22) Internal Walls (Cont)</u>				
<u>BRICKWORK AND BLOCKWORK (PROVISIONAL)</u>				
BLOCKWORK				
<u>Solid concrete blocks; I.S. 20; minimum compressive strength 7N/mm2; nominal size 440 x 215mm; built in cement, lime, sand mortar, as described in the Engineer's specification</u>				
Walls				
A	215mm thick	m2	407	
B	extra over the above for forming concrete band beam 215mm x 215mm with 4nr B12 bars and links at 300mm centres; include for all concrete and formwork required and striking formwork on completion; include for any concrete pumps etc required to install a height of approximately 3000mm	m	13	
Labours				
C	on blockwork	item	1	
<u>Bonding to other work</u>				
D	"Ancon" or similar approved wall starter system; Stainless steel, single flange, integral tie wall starter; include for drilling existing block wall with 10mm masonry bit avoiding mortar joints; include for plugging; include for screwing starter system to wall; include for weather seal approximately 10mm wide between the Starter and the existing wall	m	71	
<u>Damp proof courses; Ruberoid Hyload original as per Architect's specification; 150mm lapped joints; welded in accordance with manufacturers instructions; bedding in cement, sand, lime, mortar (1:1:6); no allowance in measurement for laps</u>				
On horizontal surfaces				
E	over 225mm wide	m2	28	

(22) Internal Walls (Cont) (Cont) BRICKWORK AND BLOCKWORK (PROVISIONAL) ALTERATIONS TO OPENINGS Reducing Opening Block up existing double door opening 2200mm wide x 2200mm high to form new single door opening 1000mm wide x 2000mm high; include for 215mm thick blockwork, ancon wall starter kits as required and insertion of precast concrete lintel; leave opening ready for installation of door and frame set				
A	Altering to single door opening	Nr	1	
ADDITIONAL ITEMS				
B	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	
Carrolls Talbot Street			To Collection €	
BQ/140				

(22) Internal Walls (Cont) COLLECTION Page No. BQ/137 Page No. BQ/138 Page No. BQ/139 Page No. BQ/140 (22) Internal Walls Carried to Summary				
Carrolls Talbot Street				BQ/141

(23) Suspended Floors				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/142				

To Collection €

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK IN SITU CONCRETE Reinforced in-situ concrete; Grade C28/35; vibrated; in accordance with Engineers Concrete Specification; in suspended slab poured over profiled metal deck permanent formwork (metal deck elsewhere measured); slab to be poured at varying heights throughout a multi story building with intermediate floors; generally circa 3000mm high between floors with a total height from top floor to ground level of 9700mm; contractor is to include for any additional works associated with these constraints including any scaffolding, pumping, health and safety measures etc that may be required				
A	greater than 150mm thick	m3	43	
FORMWORK 60mm thick Comfloor 60 steel permanent formwork system; all as per engineers specifications; include for filler blocks as required; installed as per manufacturers instructions; installed on structural steel sub frame with fixings to manufacturers recommendations at a height of 3000mm from ground or intermediate floor level; contractor is to include for any additional works associated with these constraints; include for all propping required; the contractors attentions is drawn to the Comfloor 60 technical documentation				
B	Soffit of Slabs; Soffit height 2000mm to 4000mm from previous intermediate floor; contractors attention however is drawn to the multi floor level nature of the installation with a maximum height from ground level of 9700mm	m2	225	
C	Extra for Comfloor 60 edge trim detail; include for all fixings, restraint straps etc required; all installed in accordance with manufacturers recommendations	m	210	

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK REINFORCEMENT Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps Fabric Ahorizontal; slab ALL THE FOLLOWING IN SUSPENDED FLOOR TO REAR STAIRWELL CONCRETE WORK Information BFor kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specification IN SITU CONCRETE Reinforced in-situ concrete; Grade C28/35; vibrated; in accordance with Engineers Concrete Specification; in suspended slab poured over profiled metal deck permanent formwork (metal deck elsewhere measured); slab to be poured at varying heights throughout a multi story building with intermediate floors; generally circa 3000mm high between floors with a total height from top floor to ground level of 9700mm; contractor is to include for any additional works associated with these constraints including any scaffolding, pumping, health and safety measures etc that may be required Cgreater than 150mm thick				
	m2	225		
	note			
	m3	3		

<u>(23) Suspended Floors (Cont)</u>				
<u>(Cont) CONCRETE WORK</u>				
FORMWORK				
<u>60mm thick Comfloor 60 steel permanent formwork system; all as per engineers specifications; include for filler blocks as required; installed as per manufacturers instructions; installed on structural steel sub frame with fixings to manufacturers recommendations at a height of 3000mm from ground or intermediate floor level; contractor is to include for any additional works associated with these constraints; include for all propping required; the contractors attentions is drawn to the Comfloor 60 technical documentation</u>				
A	Soffit of Slabs; Soffit height 2000mm to 4000mm from previous intermediate floor; contractors attention however is drawn to the multi floor level nature of the installation with a maximum height from ground level of 9700mm	m2	12	
B	Extra for Comfloor 60 edge trim detail; include for all fixings, restraint straps etc required; all installed in accordance with manufacturers recommendations	m	20	
REINFORCEMENT				
<u>Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps</u>				
Fabric				
C	horizontal; slab	m2	12	

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK (Cont) REINFORCEMENT (Cont) Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps ALL THE FOLLOWING IN SUSPENDED FLOOR TO CINEMA AREA CONCRETE WORK Information AFor kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specification IN SITU CONCRETE Reinforced in-situ concrete; Grade C28/35; vibrated; in accordance with Engineers Concrete Specification; in suspended slab poured over profiled metal deck permanent formwork (metal deck elsewhere measured); slab to be poured at varying heights throughout a multi story building with intermediate floors; generally circa 3000mm high between floors with a total height from top floor to ground level of 9700mm; contractor is to include for any additional works associated with these constraints including any scaffolding, pumping, health and safety measures etc that may be required Bgreater than 150mm thick				
	note			
	m3	8		

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK FORMWORK 60mm thick Comfloor 60 steel permanent formwork system; all as per engineers specifications; include for filler blocks as required; installed as per manufacturers instructions; installed on structural steel sub frame with fixings to manufacturers recommendations at a height of 3000mm from ground or intermediate floor level; contractor is to include for any additional works associated with these constraints; include for all propping required; the contractors attentions is drawn to the Comfloor 60 technical documentation				
A	Soffit of Slabs; Soffit height 2000mm to 4000mm from previous intermediate floor; contractors attention however is drawn to the multi floor level nature of the installation with a maximum height from ground level of 9700mm	m2	39	
B	Extra for Comfloor 60 edge trim detail; include for all fixings, restraint straps etc required; all installed in accordance with manufacturers recommendations	m	37	
REINFORCEMENT Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps Fabric				
C	horizontal; slab	m2	39	

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK (Cont) REINFORCEMENT (Cont) Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps ALL THE FOLLOWING IN SUSPENDED FLOOR TO COMMS ROOM CONCRETE WORK Information AFor kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specification IN SITU CONCRETE Reinforced in-situ concrete; Grade C28/35; vibrated; in accordance with Engineers Concrete Specification; in suspended slab poured over profiled metal deck permanent formwork (metal deck elsewhere measured); slab to be poured at varying heights throughout a multi story building with intermediate floors; generally circa 3000mm high between floors with a total height from top floor to ground level of 9700mm; contractor is to include for any additional works associated with these constraints including any scaffolding, pumping, health and safety measures etc that may be required Bgreater than 150mm thick				
	note			
	m3	9		

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK FORMWORK 60mm thick Comfloor 60 steel permanent formwork system; all as per engineers specifications; include for filler blocks as required; installed as per manufacturers instructions; installed on structural steel sub frame with fixings to manufacturers recommendations at a height of 3000mm from ground or intermediate floor level; contractor is to include for any additional works associated with these constraints; include for all propping required; the contractors attentions is drawn to the Comfloor 60 technical documentation				
A	Soffit of Slabs; Soffit height 2000mm to 4000mm from previous intermediate floor; contractors attention however is drawn to the multi floor level nature of the installation with a maximum height from ground level of 9700mm	m2	45	
B	Extra for Comfloor 60 edge trim detail; include for all fixings, restraint straps etc required; all installed in accordance with manufacturers recommendations	m	31	
REINFORCEMENT Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps Fabric				
C	horizontal; slab	m2	45	

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK (Cont) REINFORCEMENT (Cont) Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps ALL THE FOLLOWING IN SLAB INFILL AT CINEMA ROOM CONCRETE WORK Information AFor kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specification IN SITU CONCRETE Reinforced in-situ concrete; Grade C28/35; vibrated; in accordance with Engineers Concrete Specification; in suspended slab poured over profiled metal deck permanent formwork (metal deck elsewhere measured); slab to be poured at varying heights throughout a multi story building with intermediate floors; generally circa 3000mm high between floors with a total height from top floor to ground level of 9700mm; contractor is to include for any additional works associated with these constraints including any scaffolding, pumping, health and safety measures etc that may be required Bgreater than 150mm thick				
	note			
	m3	2		

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK FORMWORK 60mm thick Comfloor 60 steel permanent formwork system; all as per engineers specifications; include for filler blocks as required; installed as per manufacturers instructions; installed on structural steel sub frame with fixings to manufacturers recommendations at a height of 3000mm from ground or intermediate floor level; contractor is to include for any additional works associated with these constraints; include for all propping required; the contractors attentions is drawn to the Comfloor 60 technical documentation				
A	Soffit of Slabs; Soffit height 2000mm to 4000mm from previous intermediate floor; contractors attention however is drawn to the multi floor level nature of the installation with a maximum height from ground level of 9700mm	m2	7	
B	Extra for Comfloor 60 edge trim detail; include for all fixings, restraint straps etc required; all installed in accordance with manufacturers recommendations	m	12	
REINFORCEMENT Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps Fabric				
C	horizontal; slab	m2	7	

(23) Suspended Floors (Cont) (Cont) CONCRETE WORK (Cont) REINFORCEMENT (Cont) Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps ALL THE FOLLOWING IN TIMBER SECTION OF COMMS FLOOR AND AT STAIRWELL STEPS WOODWORK STRUCTURAL AND FIRST FIXINGS Softwood Grade C24 unless otherwise stated, double vacuum treated Carcassing in pitched roof				
A	225mm x 44mm joists	m	28	
B	225mm x 44mm bridging	m	10	
Sundries (Provisional)				
C	Joist hangers; 'BAT' SPH mild steel 30 x 5mm or similar approved; single hanger type 225mm deep, galvanised to B.S. 2989; building into Blockwork to B.S. 5628 Part 1; to suit 44 x 225mm joist; all to Engineer's details	nr	30	
BOARDING AND SECOND FIXINGS 22mm thick Norbord Sterling OSB3 T & G flooring; fixed in accordance with manufacturers recommendations; all as per Engineers Drawings and Specification Boarding and sheeting, floors				
D	fixed to joists (joists e.m.) ; greater than 300mm wide	m2	8	

(23) Suspended Floors (Cont) (Cont) WOODWORK INSULATION Knauf mineral wool insulation as specified by Architect; fixed between joists accordance with manufacturers instructions and recommendations Insulation; fixed between joists in suspended floor Athermal; 150mm thick ALL THE FOLLOWING IN TIMBER CAPPING OF STAIRWELL (PROVISIONAL) WOODWORK STRUCTURAL AND FIRST FIXINGS Softwood Grade C24 unless otherwise stated, double vacuum treated Carcassing in pitched roof B225mm x 44mm joists C225mm x 44mm bridging Sundries (Provisional) DJoist hangers; 'BAT' SPH mild steel 30 x 5mm or similar approved; single hanger type 225mm deep, galvanised to B.S. 2989; building into Blockwork to B.S. 5628 Part 1; to suit 44 x 225mm joist; all to Engineer's details BOARDING AND SECOND FIXINGS 22mm thick Norbord Sterling OSB3 T & G flooring; fixed in accordance with manufacturers recommendations; all as per Engineers Drawings and Specification Boarding and sheeting, floors Efixed to joists (joists e.m.) ; greater than 300mm wide				
	m2	8		
	m	90		
	m	25		
	nr	30		
	m2	30		

(23) Suspended Floors (Cont) (Cont) WOODWORK INSULATION Knauf mineral wool insulation as specified by Architect; fixed between joists accordance with manufacturers instructions and recommendations Insulation; fixed between joists in suspended floor				
A	thermal; 150mm thick	m2	30	
ADDITIONAL ITEMS B The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element				
		item	1	

(23) Suspended Floors (Cont)				
COLLECTION				
Page No. BQ/142				
Page No. BQ/143				
Page No. BQ/144				
Page No. BQ/145				
Page No. BQ/146				
Page No. BQ/147				
Page No. BQ/148				
Page No. BQ/149				
Page No. BQ/150				
Page No. BQ/151				
Page No. BQ/152				
Page No. BQ/153				
Page No. BQ/154				
Page No. BQ/155				
(23) Suspended Floors Carried to Summary				
Carrolls Talbot Street				
BQ/156				

(24) Stairs				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/157				

<u>(24) Stairs (Cont)</u>				
(Cont) NOTES				
Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications		Note		
Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below		Note		
ALL THE FOLLOWING IN CAST STAIRCASES TO GALLERY BUILDING				
<u>CONCRETE WORK</u>				
IN SITU CONCRETE				
<u>Reinforced in situ concrete; Grade C28/35; vibrated; as Engineer's specification</u>				
Staircases				
generally	m3	8		
Landings				
generally	m3	5		
<u>Surface Finishes</u>				
Trowelling				
generally, as described in Engineer's specification	m2	54		

<u>(24) Stairs (Cont)</u>				
<u>(Cont) CONCRETE WORK</u>				
REINFORCEMENT (PROVISIONAL)				
<u>Reinforcement bars; of various diameter; deformed high yield steel to B.S. 4449 or 4461; spacers and chairs as necessary to support reinforcement in position, as specified by Engineer</u>				
Bars; straight and bent				
A	over 25mm diameter	tonne	1.95	
B	dowel bars as required to connect staircase to ground floor slab	item	1	
C	include here for all additional works associated with forming ties, links, bends etc required to form reinforcing structures generally including links with proposed cast landings and internal face of external walls	item	1	
FORMWORK				
<u>Formwork generally; Type C finish, as described in Engineer's specification; See Architects Drawing CIX TD 63.01 for sectional details</u>				
D	Flight from basement to half landing consisting of 9 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at half landings	item	1	
E	Flight from basement half landing to ground floor consisting of 4 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at cast suspended floors	item	1	

(24) Stairs (Cont)				
(Cont) CONCRETE WORK				
(Cont) FORMWORK				
(Cont) Formwork generally; Type C finish, as described in Engineer's specification; See Architects Drawing CIX TD 63.01 for sectional details				
A	Flight from ground floor to half landing consisting of 13 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at half landings	item	1	
B	Flight from ground floor half landing to first floor consisting of 11 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at cast suspended floors	item	1	
C	Flight from first floor to second floor consisting of 6 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with cast suspended floors	item	1	
D	Flight from second floor to half landing consisting of 12 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at half landings	item	1	

<u>(24) Stairs (Cont)</u>				
<u>(Cont) CONCRETE WORK</u>				
<u>(Cont) FORMWORK</u>				
<u>(Cont) Formwork generally; Type C finish, as described in Engineer's specification; See Architects Drawing CIX TD 63.01 for sectional details</u>				
A	Flight from second floor half landing to third floor consisting of 5 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at cast suspended floors	item	1	
	Soffit			
B	height to soffit not exceeding 5.00m; in half landings between suspended floors all levels	m2	25	
SUNDRIES				
<u>Connection to Comfloor Suspended Floors</u>				
C	Include here for all works associated with connecting proposed cast in-situ staircases to comfloor suspended floors; include for any additional reinforcing bars, formwork, edge trims, straps, restraints etc that may be required	Nr	3	
ALL THE FOLLOWING IN CAST STAIRCASE TO REAR OF CINEMA				
<u>CONCRETE WORK</u>				
IN SITU CONCRETE				
<u>Reinforced in situ concrete; Grade C28/35; vibrated; as Engineer's specification</u>				
	Staircases			
D	generally	m3	4	
	Landings			
E	generally	m3	2	

(24) Stairs (Cont) (Cont) CONCRETE WORK (Cont) IN SITU CONCRETE Surface Finishes Trowelling A generally, as described in Engineer's specification REINFORCEMENT (PROVISIONAL) Reinforcement bars; of various diameter; deformed high yield steel to B.S. 4449 or 4461; spacers and chairs as necessary to support reinforcement in position, as specified by Engineer Bars; straight and bent B over 25mm diameter C dowel bars as required to connect staircase to ground floor slab D include here for all additional works associated with forming ties, links, bends etc required to form reinforcing structures generally including links with proposed cast landings and internal face of external walls FORMWORK Formwork generally; Type C finish, as described in Engineer's specification; See Architects Drawing CIX TD 63.01 for sectional details E Flight from ground floor to half landing consisting of 8 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at half landings				
	m2	24		
	tonne	0.9		
	item	1		
	item	1		
	item	1		

<u>(24) Stairs (Cont)</u>				
<u>(Cont) CONCRETE WORK</u>				
<u>(Cont) FORMWORK</u>				
<u>(Cont) Formwork generally; Type C finish, as described in Engineer's specification; See Architects Drawing CIX TD 63.01 for sectional details</u>				
A	Flight from first to second half landing consisting of 9 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at half landings	item	1	
B	Flight from second half landing to first floor consisting of 8 steps; 1200mm wide with 250mm going and 150mm riser; include for forming strings, soffit, steps etc in form work; include for all temporary props required and removal on completion; include for any additional works associated with connections at cast suspended floors	item	1	
Soffit				
C	height to soffit not exceeding 4.00m; in half landings between suspended floors all levels	m2	12	
SUNDRIES				
<u>Connection to Comfloor Suspended Floors</u>				
D	Include here for all works associated with connecting proposed cast in-situ staircases to comfloor suspended floors; include for any additional reinforcing bars, formwork, edge trims, straps, restraints etc that may be required	Nr	1	
ADDITIONAL ITEMS				
E	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	

<u>(24) Stairs (Cont)</u>				
COLLECTION				
Page No. BQ/157				
Page No. BQ/158				
Page No. BQ/159				
Page No. BQ/160				
Page No. BQ/161				
Page No. BQ/162				
Page No. BQ/163				
(24) Stairs Carried to Summary				
Carrolls Talbot Street	BQ/164			

(27) Roof Structure				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/165				

(27) Roof Structure (Cont)				
(Cont) NOTES				
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note		
B	Note: - All structural timber to be in accordance with the specifications for structural timber outlined in the Engineers Specification	Note		
C	Note: - Notching timbers to allow them to be fixed to steel beams is deemed to be included in the rates generally in this element	Note		
D	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below	Note		
ALL THE FOLLOWING IN INTERVENTIONS TO EXISTING GALLERY ROOF (PROVISIONAL)				
DEMOLITIONS				
Stripping Existing Roof Slates				
Carefully remove existing roof slates and associated felt, battens etc and dispose off site; include for carefully protecting existing roof structure being retained and making good as necessary; include for removal of demolished material from site; include for stripping all associated flashings, junctions etc and disposing off site; carefully protecting existing structures adjacent being retained and make good as necessary				
E	Roof slates generally	m2	124	

(27) Roof Structure (Cont) (Cont) DEMOLITIONS (Cont) Stripping Existing Roof Slates (Cont) Carefully remove existing roof slates and associated felt, battens etc and dispose off site; include for carefully protecting existing roof structure being retained and making good as necessary; include for removal of demolished material from site; include for stripping all associated flashings, junctions etc and disposing off site; carefully protecting existing structures adjacent being retained and make good as necessary				
A	Extra for removing and disposing associated ridge tiles	m	12	
B	Extra for carefully working around existing chimney stack	item	1	
Removing Sections of Existing Roof Include for carefully removing sections of rafters (assumed 225mm x 44mm @ 300mm centres) and ridge board between existing retained structural trusses and purlins; include for carefully stripping all roof timbers and disposing off site; include for carefully protecting structural trusses and purlins for the duration and making good as necessary; leave purlins ready to receive new roof structure; see Engineers Drawing T4988-S009				
C	Section of roof between structural trusses 3000mm wide x 5000mm long	Nr	8	
WOODWORK STRUCTURAL AND FIRST FIXINGS Softwood Grade C24 unless otherwise stated, double vacuum treated Carcassing in pitched roof				
D	125 x 75mm wallplate; bolted to concrete U blocks with M12 bolts at 750mm centres and strapped to blockwork using 1000mm long 30mm x 5mm galvanised straps @ 1200mm centres	m	24	

(27) Roof Structure (Cont) (Cont) WOODWORK (Cont) STRUCTURAL AND FIRST FIXINGS (Cont) Softwood Grade C24 unless otherwise stated, double vacuum treated				
A	225 x 44mm rafters	m	300	
B	175 x 44mm ceiling joists	m	234	
C	225mm x 44mm ridge board	m	12	
Sundries (Provisional)				
D	Twist straps; 30mm x 1000mm x 5mm galvanised; all to Engineer's details	nr	20	
ALL THE FOLLOWING IN ROOF OVER REAR STAIRWELL CONCRETE WORK Information				
E	For kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specification	note		
IN SITU CONCRETE Reinforced in-situ concrete; Grade C28/35; vibrated; in accordance with Engineers Concrete Specification; in suspended slab poured over profiled metal deck permanent formwork (metal deck elsewhere measured); slab to be poured at varying heights throughout a multi story building with intermediate floors; generally circa 3000mm high between floors with a total height from top floor to ground level of 9700mm; contractor is to include for any additional works associated with these constraints including any scaffolding, pumping, health and safety measures etc that may be required				
F	greater than 150mm thick	m3	4	

(27) Roof Structure (Cont)				
(Cont) CONCRETE WORK				
FORMWORK				
60mm thick Comfloor 60 steel permanent formwork system; all as per engineers specifications; include for filler blocks as required; installed as per manufacturers instructions; installed on structural steel sub frame with fixings to manufacturers recommendations at a height of 3000mm from ground or intermediate floor level; contractor is to include for any additional works associated with these constraints; include for all propping required; the contractors attentions is drawn to the Comfloor 60 technical documentation				
A	Soffit of Slabs; Soffit height 2000mm to 4000mm from previous intermediate floor; contractors attention however is drawn to the multi floor level nature of the installation with a maximum height from ground level of 9700mm	m2	13	
B	Extra for Comfloor 60 edge trim detail; include for all fixings, restraint straps etc required; all installed in accordance with manufacturers recommendations	m	16	
REINFORCEMENT				
Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps				
Fabric				
C	horizontal; slab	m2	13	

(27) Roof Structure (Cont) (Cont) CONCRETE WORK (Cont) REINFORCEMENT (Cont) Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps ALL THE FOLLOWING IN COMMS ROOM ROOF CONCRETE WORK Information AFor kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specification IN SITU CONCRETE Reinforced in-situ concrete; Grade C28/35; vibrated; in accordance with Engineers Concrete Specification; in suspended slab poured over profiled metal deck permanent formwork (metal deck elsewhere measured); slab to be poured at varying heights throughout a multi story building with intermediate floors; generally circa 3000mm high between floors with a total height from top floor to ground level of 9700mm; contractor is to include for any additional works associated with these constraints including any scaffolding, pumping, health and safety measures etc that may be required Bgreater than 150mm thick				
	note			
	m3	10		

(27) Roof Structure (Cont)				
(Cont) CONCRETE WORK				
FORMWORK				
60mm thick Comfloor 60 steel permanent formwork system; all as per engineers specifications; include for filler blocks as required; installed as per manufacturers instructions; installed on structural steel sub frame with fixings to manufacturers recommendations at a height of 3000mm from ground or intermediate floor level; contractor is to include for any additional works associated with these constraints; include for all propping required; the contractors attentions is drawn to the Comfloor 60 technical documentation				
A	Soffit of Slabs; Soffit height 2000mm to 4000mm from previous intermediate floor; contractors attention however is drawn to the multi floor level nature of the installation with a maximum height from ground level of 9700mm	m2	48	
B	Extra for Comfloor 60 edge trim detail; include for all fixings, restraint straps etc required; all installed in accordance with manufacturers recommendations	m	33	
REINFORCEMENT				
Reinforcement; structural mesh fabric; B.S. 4483, round mild steel; reference A393; no allowance in measurement made for laps				
Fabric				
C	horizontal; slab	m2	48	
ADDITIONAL ITEMS				
D	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	

(27) Roof Structure (Cont) COLLECTION Page No. BQ/165 Page No. BQ/166 Page No. BQ/167 Page No. BQ/168 Page No. BQ/169 Page No. BQ/170 Page No. BQ/171 (27) Roof Structure Carried to Summary				
Carrolls Talbot Street	BQ/172			

<u>(28) Frame</u>				
NOTES				
A	Note:- All steelwork to comply with the National Structural Steelwork specifications (including corrosion protection) as amended by the project specifications	Note		
B	Note:- Fabrication & erection of steel shall conform to BS5950 & National Structural Steelwork specification	Note		
C	Note:- Ordinary nuts and bolts to be grade 8.80, hot dipped, galvanised to BS EN20898 U.N.O.	Note		
D	Note: - All foundation bolts to be in accordance with BS7419	Note		
E	Note: - Minimum plate thickness 10mm	Note		
F	Note: - Grout around foundation bolts and under baseplates to have a minimum characteristic strength @ 28 days of 40N/mm to BS 5328	Note		
G	Note: - All welds to be 8mm fillet welds U.N.O.	Note		
H	Note: - Paint System, Corrosion Protection - paint system shall provide a minimum structure life of 50 years based on Environment category C2 given in BSEN ISO 12944	Note		
J	Note: - Distribution of materials is deemed to be included within all rates below	note		
K	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		

(28) Frame (Cont)				
(Cont) NOTES				
A	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
B	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
C	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
D	Note: - All quantities measured in this element are provisional	Note		
E	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note		

(28) Frame (Cont)				
(Cont) NOTES				
Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below		Note		
STRUCTURAL STEELWORK				
STRUCTURAL STEELWORK in accordance with Architects/Engineers drawings				
Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details				
STRUCTURAL STEELWORK AS ILLUSTRATED ON GROUND FLOOR STRUCTURAL PLAN				
Fabricated members; main frame of building				
Columns				
columns; member profile 25-50kg/m (203 x 203 UC46) - C3	tonne	0.41		
columns; member profile 25-50kg/m (152 x 152 UC37) - C8	tonne	1.11		
columns; member profile 25-50kg/m (152 x 152 UC44) - C9	tonne	0.14		
columns; member profile 50-100kg/m (305 x 305 UC97) - C7	tonne	2.28		
Beams				
beams; member profile 0-25kg/m (178 x 102 UB19) - B8	tonne	1.03		
extra over the above for 200mm x 12mm plate stitch welded to bottom flange as per engineers specifications	m	27		
Carrolls Talbot Street		To Collection €		
BQ/175				

<u>(28) Frame (Cont)</u>				
<u>(Cont) STRUCTURAL STEELWORK</u>				
<u>(Cont) STRUCTURAL STEELWORK in accordance with Architects/Engineers drawings</u>				
<u>(Cont) Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details</u>				
<u>(Cont) Beams</u>				
A	beams; member profile 0-25kg/m (178 x 102 UB19) - B9	tonne	0.53	
B	beams; member profile 25-50kg/m (203 x 203 UC46) - B16	tonne	0.79	
Other				
Channels				
C	PFC; member profile 25-50kg/m (PFC - 260 x 90 32kg/m) - B10	tonne	0.77	
D	PFC; member profile 25-50kg/m (PFC - 260 x 90 30kg/m) - B11	tonne	0.24	
STRUCTURAL STEELWORK AS ILLUSTRATED ON FIRST FLOOR STRUCTURAL PLAN				
Columns				
E	columns; member profile 25-50kg/m (203 x 203 UC46) - C3	tonne	1.47	
F	columns; member profile 25-50kg/m (152 x 152 UC37) - C8	tonne	0.93	
G	columns; member profile 25-50kg/m (152 x 152 UC44) - C9	tonne	0.11	
Beams				
H	beams; member profile 0-25kg/m (178 x 102 UB19) - B8	tonne	0.58	
J	extra over the above for 200mm x 12mm plate stitch welded to bottom flange as per engineers specifications	m	16	

(28) Frame (Cont)				
(Cont) STRUCTURAL STEELWORK				
(Cont) STRUCTURAL STEELWORK in accordance with Architects/Engineers drawings				
(Cont) Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details				
(Cont) Beams				
A	beams; member profile 0-25kg/m (178 x 102 UB19) - B9	tonne	0.54	
B	beams; member profile 25-50kg/m (203 x 203 UC46) - B16	tonne	0.35	
C	beams; member profile 50-100kg/m (203 x 203 UC60) - B12	tonne	2.4	
D	beams; member profile 50-100kg/m (305 x 165 UB60) - B14	tonne	0.51	
E	beams; member profile 100-150kg/m (533 X 210 UB122) - B1	tonne	2.76	
F	beams; member profile 100-150kg/m (305 X 305 UC118) - B5	tonne	3.4	
Other				
Channels				
G	PFC; member profile 25-50kg/m (PFC - 260 x 90 32kg/m) - B10	tonne	1.08	
H	PFC; member profile 25-50kg/m (PFC - 260 x 90 30kg/m) - B11	tonne	0.24	
STRUCTURAL STEELWORK AS ILLUSTRATED ON SECOND FLOOR STRUCTURAL PLAN				
Columns				
J	columns; member profile 25-50kg/m (152 x 152 UC37) - C8	tonne	0.93	
K	columns; member profile 25-50kg/m (152 x 152 UC44) - C9	tonne	0.11	

<u>(28) Frame (Cont)</u>				
<u>(Cont) STRUCTURAL STEELWORK</u>				
<u>(Cont) STRUCTURAL STEELWORK in accordance with Architects/Engineers drawings</u>				
<u>(Cont) Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details</u>				
Beams				
A	beams; member profile 0-25kg/m (178 x 102 UB19) - B8	tonne	1.16	
B	extra over the above for 200mm x 12mm plate stitch welded to bottom flange as per engineers specifications	m	31	
C	beams; member profile 0-25kg/m (178 x 102 UB19) - B9	tonne	0.43	
D	beams; member profile 50-100kg/m (203 x 203 UC60) - B12	tonne	0.46	
Other				
Channels				
E	PFC; member profile 25-50kg/m (PFC - 260 x 90 32kg/m) - B10	tonne	1.05	
F	PFC; member profile 25-50kg/m (PFC - 260 x 90 30kg/m) - B11	tonne	0.23	
STRUCTURAL STEELWORK AS ILLUSTRATED ON THIRD FLOOR STRUCTURAL PLAN				
Columns				
G	columns; member profile 25-50kg/m (152 x 152 UC37) - C8	tonne	0.93	
H	columns; member profile 25-50kg/m (152 x 152 UC44) - C9	tonne	0.11	

<u>(28) Frame (Cont)</u>				
<u>(Cont) STRUCTURAL STEELWORK</u>				
<u>(Cont) STRUCTURAL STEELWORK in accordance with Architects/Engineers drawings</u>				
<u>(Cont) Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details</u>				
Beams				
A	beams; member profile 0-25kg/m (178 x 102 UB19) - B8	tonne	1.16	
B	extra over the above for 200mm x 12mm plate stitch welded to bottom flange as per engineers specifications	m	31	
C	beams; member profile 0-25kg/m (178 x 102 UB19) - B9	tonne	0.43	
D	beams; member profile 50-100kg/m (203 x 203 UC60) - B12	tonne	0.46	
Other				
Channels				
E	PFC; member profile 25-50kg/m (PFC - 260 x 90 32kg/m) - B10	tonne	0.72	
F	PFC; member profile 25-50kg/m (PFC - 260 x 90 30kg/m) - B11	tonne	0.23	
STRUCTURAL STEELWORK COMMS ROOM ROOF				
Columns				
G	columns; member profile 25-50kg/m (203 x 203 UC46) - C3	tonne	1.27	
Beams				
H	beams; member profile 50-100kg/m (203 x 203 UC60) - B12	tonne	1.84	
J	beams; member profile 100-150kg/m (203 X 203 UB102) - B2	tonne	3.02	

	(28) Frame (Cont) (Cont) STRUCTURAL STEELWORK (Cont) STRUCTURAL STEELWORK in accordance with Architects/Engineers drawings (Cont) Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details (Cont) Beams				
A	beams; member profile 100-150kg/m (305 X 305 UC118) - B5	tonne	0.52		
	STRUCTURAL STEELWORK COMMS ROOM ROOF (ADDITIONAL TRIMMING STEEL IN FINAL DRAWING REVISION)				
	Beams				
B	beams; member profile 0-25kg/m (178 x 102 UB19) - B9	tonne	0.39		
	Sundries (Provisional)				
	Holding down assemblies				
C	450mm x 450mm x 25mm S275 baseplate; 8 FW full profile; include 4 Nr M20 grade 8.80 holding down bolts x 400mm long (galvanised) and associated washers; include tapered sleeves; include 150 x 150 x 12mm RSA anchor plates with 50mm void former; all as shown on Engineers Drawing 2000/B01 P2	nr	49		
	Grouting; non shrink grout 40N/mm2; as per Engineers specification				
D	holding down bolts; 100 diameter x 400 long	nr	196		
E	baseplates; 25mm thick; under 450 x 450 plate	nr	49		
	Sundries				
F	drilling/forming holes in reinforced concrete to facilitate insertion of bolts	nr	196		

(28) Frame (Cont) (Cont) STRUCTURAL STEELWORK (Cont) STRUCTURAL STEELWORK in accordance with Architects/Engineers drawings (Cont) Sundries (Provisional)				
A	drilling holes in steel plate to facilitate insertion of bolts	nr	196	
Erection of all the foregoing steelwork				
B	generally	item	1	
STEELWORK (Provisional)				
Structural steelwork to receive treatment to achieve a minimum of one hour fire resistance by coating with Hamron XPW intumescent coatings Protective coatings				
C	general surfaces	tonne	39.13	
SURFACE TREATMENTS				
Preparing; Blast clean all steelwork to preparation grade SA 2.5 to ISO 8501-01. Remove all traces of loose rust, grit, etc by compressed air hose, inspect for laminations and remove by careful grinding leaving a smooth surface; Pre fabrication apply one coat of zinc rich blast primer to a minimum DFT of 25 microns; Post fabrication apply one coat of zinc rich site holding primer to a minimum DFT of 75 microns (125 microns where intumescent coat is to be applied); apply one coat of intumescent paint, where required, for fire resistance periods as specified on drawings; touch up damaged surfaces and fixings after erection; cosmetic painting to Architects Specification; all work to comply with BS5493 and paint manufacturer's instructions ; all in accordance with the Structural Engineers drawings and specification Protective coatings				
D	general surfaces	tonne	39.13	

(28) Frame (Cont) (Cont) STRUCTURAL STEELWORK STITCHING CORNER CRACKING Stitching Cracks A Stitch existing cracks at rear stairwell using TWD13 corner angles 250mm long; 150mm x 150mm x 12mm fixed with 8nr M16 resin anchors BEARING PADS (Provisional) Reinforced concrete bearing pads Reinforced concrete bearing pads including 35N20 concrete, 0.10 tonne of rebar per bearing pad, formwork; all as per Engineers Drawings Ground Floor Blockwork Walls B 450mm long x 450mm wide x 215mm deep SUNDRY INSTALLATION COSTS Installation of Steelwork in Confined Spaces C The contractor should particularly note the access constraints associated with the installation of steelwork generally and should include here for any additional costs associated; including but not limited to craneage, hoisting, additional labour, additional health and safety requirements, additional plant, installation of a craneage base and removal on completion; hoarding and traffic management associated with craneage, any licenses required etc; it should be noted that it is proposed to remove sections of the existing roof to facilitate installation of steelwork from above should that be the chosen strategy and the costs for the removal and reinstatement of the roof is included elsewhere in this document Nr 10 nr 12 item 1				
Carrolls Talbot Street BQ/182				To Collection €

(28) Frame (Cont) (Cont) Installation of Steelwork in Confined Spaces PROVISIONAL SUM Provisional Sum A Include a provisional sum of €10,000.00 for additional unforeseen works in this element ADDITIONAL ITEMS B The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element								
					1			
					item			
Carrolls Talbot Street					To Collection €			
BQ/183								

(28) Frame (Cont)				
COLLECTION				
Page No. BQ/173				
Page No. BQ/174				
Page No. BQ/175				
Page No. BQ/176				
Page No. BQ/177				
Page No. BQ/178				
Page No. BQ/179				
Page No. BQ/180				
Page No. BQ/181				
Page No. BQ/182				
Page No. BQ/183				
(28) Frame Carried to Summary				
Carrolls Talbot Street	BQ/184			

<u>(31) External Walls Completions</u>				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/185				

(31) External Walls Completions (Cont) (Cont) NOTES				
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note		
B	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below	Note		
DEMOLITIONS				
Removing Existing Windows Take out and remove from site existing windows and external doors and associated frames, ironmongery etc; include for making good existing openings and leaving ready for installation of new windows and doors				
Windows				
C	1855mm wide x 1755mm high (GL3-04)	Nr	1	
D	1300mm wide x 1500mm high (GL3-03 and GL3-05)	Nr	2	
E	1305mm wide x 1200mm high (GL3-01 and GL3-02)	Nr	2	
F	1000mm x 1000mm (at switch room opening)	Nr	1	
Doors				
G	Double doors to rear elevation 3000mm wide x 2600mm high (7)	Nr	1	
H	Double doors to rear elevation 1800mm wide x 2400mm high (5)	Nr	1	
Carrolls Talbot Street			To Collection €	
BQ/186				

<u>(31) External Walls Completions (Cont)</u>				
<u>(Cont) Removing Existing Windows</u>				
<u>(Cont) Take out and remove from site existing windows and external doors and associated frames, ironmongery etc; include for making good existing openings and leaving ready for installation of new windows and doors</u>				
<u>(Cont) Doors</u>				
A	Single door to rear elevation 900mm wide x 2100mm high (11)	Nr	1	
<u>Removal of Signage</u>				
<u>Take down existing signage externally and remove from site; make good external facade under following removal; the contractor is deemed to have visited the site to ascertain the precise scope associated with removal of the signage outlined below</u>				
B	Signage over existing retained rollershutter at gallery building (2)	item	1	
C	Signage adjacent steel doors at gallery building (2)	item	1	
D	Signage over removed double doors at rear elevation (5)	item	1	
<u>Removal of Rollershutters</u>				
<u>Take out existing rollershutters and associated housings, equipment, runners, frames, boxing etc and remove from site; carefully protect existing structures adjacent being retained and make good as necessary</u>				
E	3000mm x 3000mm (6)	item	1	

(31) External Walls Completions (Cont) (Cont) Removal of Rollershutters ALTERATIONS TO EXTERNAL OPENINGS Forming New Openings Break out openings through existing 450mm thick brickwork external facade of existing gallery building; include for sawcutting as required and removal of demolished material from site; include for inserting lintels as required and associated bearing pads; leave openings ready to receive new door and frame set A1200mm wide x 2200mm high (single door to rear elevation of gallery building) B1800mm wide x 2200mm high (double door to proposed switch room) Infilling Openings Infill openings in 215mm thick solid concrete blockwork; include for ancon wall starter systems at junctions with existing structure; include for tothing to existing structure as required; include for plastered external finish and making good existing external facade as required on completion C1000mm x 2100mm Infill opening in 450mm thick solid brickwork; include for tothing new brickwork into existing as required D2000mm x 2200mm				
	item	1		
	item	1		
	item	1		
	item	1		
Carrolls Talbot Street BQ/188 To Collection €				

(31) External Walls Completions (Cont) (Cont) Infilling Openings NEW WINDOWS AND DOORS Works to Existing Windows Inspect existing windows and make good as necessary; include for replacement of any sections of frames or sashes showing damage or rot; include for replacing any damaged panes of glass to match existing; include for fixing panes closed and leaving ready to receive manifestations; all as per Architects Elevations and Window Schedules				
A	1300mm wide x 2435mm high (GL2-01)	Nr	1	
B	1420mm wide x 2435mm high (GL2-02 & 04)	Nr	2	
C	2030mm wide x 2420mm high (GL2-03)	Nr	1	
D	1600mm wide x 2200mm high (GL0-05)	Nr	1	
E	1900mm wide x 1400mm high (Provisional)	Nr	11	
Aluminium External Doors Aluminium external door and frame including associated ironmongery; doors to achieve a 60 minute fire rating; include for installation to manufacturers recommendations; include for factory painted finish internally and externally in RAL colour as selected by the Architect; all as per Architect External Window and Door Schedule Double Doors				
F	2540mm wide x 2200mm high (DL0-05)	Nr	1	
G	1740mm wide x 2100mm high (DL0-07)	Nr	1	
H	1975mm wide x 2360mm high (DL0-08)	Nr	1	
J	1775mm wide x 2450mm high (DL0-09)	Nr	1	
K	1740mm wide x 2100mm high (DL0-11)	Nr	1	
Carrolls Talbot Street			To Collection €	
BQ/189				

<u>(31) External Walls Completions (Cont)</u>				
<u>(Cont) Aluminium External Doors</u>				
<u>(Cont) Aluminium external door and frame including associated ironmongery; doors to achieve a 60 minute fire rating; include for installation to manufacturers recommendations; include for factory painted finish internally and externally in RAL colour as selected by the Architect; all as per Architect External Window and Door Schedule</u>				
Single Doors				
A	1200mm wide x 2200mm high (DL0-6)	Nr	1	
B	1275mm wide x 2450mm high (DL0-10)	Nr	1	
<u>Hardwood External Doors</u>				
<u>Hardwood door and frame 57mm thick; double sheeted in style to replicate existing door being removed; include for factory painted finish internally and externally in RAL colour as selected by the Architect; all as per Architect External Window and Door Schedule</u>				
C	1430mm wide x 3820mm high fixed panel non openable (DL1-01)	Nr	1	
<u>Hardwood External Windows</u>				
<u>Replacement hardwood sliding sash external windows to match existing; weight and chord operation not required; glazing to be clear double glazing with 24mm toughened glass; sashes to have full panes of glass with spacer bars between glazing and timber bars fixed externally to glazing face; include for factory painting in RAL colour as selected by the Architect Internally and externally; include for all ironmongery required in antique brass</u>				
D	1855mm wide x 1755mm high (GL3-04)	Nr	1	
E	1300mm wide x 1500mm high (GL3-03 and GL3-05)	Nr	2	
F	1305mm wide x 1200mm high (GL3-01 and GL3-02)	Nr	2	
Carrolls Talbot Street			To Collection €	
BQ/190				

Carrolls To Collection €
Talbot Street BQ/191

Carrolls
Talbot Street

<u>(34) Stairs Completions</u>				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/193				

<u>(34) Stairs Completions (Cont)</u>				
(Cont) NOTES				
Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications				
	Note			
Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below				
	Note			
BALUSTRADES AND HANDRAILS				
<u>METALWORK: Non-structural</u>				
<u>Mild steel balustrade consisting 50mm x 50mm mild steel posts at spacings as illustrated on Architects sectional drawings; fixed to proposed cast staircases with 150mm x 50mm x 10mm fixing brackets and 2Nr M12 Resin Anchor Bolts; 50mm x 10mm flat top and bottom bars with 20mm diameter vertical bars @ 100mm centres; handrail to be 50mm x 50mm mild steel on 50 x 10mm flat steel rail fixed to top bar with 15mm vertical upstand bars; finish to bar rail and clamp to match that of handrail; all as per Architects Drawing CIX TD 63.01; all installed as per manufacturers recommendations</u>				
Horizontal; 1100mm high	m	31		
Raking; 1100mm high	m	56		
Carrolls Talbot Street			<i>To Collection €</i>	
BQ/194				

(34) Stairs Completions (Cont) (Cont) METALWORK: Non-structural 50mm x 50mm mild steel handrail to match balustrade; fixed to blockwork with and including mild steel brackets at 900mm centres; all as per Architects Drawing GPW TD 63.01; all installed as per manufacturers recommendations				
A	50mm diameter; horizontal	m	50	
B	50mm diameter; raking	m	10	
PAINTING AND DECORATING PAINTING Cleaning; removing any rust; preparing; one coat primer; two undercoat flat oil paint and one finish coat gloss oil paint; to mild steel; colour as selected by the Architect; all in accordance with Architect's specification Balustrades				
C	1100mm high balustrades; including handrail	m2	209	
Cleaning; removing any rust; preparing; one coat primer; two undercoat flat oil paint and one finish coat gloss oil paint; to mild steel; colour as selected by the Architect; all in accordance with Architect's specification Handrails				
D	50mm diameter wall mounted handrail	m	60	
ADDITIONAL ITEMS				
E	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	

(34) Stairs Completions (Cont) COLLECTION Page No. BQ/193 Page No. BQ/194 Page No. BQ/195 (34) Stairs Completions Carried to Summary				
Carrolls Talbot Street				

<u>(37) Roofs Completions</u>				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		

(37) Roofs Completions (Cont)				
(Cont) NOTES				
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note		
B	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below INSULATION TO PITCHED ROOF AT GALLERY BUILDING Roof Insulation - Pitched Roof <u>Kingspan Kooltherm K7 rigid PIR insulation installed between support timbers; all installed in accordance with manufacturers recommendations and Architects Specification</u>	Note		
C	150mm thick friction fitted between timbers AOV <u>Rooflight</u> <u>Rooflights complete including proprietary flashings and upstands; to prepared openings in timber roof structure; fixed strictly in accordance with the manufacturer's instructions</u> Rooflights	m2	124	

(37) Roofs Completions (Cont) (Cont) Rooflight (Cont) Rooflights complete including proprietary flashings and upstands; to prepared openings in timber roof structure; fixed strictly in accordance with the manufacturer's instructions				
A	"Velux Ref. GGUSD0L140 smoke ventilation system; triple glazed; overall size; 1140mm x 1180mm clear internal opening; including all ironmongery, proprietary flashings and insulated upstands; include for forming light shaft from roof to ceiling including trimmers, 62.50mm thick insulated plasterboard, 3mm skim finish and painting with one sealer coat and two finishing coats of emulsion paint; all as shown on Architects Drawing	Nr	3	
ALTERATIONS TO EXISTING ROOFS TO FACILITATE INSTALLATION OF AOV'S Forming Opening in Existing Roof Include for forming opening through existing slated roof to facilitate installation of above AOV rooflights; include for stripping existing slates as required; include for trimming around rooflight in 175mm x 44mm trimmers as per engineers specifications and any alterations to existing roof structure required to facilitate same; include for making good slates around installed rooflight on completion and weathering as required; all as per Architects Drawings and Specifications				
B	1140mm x 1180mm	Nr	3	
ADDITIONAL ITEMS				
C	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item		

(37) Roofs Completions (Cont) COLLECTION Page No. BQ/197 Page No. BQ/198 Page No. BQ/199 (37) Roofs Completions Carried to Summary				
Carrolls Talbot Street				BQ/200

(41) External Wall Finishes				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/201				

(41) External Wall Finishes (Cont)				
(Cont) NOTES				
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note		
B	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below	Note		
CLEANING OF EXISTING BRICKWORK				
<u>Cleaning of Existing Brickwork</u>				
<u>Include here for the cleaning of all existing external brickwork finishes; brick to be soft washed and cleaned in a manner so as to protect all existing pointing; include for removing any vegetation or existing paint or graffiti prior to cleaning; include for all access requirements to facilitate the works; the contractor is deemed to have visited site to ascertain any access constraints and to understand the condition of the existing facade prior to pricing this item</u>				
C	External facade	m2	362	

(41) External Wall Finishes (Cont) (Cont) Cleaning of Existing Brickwork RENDERED FINISHES New Plastered Finishes (Provisional) Sand and cement rendered finish; consisting of bonding coat; twop undercoats and one finishing coat of sand and cement render; undercoats to consist of 1:5-6 air entrained sulfate resisting cement:sand; first underocat to be 8-12mm thick, second undercoat to be 6-10mm thick; finish coat to consist of 1:4-5 Masonry sand:cement 5-8mm thick; plain smooth finish; all applied in accordance with manufacturers instructions and Architects Specification				
A	over 300mm girth	m2	145	
PAINTING; EXTERNALLY Painting Paint to plaster base; Dulux weathershiled Acrylic paint; one coat approved sealer; three coats Dulux external quality acrylic paint or equivalent; colour to be selected by the Architect; all in accordance with the Architects specification				
B	Walls over 300mm girth	m2	388	
C	extra over the above for painting existing Quoins, parapet details, protruding bay windows etc in an alternate contrasting colour as selected by the Architect	item	1	
PROVISIONAL SUM Repairs Include a Provisional Sum of €10,000.00 for any repairs that may be required to the existing external facade				
D			1	

<u>(41) External Wall Finishes (Cont)</u> <u>(Cont) Repairs</u> ADDITIONAL ITEMS The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item			
Carrolls Talbot Street				To Collection €
BQ/204				

(41) External Wall Finishes (Cont) COLLECTION Page No. BQ/201 Page No. BQ/202 Page No. BQ/203 Page No. BQ/204 (41) External Wall Finishes Carried to Summary				
Carrolls Talbot Street				

(47) Roof Finishes				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
Carrolls Talbot Street			To Collection €	
BQ/206				

<u>(47) Roof Finishes (Cont)</u>				
(Cont) NOTES				
Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications		Note		
Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below		Note		
ROOF FINISHES TO NEW FLAT ROOFS				
<u>Sebum Roof</u>				
<u>BauderGREEN XF301 Sedum Blanket; on and including 40mm BauderGREEN AL 40 drainage Trim; on and including 20mm BauderGREEN SDF drainage and protection mat; on and including Bauder underlying Total Roof System including Bauder Cap Sheet (Bauder K5K) on Underlayer (BauderTEC KSA DUO); on and including 160mm Insulation (Bauder PIR FA-G16 Tapered Insulation); on and including Air and Vapour Control Layer (BauderTEC KSD FBS); fixed strictly in accordance with manufacturers recommendations; all as shown on Architects Drawings & specification</u>				
Comms Roof	m2	47		
Rear Stairwell Roof	m2	11		
Upstands Generally 450mm girth	m	15		
Upstands Generally 700mm girth	m	32		

(47) Roof Finishes (Cont)				
Outlets				
Harmer two way aluminium outlet; 110mm diameter spigot; include for Harmer threaded ADP adaptor; include for DPC across top of spigot; include for Harmer aluminium downspouts push fit connect to standard 110mm plain ended pipe using an "O" ring seal and mechanically fixed into masonry; include for all associated flashings; installed in accordance with manufacturers instructions and recommendations				
Roof outlets				
A	all as per Architects Drawing & Specification	nr	5	
SLATING TO EXISTING ROOFS (Provisional)				
Blue Bangor Roof Slates				
Roadstone SL8 interlocking roof tiles installed with fixings as required to manufacturers recommendations; 50 x 50mm softwood battens pressure impregnated with an approved preservative, at 400mm centres; 50 x 36mm counterbattens ; Solitex plus low resistance underlay roof membrane , vertical laps 150mm minimum over rafter and 200mm horizontally under batten, dressed into gutters, hips and valleys; all in accordance with Architect's specification				
B	Gallery Building Roof	m2	124	
C	Extra for matching ridge tiles fitted on dry ridge system	m	12	
D	Extra for roof slate vent; klober inline or equal approved; installed in accordance with manufacturers recommendations and Architects Specification	Nr	10	
Carrolls Talbot Street			To Collection €	
BQ/208				

(47) Roof Finishes (Cont) Lead Finishes to Box Gutters Between Roofs Forming new Code 8 lead box gutters; lengths of lead not to exceed 3000mm; include for lapping as required; include for 225mm high lead upstand at parapet wall chased into stonework and sealed with a lead mastic; include for lapping lead under first row of tiles minimum 250mm; include for all lead mastic, copper nails, pins, fixings, clips etc required; include for any welding required; include for any lengths of cover flashing required; include for geotextile membrane under; all installed in accordance with Architects Details and lead association guidelines A600mm girth (including slate lap) at junction with stairwell roof Lead Apron Flashings to Chimneys Straight Flashings Code 6 lead apron flashings and cover flashing to chimney stacks; include for front and rear cap 600-800mm girth underflashings carried up face and rear of chimney stacks 200mm and carried down roof tiles as required; include for cover flashing 400mm girth saw cut into chimney stack and sealed with lead mastic; include for all screws, nails, fixings and welding required, include for carefully protecting the existing facade and making good as necessary on completion; all as per Architects specification; Installed in accordance with lead association guidelines B800mm girth				
	m	3		
	m	4		
Carrolls Talbot Street				To Collection €
BQ/209				

<u>(47) Roof Finishes (Cont)</u>		
<u>(Cont) Lead Apron Flashings to Chimneys</u>		
<u>Soaker Flashings</u> Include for soaker flashings installed to a raking profile over individual roof slates where roofs meet external walls; include for underflashings and coverflashings as required; include for saw cutting soaker flashings into chimney stack and sealing with lead mastic as required; include for all screws, nails, fixings and welding required, include for carefully protecting the existing facade and making good as necessary on completion; all as per Architects specification; Installed in accordance with lead association guidelines	m	4
<u>Leadwork at Lift Shaft Protrusion</u>		
<u>Straight Flashings</u> Code 6 lead apron flashings and cover flashing to chimney stacks; include for front and rear cap 600-800mm girth underflashings carried up face and rear of lift shaft 200mm and carried down roof tiles as required; include for cover flashing 400mm girth saw cut into lift shaft and sealed with lead mastic; include for all screws, nails, fixings and welding required, include for carefully protecting the existing facade and making good as necessary on completion; all as per Architects specification; Installed in accordance with lead association guidelines		
800mm girth	m	4

<u>(47) Roof Finishes (Cont)</u>				
<u>(Cont) Leadwork at Lift Shaft Protrusion</u>				
<u>Soaker Flashings</u>				
Include for soaker flashings installed to a raking profile over individual roof slates where roofs meet external walls; include for underflashings and coverflashings as required; include for saw cutting soaker flashings into lift shaft and sealing with lead mastic as required; include for all screws, nails, fixings and welding required, include for carefully protecting the existing facade and making good as necessary on completion; all as per Architects specification; Installed in accordance with lead association guidelines		m	4	
<u>Lead work to Top of Chimney Stacks</u>				
<u>Leadwork</u>				
Form bespoke lead tray in minimum Code 6 lead with preformed spigot upstands to suit retained chimney pots; lead to be fitted over existing concrete; include for all laps required; include for any welding or lead mastic required; include for all fixings, nails, screws, clips, straps etc that may be required; include for drip detail to perimeter of covering; include for geotextile membrane under; See Architects Drawing SFD-DFT-PP-50.20				
2300mm x 800mm	Nr	1		
<u>Reinstating Chimney Pots</u>				
Remove existing chimney pots and send off site for a complete restoration; restored chimney pots to be installed over new lead tray in their original locations; include for refurbishing chimney grates as required; include for any replacement pieces or fixings required; include for replacement chimney guards to match existing		Nr	2	
Extra over the above for replacing chimney pots to match existing due to breakage or unusability	Nr	2		
Carrolls Talbot Street			To Collection €	
BQ/211				

(47) Roof Finishes (Cont)				
Forming Gutter Catch Pits				
Include here for forming openings through existing parapet walls as required at proposed locations of new downpipes; include for any coring required; include for dressing openings formed in lead in accordance with lead association guidelines; include for pre formed outlet; include for carefully protecting existing structures adjacent being retained; ; include for geotextile membrane under;				
A	200mm diameter	Nr	1	
RAINWATER GOODS (Provisional)				
Rainwater Goods				
Removal of Existing				
B	Carefully remove existing cast iron gutters and downpipes to existing stone buildings only and dispose off site; leave structure ready to receive new rainwater goods	item	1	
New Gutters				
Rainwater pipework; cast iron rainwater system; Heritage Range; square; standard brackets; polyester powder coating to RAL colour to be specified by Architect; approved jointing in the running length; all in accordance with the manufacturer's recommendations				
C	100mm diameter gutters	m	24	
New Downpipes				
Rainwater pipework; Aluminium; square; standard brackets; polyester powder coating to RAL colour to be specified by Architect; approved jointing in the running length; all in accordance with the manufacturer's recommendations				
D	102mm diameter circular downpipes	m	35	
Extra over the foregoing pipework for the following additional fittings from the Heritage Range				
Carrolls Talbot Street			To Collection €	
BQ/212				

(47) Roof Finishes (Cont) (Cont) New Downpipes				
A	Swan neck	nr	5	
B	outlets	nr	5	
C	shoes	nr	5	
D	connection to drain upstand	nr	5	
ADDITIONAL ITEMS				
E	The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element	item	1	
Carrolls Talbot Street BQ/213				
To Collection €				

<u>(47) Roof Finishes (Cont)</u>					
COLLECTION					
Page No. BQ/206					
Page No. BQ/207					
Page No. BQ/208					
Page No. BQ/209					
Page No. BQ/210					
Page No. BQ/211					
Page No. BQ/212					
Page No. BQ/213					
(47) Roof Finishes Carried to Summary					
Carrolls Talbot Street					
BQ/214					

<u>(50) Site Services Piped and Ducted</u>				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
E	Note: - All quantities measured in this element are provisional	Note		
Carrolls Talbot Street			To Collection €	
BQ/215				

[illegible]

(50) Site Services Piped and Ducted (Cont) WORKS TO EXTERNAL YARD AND ROADWAY TO FACILITATE Path and Roadway at Front Entrance Foul Connection Excavate through existing concrete paved pathway at front entrance, across existing stone kerbing and through section of coloured tarmacadam at loading bay to facilitate connection to existing foul manhole; include for lifting concrete paviours, removing section of kerbing and saw cutting through existing coloured tarmac to a total width of 600mm wide and to a depth of 1500mm; include for all traffic or pedestrian management required; include for all road opening licenses required; include for any hoarding or barriers required to segment proposed works from the public; include for bed and surround of pipework in C28/35 concrete 600mm x 400mm and backfilling remaining trench in clause 808 hardcore well compacted; include for making good paving, reinstating kerbing and making good tarmacadam to loading bay; all as per Engineers Drawings and Specifications A extra over the quantities measured below for pipework outside the boundary of the site with additional scope as described above				
	m	6		
Carrolls Talbot Street BQ/217				To Collection €

(50) Site Services Piped and Ducted (Cont) (Cont) WORKS TO EXTERNAL YARD AND ROADWAY TO FACILITATE Roadway at Rear Entrance Foul Connection Excavate through existing concrete roadway to facilitate connection to existing foul manhole; include for saw cutting and removing sections of concrete roadway to a total width of 600mm wide and to a depth of 1500mm; include for all traffic or pedestrian management required; include for all road opening licenses required; include for any hoarding or barriers required to segment proposed works from the public; include for bed and surround of pipework in C28/35 concrete 600mm x 400mm and backfilling remaining trench in clause 808 hardcore well compacted; include for making good concrete surfaces on completion; all as per Engineers Drawings and Specifications				
A	extra over the quantities measured below for pipework outside the boundary of the site with additional scope as described above	m	12	
Carrolls Talbot Street BQ/218				To Collection €

(50) Site Services Piped and Ducted (Cont) (Cont) WORKS TO EXTERNAL YARD AND ROADWAY TO FACILITATE Roadway at Rear Entrance Surface Water Connection Excavate through existing concrete roadway to facilitate connection to existing foul manhole; include for saw cutting and removing sections of concrete roadway to a total width of 600mm wide and to a depth of 1500mm; include for all traffic or pedestrian management required; include for all road opening licenses required; include for any hoarding or barriers required to segment proposed works from the public; include for bed and surround of pipework in C28/35 concrete 600mm x 400mm and backfilling remaining trench in clause 808 hardcore well compacted; include for making good concrete surfaces on completion; all as per Engineers Drawings and Specifications				
A	extra over the quantities measured below for pipework outside the boundary of the site with additional scope as described above	m	20	
DRAINAGE; SURFACE WATER BELOW GROUND Excavating trenches to receive pipes; not exceeding 250mm nominal size; grading bottoms; disposing of surplus excavated material on site Excavating trenches; starting from reduced ground level; backfill trenches with hardcore backfill to clause 809 in accordance with Engineer's specification; compacted in 150mm maximum layers				
B	average depth 1000 to 1500mm	m	37	
Sundries Disposal of water				
C	keeping all excavations measured above free of surface water	item	1	
Carrolls Talbot Street BQ/219			To Collection €	

(50) Site Services Piped and Ducted (Cont) (Cont) DRAINAGE; SURFACE WATER (Cont) BELOW GROUND In-situ concrete; grade 35N20, as per Engineers specification Beds and surrounds (provisional) A680mm wide x 600mm deep; in accordance with Engineer's Drawings and specification Drains; unplasticised PVC pipes and fittings complying with I.S. 424 or B.S. 5481; wavinsewer or equal and approved integral socketed pipe, laid in accordance with manufacturer's instructions 225mm pipework; in trenches Blaid in position uPVC Accessories Armstrong junctions; "Wavin" or equivalent; heavy duty cast iron cover and frame; 500 x 500mm, set and surrounded in 200mm thick concrete grade 35N20; jointing to UPVC pipework including excavation, disposal, flexible sealant etc; all as shown on Engineers Drawing C1250mm average depth to invert; one 150mm outlet; one 150mm inlet (provisional) Back inlet gulley trap; 150 x 150mm top; 150 x 150mm lockable cover grating; set and surround gulley in concrete grade C25N20 Done 150mm inlet; one 150mm outlet (provisional)				
	m	37		
	m	37		
	Nr	3		
	Nr	4		

(50) Site Services Piped and Ducted (Cont)

(Cont) DRAINAGE; SURFACE WATER

(Cont) BELOW GROUND

Precast manhole complete; all in accordance with Engineers drawings and specification; precast T & G concrete rings to B.S.5911-3 and BSEN1917, reinforcement to B.S. 4449 and B.S. 4482; 150mm thick grade Gen 3 concrete surround walls; 600mm thick insitu concrete base (Grade Gen 3 concrete, sulphate resisting) on 75mm thick blinding; 200mm thick precast reinforced concrete roof slab; forming 750 x 600mm access ope in slab; include for bituminous seal between precast rings and between roof slab and precast ring; Grano concrete benching finished with 2:1 sand cement mortar; single or double oblique curved channels as per specification; polypropylene encapsulated galvanised steel step irons; D400 heavy duty ductile iron manhole cover and frame bedded in class M1 cement mortar bed with four courses of class B engineering brickwork laid in English bond; lifting keys; forming all necessary pipe entry openings in walls; bed and surround to rocker pipe connections; forming all necessary pipe entry openings in walls; bed and surround to pipe connections; include for all excavation and earthwork support, excavation below water table level, formwork, working space, disposal of excavated material on site

Manhole

A 1200mm diameter; internal dimensions; depth to invert 1000 to 1500mm

Nr

1

B extra for forming manhole over existing live surface water sewer

Nr

1

<u>(50) Site Services Piped and Ducted (Cont)</u>				
<u>(Cont) DRAINAGE; SURFACE WATER</u>				
<u>(Cont) BELOW GROUND</u>				
<u>Galvanised steel items in compliance with NRA specification clause 1911</u>				
Manhole cover and frame to standard Local Authority pattern in compliance with I.S./E.N. 124; 1994; bedding frame in cement mortar (1:3) on and including minimum of four courses of Engineering brickwork to I.S. 91				
A	600 x 600mm; B.S. 497; grade A; heavy duty (provisional)	Nr	1	
<u>Hard uPVC channels; bedding in cement mortar (1:3)</u>				
Half section; 1200mm long				
B	300mm straight	Nr	1	
<u>Sundries</u>				
Benching to manholes; concrete grade C20/20 slope to be 1:10 / 1:30 range; include for one layer of A393 mesh reinforcement				
C	750 x 1200 x 300mm	Nr	1	
<u>Drainage Channel</u>				
"Aco" or equal and approved proprietary drainage channels and gratings system; B125 or equal approved; load class as specified by manufacturers literature; include concrete foundation and surround 500mm wide x 460mm high; include for all necessary formwork, reinforcement & concrete				
D	laying in position	m	6	
Extra on ACO drain for				
E	ends (provisional)	Nr	3	
F	Sump	Nr	3	
G	connection to 100mm diameter uPVC pipe (provisional)	Nr	3	

<u>(50) Site Services Piped and Ducted (Cont)</u>				
<u>(Cont) DRAINAGE; SURFACE WATER</u>				
<u>(Cont) BELOW GROUND</u>				
<u>Testing and Comissioning</u>				
Surface water drains and associated manholes and accessories				
A	generally	item	1	
<u>DRAINAGE; FOUL WATER</u>				
<u>BELOW GROUND</u>				
<u>Excavating trenches to receive pipes; not exceeding 250mm nominal size; grading bottoms; disposing of surplus excavated material on site</u>				
Excavating trenches; starting from reduced ground level; backfill trenches with hardcore backfill to clause 809 in accordance with Engineer's specification; compacted in 150mm maximum layers				
B	average depth 1000 to 1500mm	m	54	
<u>Sundries</u>				
Disposal of water				
C	keeping all excavations measured above free of surface water	item	1	
<u>In-situ concrete; grade 35N20, as per Engineers specification</u>				
Beds and surrounds (provisional)				
D	490mm wide x 450mm deep; in accordance with Engineer's Drawings and specification	m	54	
<u>Drains; unplasticised PVC pipes and fittings complying with I.S. 424 or B.S. 5481; wavinsewer or equal and approved integral socketed pipe, laid in accordance with manufacturer's instructions</u>				
150mm pipework; in trenches				
E	laid in position	m	54	

<u>(50) Site Services Piped and Ducted (Cont)</u>				
<u>(Cont) DRAINAGE; FOUL WATER</u>				
<u>(Cont) BELOW GROUND</u>				
<u>(Cont) Drains; unplasticised PVC pipes and fittings complying with I.S. 424 or B.S. 5481; wavinsewer or equal and approved integral socketed pipe, laid in accordance with manufacturer's instructions</u>				
A	extra over the above for pop ups through ground floor slab; locations to be set out and agreed with Architect and Engineer prior to installation	Nr	8	
<u>uPVC Accessories</u>				
Armstrong junctions; "Wavin" or equivalent; heavy duty cast iron cover and frame; 500 x 500mm, set and surrounded in 200mm thick concrete grade 35N20; jointing to UPVC pipework including excavation, disposal, flexible sealant etc; all as shown on Engineers Drawing				
B	1250mm average depth to invert; one 150mm outlet; one 150mm inlet (provisional)	Nr	2	
C	extra over the above for double seal cover and frame for internal application	Nr	1	

(50) Site Services Piped and Ducted (Cont) (Cont) DRAINAGE; FOUL WATER (Cont) BELOW GROUND Precast manhole complete; all in accordance with Engineers drawings and specification; precast T & G concrete rings to B.S.5911-3 and BSEN1917, reinforcement to B.S. 4449 and B.S. 4482; 150mm thick grade Gen 3 concrete surround walls; 600mm thick insitu concrete base (Grade Gen 3 concrete, sulphate resisting) on 75mm thick blinding; 200mm thick precast reinforced concrete roof slab; forming 750 x 600mm access ope in slab; include for bituminous seal between precast rings and between roof slab and precast ring; Grano concrete benching finished with 2:1 sand cement mortar; single or double oblique curved channels as per specification; polypropylene encapsulated galvanised steel step irons; D400 heavy duty ductile iron manhole cover and frame bedded in class M1 cement mortar bed with four courses of class B engineering brickwork laid in English bond; lifting keys; forming all necessary pipe entry openings in walls; bed and surround to rocker pipe connections; forming all necessary pipe entry openings in walls; bed and surround to pipe connections; include for all excavation and earthwork support, excavation below water table level, formwork, working space, disposal of excavated material on site Manhole A 1200mm diameter; internal dimensions; depth to invert 1000 to 1500mm B extra over the above for forming manhole over existing live foul water sewer				
		Nr	3	
		item	1	
Carrolls Talbot Street				To Collection €
BQ/225				

<u>(50) Site Services Piped and Ducted (Cont)</u>				
<u>(Cont) DRAINAGE; FOUL WATER</u>				
<u>(Cont) BELOW GROUND</u>				
<u>Galvanised steel items in compliance with NRA specification clause 1911</u>				
Manhole cover and frame to standard Local Authority pattern in compliance with I.S./E.N. 124; 1994; bedding frame in cement mortar (1:3) on and including minimum of four courses of Engineering brickwork to I.S. 91				
A	600 x 600mm; B.S. 497; grade A; heavy duty (provisional)	Nr	2	
Double seal internal manhole cover and frame				
B	600 x 600mm; B.S. 497; grade A; heavy duty (provisional)	Nr	1	
<u>Hard uPVC channels; bedding in cement mortar (1:3)</u>				
Half section; 1200mm long				
C	225mm straight	Nr	3	
<u>Sundries</u>				
Benching to manholes; concrete grade C20/20 slope to be 1:10 / 1:30 range; include for one layer of A393 mesh reinforcement				
D	750 x 1200 x 300mm	Nr	3	
<u>Testing and Comissioning</u>				
Foul water drains and associated manholes and accessories				
E	generally	item	1	

(50) Site Services Piped and Ducted (Cont) FORMING SUMP PUMP IN GALLERY BASEMENT Forming Sump Pump Chamber Include for all works associated with forming sump pump chamber at basement level in Gallery building; include for excavation and removal of excavated material from site including working space; include for forming concrete base and walls including associated formwork and reinforcing bars at 150kg/m3; include for lining walls and base in Prefpufe GCP 160R waterproofing liner; include for discharge pipework to surface water manhole approximately 6m away with a 2000mm rising main; all a as per Engineers Drawings and Specifications A1200mm x 1200mm x 900mm deepitem1 WORKS TO EXISTING LIGHTWELL Removing Lightwell Remove existing lightwell and any associated substrate and dispose off site; leave void ready to receive new concreted finish B2600mm x 1800mmitem1 CONCRETE WORK Information CFor kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specificationnote DPower floated concrete floor slabs are to be finished to a sufficient level to obviate the necessity for the spreading of levelling compound for all floor coverings. The main contractor should consult with all floor subcontractors/ suppliers to obtain their requirements for finish of concrete surfaces prior to the concrete being poured.note				
Carrolls Talbot Street BQ/227				To Collection €

(50) Site Services Piped and Ducted (Cont) (Cont) WORKS TO EXISTING LIGHTWELL (Cont) CONCRETE WORK Reinforced in-situ concrete; Grade C28/35, as per Engineer's Specification; vibrated; include for polyfibres at 9kg per m3 Beds; poured on or against earth or unblinded hardcore A250mm deep m32				
SUNDRIES Adcor 500s Waterbar to perimeter of infill BInstalled in accordance with manufacturers recommendations m9				
REINFORCEMENT Reinforcement bars; of various diameter; deformed high yield steel to B.S. 4449 or 4461; spacers and chairs as necessary to support reinforcement in position, as specified by Engineer Bars; straight and bent CGreater than 12mm diameter (B16) tonne0.26				
FORMWORK (Note: - formwork has been measured to foundations but may not be required; no payment will be made if formwork is not used) Formwork; generally as described in Engineer's specification Edges of beds Dnot exceeding 250mm high m9				

(50) Site Services Piped and Ducted (Cont) (Cont) WORKS TO EXISTING LIGHTWELL TANKING Preprufe 160 R waterproof membraine or similar approved waterproofing system to outside face of lift pit walls and underside of slab; all installed in accordance with Engineers Specification and manufacturers recommendations				
A	Under Basement Ground Bearing Slab	m2	5	
ADDITIONAL ITEMS The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element				
B		item		
Carrolls Talbot Street BQ/229				To Collection €

(50) Site Services Piped and Ducted (Cont)				
COLLECTION				
Page No. BQ/215				
Page No. BQ/216				
Page No. BQ/217				
Page No. BQ/218				
Page No. BQ/219				
Page No. BQ/220				
Page No. BQ/221				
Page No. BQ/222				
Page No. BQ/223				
Page No. BQ/224				
Page No. BQ/225				
Page No. BQ/226				
Page No. BQ/227				
Page No. BQ/228				
Page No. BQ/229				
(50) Site Services Piped and Ducted Carried to Summary				
Carrolls Talbot Street				
BQ/230				

<u>(- -) Works Associated With Lifts</u>				
NOTES				
A	Note: - Distribution of materials is deemed to be included within all rates below	note		
B	Note: - The contractor is deemed to have visited the site to ascertain the kind, quality and quantity of all materials described below; no claim for additional costs will be entertained for lack of understanding of any of the items described below which could be reasonably ascertained from a site visit	note		
C	Note: - The contractor should note the fact that these works take place adjacent existing live business environments and adjacent busy pedestrian streets and is deemed to have included within his rates for any additional items required to facilitate working alongside same; including but not limited to additional hoardings, screens etc, additional health and safety measures, phasing of intrusive elements of work, additional management on site or interaction with Carrolls or its neighbours management teams	note		
D	Note: - The contractor should note that some works take place at high and is deemed to have included for any access plant, temporary scaffolding etc required to complete those works as described	Note		
E	Note: - The contractors attention is drawn to the temporary works details as prepared by the Engineer and is deemed to have included for these works within their tendered rates; quantum of temporary works is not provided within this schedule of works and the cost and quantity of any temporary works required should be included in the tendered rates for the works themselves requiring those temporary works	Note		
F	Note: - All quantities measured in this element are provisional	Note		

(- -) Works Associated With Lifts (Cont) (Cont) NOTES				
A	Note: - The contractor when pricing all items below is deemed to have reviewed the Architects Drawings and Specification and included for any additional description not contained below contained within them within their tendered rates; no claim for additional cost will be considered for any item which could reasonably be ascertained from the reading of the Bill of Quantities, Architects Drawings, Engineers Drawings and Specifications	Note		
B	Note: - The Contractors Attention is drawn to Engineers Drawing T4988-S001 containing general project specification notes; the contractor is deemed to have reviewed these notes and to have included for any associated works or costs within the rates below	Note		
EXCAVATION AND EARTHWORK EXCAVATION Excavation Foundation trenches; starting from reduced ground level C less than or equal to 2.00m deep (Lift Pit) m3 24 Extra over all excavation items for the following: - D excavating below ground water level m3 5 E breaking up existing rock m3 5				
	All soft spots shall be immediately brought to the attention of the Engineer. The amount to be excavated shall be agreed with the Engineer and the Contractor shall furnish to the Engineer at the end of each week an accurate sketch of each softspot excavated during the week. Each sketch shall show the average plan dimensions, commencement level and depth, and shall be approved and signed by the Engineer			

<u>(- -) Works Associated With Lifts (Cont)</u>				
<u>(Cont) EXCAVATION AND EARTHWORK</u>				
<u>(Cont) EXCAVATION</u>				
<u>(Cont) Excavation</u>				
A	Excavate soft spots (irrespective of depth); dispose of excavated material off site; backfill and consolidate with 15N 20 leanmix concrete to the Engineers specification	m3	5	
<u>Disposal</u>				
Surface water				
B	keeping the surface of the site free of surface water	item	1	
Ground water				
C	keeping the excavations free of ground water	item	1	
Contaminated ground water				
D	keeping the excavations free of contaminated ground water	item	1	
Excavated material				
E	off site	m3	24	
FILLING				
<u>Hardcore; SR21, in accordance with Engineer's specification; depositing and compacting in layers 150mm maximum thickness</u>				
Filling; depositing in layers; compacting				
F	to make up levels; average thickness less than or equal to 250mm	m3	10	
<u>Surface treatments</u>				
Blinding filling				
G	levelling with sand of fine gravel; 50mm thick, T3; compacting	m2	12	

<u>(- -) Works Associated With Lifts (Cont)</u>				
<u>CONCRETE WORK</u>				
<u>Information</u>				
A	For kind and quality of materials; performance or mix details; tests; limitations on method of pouring, placing, compacting and curing refer to Engineer's Specification	note		
B	Power floated concrete floor slabs are to be finished to a sufficient level to obviate the necessity for the spreading of levelling compound for all floor coverings. The main contractor should consult with all floor subcontractors/ suppliers to obtain their requirements for finish of concrete surfaces prior to the concrete being poured.	note		
IN SITU CONCRETE				
<u>Grade C20/25 X0 lean mix concrete, as per Engineers specification</u>				
Blinding				
C	poured against earth or unblinded hardcore	m3	1	
Beds; poured on or against earth or unblinded hardcore				
D	less than or equal to 150mm deep (Lift pit)	m3	6	
<u>Reinforced in-situ concrete; Grade C30/37 XC3, as per Engineer's Specification; vibrated</u>				
Upstand Walls				
E	Upstand Walls	m3	5	
F	RC roof slab	m3	3	
Carrolls Talbot Street			To Collection €	
BQ/234				

<u>(- -) Works Associated With Lifts (Cont)</u>		
<u>(Cont) CONCRETE WORK</u>		
REINFORCEMENT		
<u>Reinforcement bars; of various diameter; deformed high yield steel to B.S. 4449 or 4461; spacers and chairs as necessary to support reinforcement in position, as specified by Engineer</u>		
Bars; straight and bent		
less than or equal to 16mm diameter (B16)	tonne	1.08
less than or equal to 16mm diameter (B12)	tonne	0.39
FORMWORK		
<u>Formwork; generally as described in Engineer's specification</u>		
Sides of Edge Beams and Upstand Walls		
1200mm high at upstand walls	m2	46
To underside of RC roof slab	m2	12
Include her for any additional formwork or supporting timbers required to facilitate pouring of the items described above; in particular to the underside of the proposed edge beam at the external glazing profile	item	
<u>Working Space</u>		
Working space; one side only; including excavation, disposal of excavated material from site and backfilling with hardcore to Engineer's specification		
to facilitate construction of lift pit walls	m2	23

(- -) Works Associated With Lifts (Cont)		
<u>(Cont) CONCRETE WORK</u>		
TANKING		
<u>Preprufe 160 R waterproof membrane or similar approved waterproofing system to outside face of lift pit walls and underside of slab; all installed in accordance with Engineers Specification and manufacturers recommendations</u>		
Surrounding lift pit	m2	35
Extra for Adcor 500 waterbars as required to both lift pits	item	1
<u>STRUCTURAL STEELWORK</u>		
STRUCTURAL STEELWORK in accordance with Architects/Engineers drawings		
<u>Fabricated weldable (steel grade S275 typical) all as per Engineer's specification; hot rolled sections; weldable fabrication and bolted on site; the details of all welded connections should comply with B.S. 5135; all welds as per Engineer's specification; Refer to Engineers specification and drawings for details</u>		
LIFTING BEAMS		
Fabricated members; main frame of building		
Beams		
beams; member profile 25-50kg/m (203 x 203 UC46) - B16	tonne	0.37
ADDITIONAL ITEMS		
The contractor should include here for any additional costs that they believe may arise because of the particular nature and location of these works, over and above any items included above in this Element		
	item	

Carrolls
Talbot Street